

SECTION 900
PROJECT NO. SAP-56(9)M
PERRY COUNTY

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	1.400	TON
COMMERCIAL FERTILIZER (13-13-13)	0.700	TON
AMMONIUM NITRATE	0.070	TON
SEEDING	0.700	AC
VEGETATIVE MATERIALS FOR MULCH	1.400	TON
EXCELSIOR BLANKET	1,156.000	SY
EROSION MAT	260.000	SY
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	1,172.000	LF
WATTLES, 20"	200.000	LF
REMOVE AND RESET RIPRAP	300.000	CY
LOOSE RIPRAP, 200 LB.	40.000	TON
LOOSE RIPRAP, 300 LB.	595.000	TON
GEOTEXTILE UNDER RIPRAP	2,313.000	SY
TYPE V, NON-WOVEN (AOS < 0.43)		
SEDIMENT CONTROL STONE	278.000	TON

BRIDGE ITEMS:

CLASS B STRUCTURAL CONCRETE, MINOR STRUCTURES	48.000	CY
REINFORCING	2,140.000	LB
MISCELLANEOUS BRIDGE APPURTENANCES	LUMP SUM	LS
MAINTENANCE PAINTING OF EXPOSED METAL COMPONENTS	LUMP SUM	LS