



SITE DEMOLITION PLAN



BE ADVISED THE CURRENT CONDITION OF THE
STRUCTURE HAS COLLAPSED. CONTRACTORS
SHOULD FAMILIARIZE THEMSELVES WITH THE
SITE AND ALL CONDITIONS PRIOR TO BIDDING:

- NOTES:
1. DEMOLITION PROJECT AREA SHALL BE ENTIRE AREA ENCLOSED BY TEMPORARY CONSTRUCTION FENCING.
 2. CONTRACTOR SHALL ASSURE ADEQUATE CLEARANCE BENEATH OVERHEAD WIRES FOR ANY AND ALL POSSIBLE VEHICLES EXPECTED TO ENTER THE SITE.
 3. MAINTAIN SAFE OPERATION OF EXISTING PEDESTRIAN WALKS OUTSIDE TEMPORARY CONSTRUCTION FENCING AT ALL TIMES.
 4. SITE SHALL REMAIN CLEAN, ORDERLY, AND FREE OF ERRANT DEBRIS AT ALL TIMES. SWEEP PAVEMENTS AND WET DEMOLITION DEBRIS AS IS NECESSARY TO INHIBIT SPREAD OF DIRT AND DUST.
 5. ALL FILL AREAS MUST BE FLUSH WITH EXISTING ADJACENT SURFACES FOLLOWING COMPACTION ACTIVITIES. ALL REMAINING SURFACES SHALL SLOPED TO POSITIVE DRAIN.
 6. CONTRACTOR SHALL PROVIDE ALL REQUIRED CLOSE-OUT FORMS, CERTIFICATIONS AND DOCUMENTATION OF DEBRIS DISPOSAL AS PART OF PROJECT CLOSE OUT.
 7. CONTRACTOR SHALL REMOVE AND HAUL AWAY ALL DEMOLITION AND SITE DEBRIS FORM THE SITE. NO DISPOSAL OF MATERIAL IS ALLOWED ONSITE. NO BURNING IS ALLOWED ONSITE.
 8. CONTRACTOR SHALL CLASSIFY DEBRIS AS REQUIRED FOR REMOVAL. RECYCLABLES, METALS, INERT MATERIALS, CONTAMINANTS. ALL DEBRIS DESIGNATED FOR REMOVAL SHOULD BE CLEARLY IDENTIFIED. MATERIAL STOCKPILES SHALL NOT BE ALLOWED TO CROSS CONTAMINANT. OR BE ALTERED DURING THE PROJECT.
 9. CONTRACTOR SHALL COORDINATE ALL ELECTRIC/CABLE/PHONE/ETC. SERVICE DISCONNECTS WITH UTILITY COMPANIES.
 10. CUT, REMOVE, AND CAP EXISTING SANITARY PIPE AS IS NEEDED FOR BUILDING DEMOLITION ONLY.
 11. CONTRACTOR SHALL COORDINATE GAS SHUT OFF AND METER REMOVAL WITH UTILITY COMPANY. EXISTING GAS LINES SHALL BE CAPPED IMMEDIATELY AFTER GAS VALVE NEAR STREET. REMOVE AS IS NECESSARY FOR BUILDING DEMOLITION.
 12. REMOVE EXISTING DRAINAGE BASINS, STORM INLET STRUCTURES AND ASSOCIATED DRAINAGE PIPE AS IS NEEDED FOR BUILDING DEMOLITION AND SITE CLEARING. CONTRACTOR SHALL INSTALL + MAINTAIN ALL NEEDED EROSION CONTROL MEASURES FOR THE DURATION OF THE PROJECT.

PROJECT:

BUILDING DEMOLITION PROJECT

HAWKINS GYMNASIUM

LOCATION: 526 Forrest Street, Hattiesburg MS 39401

CiViL**Tech, Inc.**

Engineers & Project Managers

P.O. Box 12852, Jackson, MS 39236-2852

Phone: (601) 713-1713

Fax: (601) 713-1703

DESIGN: EM	APPV'D: EM	SHEET NO. 1 OF 1
DRAWN:	DATE: JUNE-2021	
CHECKED: TL	JOB NO: 21-P002	
SCALE: NTS		