

FORREST COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Forrest County, Mississippi at the Forrest County Courthouse, Hattiesburg, Mississippi, until 10:00 A.M. on the 2nd day of March, 2023 and shortly thereafter publicly opened for the construction of 0.112 miles of BRIDGE REPLACEMENT on ROCKHILL-BROOKLYN ROAD, being known as Project No. FC21-263B in Forrest County, Mississippi.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

DESCRIPTION	QUANT.	UNIT
ROADWAY ITEMS		
Mobilization	Lump Sum	Lump Sum
Clearing And Grubbing	Lump Sum	Lump Sum
Removal of Bridge @ Sta. 374+74	1.0	Unit
Removal of Existing Bridge Abutment	1.0	Unit
Removal of Asphalt Pavement, (All Depths)	487.0	Sq. Yd.
Borrow Excavation (FME)(Contractor Furnished)(Class 9)	782.0	Cu. Yd.
Granular Material (LVM) (Class 6, Group "C")	630.0	Cu. Yd.
Hot Mix Asphalt, ST, 9.5 mm Mixture	125.0	Ton
Hot Mix Asphalt, ST, 19.0 mm Mixture	188.0	Ton
Guard Rail, W-Beam	200.0	Lin. Ft.
Guard Rail, Bridge End Section, Type I Thrie-Beam	4.0	Each
Guard Rail, Terminal End Section	4.0	Each
Roadway Construction Surveying	Lump Sum	Lump Sum
Maintenance of Traffic	Lump Sum	Lump Sum
Additional Construction Signs	0.0	Sq. Ft.
4" Wide Thermoplastic Edge Stripe (Continuous White) (60 mils)	0.225	Mile
4" Wide Thermoplastic Traffic Stripe (Skip Yellow) (90 mils)	593.0	Lin. Ft.
4" Wide Thermoplastic Traffic Stripe (Continuous Yellow) (90 mils)	593.0	Lin. Ft.
Two-Way Yellow Reflective Raised Markers	16.0	Each
Reflectorized Traffic Object Marker (Encapsulated Lens) (Type 3)	4.0	Each

SECTION 900
PROJECT NO. FC21-263B
FORREST COUNTY

EROSION CONTROL ITEMS

Agricultural Limestone	1.88	Ton
Commercial Fertilizer (13-13-13)	0.94	Ton
Seeding	0.94	Acre
Vegetative Materials for Mulch	2.82	Ton
Temporary Silt Fence	1,500.0	Lin. Ft.
Wattles, 20"	600.0	Lin. Ft.

BRIDGE ITEMS

Test Pile	2.0	Each
Conventional Static Pile Load Test	0.0	Each
14" Prestressed Concrete Piling	1,710.0	Lin. Ft.
Class "A" Bridge Concrete	186.11	Cu. Yd.
40 Ft. Prestressed Concrete Beam	397.50	Lin. Ft.
80 Ft. Prestressed Concrete Beam	398.75	Lin. Ft.
Reinforcement	32,575	Lbs.
Concrete Railing	320.00	Lin. Ft.
Loose Riprap (Size 300 Lb.)	195.0	Tons
Geotextile Under Riprap, Type V, AOS 0.21 - 0.43	423.0	Sq. Yd.

SECTION 900
PROJECT NO. FC21-263B
FORREST COUNTY

NOTICE TO CONTRACTORS:

CONTRACT TIME: 130 Working Days

BASIS OF AWARD

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Purchasing Clerk of Forrest County at 641 Main St., Hattiesburg, MS, and the County Engineer's office at 301 Second Ave. Hattiesburg, MS. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be downloaded from Central Bidding at www.centralbidding.com. Electronic bids may be submitted at www.centralbidding.com, but may be submitted in hard copy at the Office of the Purchasing Clerk. For any questions relating to the electronic bidding process, please call Central Bidding at 225-810-4814.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

David Hogan, President

Advertise:

January 26, 2023 & February 2, 2023