

## SECTION 900

### NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Quitman County Mississippi at the Quitman County Courthouse, Marks, Mississippi, until 10:00 AM on the 8th day of December, 2023 and shortly thereafter publicly opened for the construction of 0.114 miles of Bridge & Approaches on the Roosevelt Road being known as Project No. ERBR-60(01) in Quitman County Mississippi.

### **PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS**

<u>ROADWAY ITEMS:</u>	QUANTITY	UNIT
MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
UNCLASSIFIED EXCAVATION (FM)	500.000	CY
BORROW EXCAVATION (FM)	2,400.000	CY
GRANULAR MATERIAL (FM), (CLASS 4, GROUP B)	800.000	CY
GUARD RAIL, W/BEAM	75.000	LF
GUARD RAIL, BRIDGE END SECTION, TYPE I	4.000	EA
GUARD RAIL, TERMINAL END SECTION	4.000	EA
RIGHT-OF-WAY MARKERS (TYPE I)	4.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA
 <u>EROSION CONTROL ITEMS:</u>		
AGRICULTURAL LIMESTONE	1.980	TON
COMMERCIAL FERTILIZER (13-13-13)	0.990	TON
SEEDING	0.990	AC
VEGETATIVE MATERIALS FOR MULCH	2.970	TON
TEMPORARY SILT FENCE (TYPE I) (AOS 0.15 - 0.84)	400.000	LF
WATTLES, 20"	100.000	LF
 <u>BRIDGE ITEMS:</u>		
TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
18" PRESTRESSED CONCRETE PILING	690.000	LF
24" PRE-FORMED PILE HOLES	200.000	LF
BOX BRIDGE CONCRETE, CLASS A	45.780	CY
REINFORCEMENT	8,024.000	LB
31' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR, NO SKEW	18.000	EA
31' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR, NO SKEW	6.000	EA
PRECAST CONCRETE BARRIER RAIL	186.000	LF
LOOSE RIPRAP, 300 LB.	300.000	TON
GEOTEXTILE FABRIC UNDER RIPRAP, TYPE V, (NON-WOVEN)AOS <0.43	600.000	SY

CONTRACT TIME: 120.00 WORKING DAYS

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The Board of Supervisors hereby notifies all bidders that it will affirmatively ensure that in any contract entered into pursuant to this advertisement; minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Quitman County, J. WAYNE MORRISON, the County Engineer's office, 213 South Main St, Yazoo City, MS. The cost is \$100 for plans and proposals non-refundable. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

Certified check or bid bond for five percent (5%) of the total bid, made payable to Quitman County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Manuel Killebrew, President  
Quitman County Board of Supervisors