



OFFICE OF STATE AID ROAD CONSTRUCTION
AND
COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Bidders shall submit their bids either in a sealed envelope or electronically. Electronic bids will be received at www.copiahcountybids.org and shall include a copy of their Certificate of Responsibility as an attachment to the electronic bid. Sealed bids and electronic bids will be received by the Board of Supervisors of Copiah County in Hazlehurst, Mississippi, at the Copiah County Courthouse located at 100 Caldwell Drive, Hazlehurst, MS 39083 until 10:00 A.M., February 9, 2024, and shortly thereafter publicly opened for the construction of 0.174 miles of Bridge and Approaches on Martinsville Road and in Copiah County, also known as Local System Bridge Project No. LSBP-15(19).

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS

<u>ROADWAY ITEMS:</u>	QUANTITY	UNIT
MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF BRIDGE AT STA. 13+96.00	1.000	UN
REMOVAL OF ASPHALT (ALL DEPTHS)	1,891.000	SY
REMOVAL OF PIPE (ALL SIZES)	96.000	LF
UNCLASSIFIED EXCAVATION (FM)	2,522.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	322.000	CY
GRANULAR MATERIAL (LVM), (CLASS 4, GROUP B)	604.000	CY
HOT MIX ASPHALT, ST 9.5MM	208.000	TON
HOT MIX ASPHALT, ST 19MM	426.000	TON
18" REINFORCED CONCRETE PIPE, CLASS 3	96.000	LF
RIGHT-OF-WAY MARKERS (TYPE II)	24.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 MILS)	0.348	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (SKIP YELLOW) (90 MILS)	0.174	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 MILS)	640.000	LF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA
THERMOPLASTIC DETAIL STRIPE (4" EQUIVALENT LENGTH)(WHITE)(90 MILS)	140.000	LF
THERMOPLASTIC LEGEND (WHITE)(90 MILS)	162.000	LF

<u>EROSION CONTROL ITEMS:</u>		
AGRICULTURAL LIMESTONE	3.000	TON
COMMERCIAL FERTILIZER (13-13-13)	1.000	TON
AMMONIUM NITRATE	0.200	TON
SEEDING	1.500	AC
VEGETATIVE MATERIALS FOR MULCH	4.500	TON
SOLID SODDING	200.000	SY
TEMPORARY SILT FENCE (TYPE I) (AOS 0.15-0.84)	1,840.000	LF

WATTLES, 20"	500.000	LF
LOOSE RIPRAP, (300 LB)	485.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, NON-WOVEN, AOS 0.21-0.43	895.000	SY

BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14" PRESTRESSED CONCRETE PILING	1,040.000	LF
18" PRE-FORMED PILE HOLES	520.000	LF
31' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	24.000	EA
40' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	6.000	EA
31' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	8.000	EA
40' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	2.000	EA
PRECAST CONCRETE BARRIER RAIL	328.000	LF
31' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE,	2.000	EA
31.33' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE,	2.000	EA
31' PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE,	2.000	EA
9.25' PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP, 300 LB.	347.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, NON-WOVEN, AOS <0.43	642.000	SY

PROJECT NO.
Copiah

LSBP-15(19)
COUNTY

NOTICE TO CONTRACTORS:

CONTRACT TIME: 90 Working Days

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The Board of Supervisors hereby notifies all bidders that it will affirmatively ensure that in any contract entered into pursuant to this advertisement; minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

BASIS OF AWARD: The award, if made, will be to the lowest qualified bidder on the basis of the quantities listed in the proposal. If requested by the Owner/Engineer, the bidder shall submit five project of similar scope and size for review and evaluation. The Copiah County Board of Supervisors reserves the right to reject any and all bids and to waive any informalities or irregularities in the bids received.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Copiah County, the LSBP Engineer's office, and the Office of the State Aid Engineer, 412 E. Woodrow Wilson Avenue, Jackson, Mississippi. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction. Paper and electronic copies of the plans and proposals may be ordered at www.copiahcountybids.org for \$100.00.

Certified check or bid bond for five percent (5%) of the total bid, made payable to Copiah County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Publish Dates:

1/10/2024

1/17/2024

JUDSON JACKSON, PRESIDENT
Copiah County Board of Supervisors