

**OFFICE OF STATE AID ROAD CONSTRUCTION
BOARD OF SUPERVISORS OF WAYNE COUNTY**

**SECTION 900
NOTICE TO CONTRACTORS**

Sealed bids will be received by the Board of Supervisors of Wayne County in Waynesboro, Mississippi until **9:00 A.M., on Thursday, April 18, 2024**, and shortly thereafter publicly opened for the construction of 0.170 MI of Bridge & Approaches on Springhill Church Road in District Four, Wayne County, Mississippi, also known as Local System Bridge Project No. LSBP-77(22).

Principal Items of Work are Approximately as Follows:

Roadway Items

Mobilization	Lump Sum	L.S.
Clearing and Grubbing	Lump Sum	L.S.
Removal of Bridge @ Station 14 + 00	1.0	Unit
Unclassified Excavation (F.M.)	1,265.00	Cu. Yd.
Borrow Excavation (F.M.E.) (Contractor Furnished) (Class 9)	3,699.00	Cu. Yd.
Crushed Stone, Size 825	866.00	Ton
18" Reinforced Concrete Pipe, Class III	64.00	Lin. Ft.
Roadway Construction Surveying	Lump Sum	L.S.
Right-of-Way Markers (Type II)	16.00	Each
Maintenance of Traffic	Lump Sum	L.S.
Additional Construction Signs	0.00	Sq. Ft.
Reflectorized Traffic Object Marker (Encapsulated Lens) (Type 3)	4.00	Each
Geotextile Under at Bridge End Treatments, Type V, (AOS <0.43)	109.00	Sq. Yd.

Erosion Control Items

Agricultural Limestone	4.00	Ton
Commercial Fertilizer (13:13:13)	2.00	Ton
Seeding	2.00	Acre
Vegetative Materials for Mulch	4.00	Ton
Solid Sodding	227.00	Sq. Yd.
Portland Cement Concrete Paved Ditch	38.40	Cu. Yd.
Temporary Silt Fence (Type II) (AOS – 0.15-0.84)	1,842.00	Lin. Ft.
Wattles, 20"	400.00	Lin. Ft.

Bridge Items

Test Pile	2.00	Each
Conventional Static Pile Load Test	0.00	Each
14" Prestressed Concrete Piling	870.00	Lin. Ft.
18" Pre-Formed Pile Holes	200.00	Lin. Ft.
40' Precast Concrete Slab Unit, 3.5' Interior	24.00	Each
40' Precast Concrete Slab Unit, 3.5' Exterior	8.00	Each
Precast Concrete Barrier Rail	320.00	Lin. Ft.
31.17' Precast Concrete Cap, Intermediate Unit, Concrete Pile	3.00	Each
31.17' Precast Concrete Cap, End Unit, Concrete Pile	2.00	Each
9.17' Precast Concrete Wing	4.00	Each
Loose Riprap (300 lb.)	252.00	Ton
Geotextile Under Riprap Non-Woven, Type V, (AOS - <0.43)	509.00	Sq. Yd.

BASIS OF AWARD: The award, if made, will be made to the lowest qualified bidder on the basis of the published quantities.

Total Contract Time as Advertised: 80 Working Days

The Board of Supervisors hereby notifies all bidders that it will affirmatively ensure that, in any contract entered into pursuant to this advertisement, minority business enterprises will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color or national origin in consideration for an award.

The Plans, Specifications, and Contract documents are on file and can be viewed at the Office of State Aid Road Construction, 412 Woodrow Wilson Avenue, Jackson, MS 39216 and obtained online via the website of the County Engineer, Lawrence R. Clark, P.E. at www.clarkengineersprojects.com. By use of the website the plan holders shall have the option of obtaining hard copy of the Plans and Specifications and/or shall have the opportunity to submit an official bid online.

All hard copy proposals shall be directed to the attention of The Wayne County Board of Supervisors with the outside of the envelope marked "Project No. LSBP-77(22) Bid Proposal for Bridge Replacement Project". Contractor shall indicate certificate of responsibility number on the outside of the envelope. Online bids shall be accepted and opened as instructed on the website and in the Contract Documents.

Certified Check or Bid Bond for five percent (5%) of total bid payable to Wayne County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letter qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid, and such proposals will not be considered in making the award.

R. Keith Clay, President
Wayne County Board of Supervisors
State of Mississippi

Published Dates: March 14, 2024 & March 21, 2024