

BID SCHEDULE

Project # GS#531-001
 Project Title BROADWATER MARINA RESTORATION
 Location BILOXI, MISSISSIPPI

Item No.	Description	Unit	Estimated Quantity
	<u>BASE BID – RESTORE FUDNING:</u>		
01030-A	SPECIAL MDOT SURETY BOND FOR HDD WORK	LS	1
01505-A	MOBILIZATION (BASE BID)	LS	1
02050-A	REMOVAL OF EXISTING TREES & SHRUBS	LS	1
02050-C	REMOVAL OF EXISTING CONCRETE PAVEMENT	SY	9,560
02050-D	REMOVAL OF EXISTING DRAINAGE CULVERT	LF	446
02050-E	REMOVAL OF SOIL FROM PAVEMENT TO REMAIN	LS	1
02050-J	REMOVE SECTION OF EXISTING SEAWALL FOR HDD	EA	1
02050-K	REMOVAL OF EXISTING DRAIN INLETS	EA	8
02221-A	SELECT BEDDING MATERIAL	CY(FM)	200
02221-B	SELECT FOUNDATION MATERIAL	CY(FM)	500
02227-A	CLEAN SAND BORROW MATERIAL	CY(PM)	26,893
02227-B	TOPSOIL	CY(PM)	9,220
02227-C	SITE GRADING	AC	9.9
02227-D	EXPLORATORY EXCAVATION (TIEBACK RODS)	EA	75
02227-E	EXPLORATORY EXCAVATION (TYPE B3-B WALER REPAIRS)	LF	1,500
02234-A	STONE CONSTRUCTION ENTRANCE	EA	2
02234-B	MAINTENANCE LIMESTONE	CY	500
02295-A	SILT FENCE	LF	3,700
02295-B	TREE PROTECTION FENCING	LS	1
02311-A	MOBILIZATION - HORIZONTAL DIRECTION DRILLING	LS	1
02311-B	20" HDPE CASING – WATER	LF	160
02311-C	12" HDPE WATER MAIN	LF	180
02311-D	12" HDPE/PVC TRANSITION FITTINGS	EA	2
02522-A	NON-REINFORCED CONCRETE PAVEMENT PATCHING (6" THICK)	SY	660
02525-A	REINFORCED CONCRETE SCOUR PAD	SY	6,625
02585-A	REFLECTORIZED TRAFFIC SIGNS & STEEL U-SECTION POST	EA	2
02660-A	12" PVC WATER MAIN	LF	1,500
02660-B	12" GATE VALVES	EA	6
02660-C	FIRE HYDRANT ASSEMBLIES	EA	4

Item No.	Description	Unit	Estimated Quantity
02660-D	16"X12" TAPPING SLEEVE & 12" VALVE	EA	1
02660-E	DUCTILE IRON FITTINGS (WATER)	TON	2
02660-F	24" DUCTILE IRON PIPE (DRAINAGE)	LF	110
02721-A	DRAIN INLETS	EA	3
02721-B	WATER QUALITY STRUCTURE	EA	3
02721-C	REPAIR EXIST. SEAWALL	EA	1
02724-A	24" PVC CULVERT PIPE	LF	75
02831-A	CONSTRUCTION SECURITY FENCE	LS	1
02842-A	THERMOPLASTIC LEGEND (WHITE, 120 MIL)	SF	336.1
02870-A	PROJECT SIGN	LS	1
02931-A	PLANT ESTABLISHMENT (SEEDING)	AC	11
03300-B	DRAINAGE PIPE PENETRATIONS	CY	9
03300-C	CONCRETE TIEBACK REPAIRS	CY	90
03360-C	B3-A - WALER REPAIRS	SF	2,200
03360-D	B3-B - WALER REPAIRS	SF	1,500
03360-E	B4 - WALER REPAIRS	EA	30
03360-F	REINFORCING STEEL	TON	3
03600-A	B1 - WALER REPAIRS (EPOXY INJECT)	LF	100
05122-A	12' GALVANIZED STEEL GATE ASSEMBLY	EA	2
05122-B	6" BOLLARD	EA	65
05500-A	LADDER	EA	1
	<u>BASE BID – GOMESA FUNDING:</u>		
02050-G	REMOVAL OF EXIST. CONCRETE PILE CAP	CF	2715
02050-H	REMOVAL OF EXIST. CONCRETE WALER	CF	625
02050-I	PARTIAL REMOVAL OF TIE RODS	EA	36
02243-A	NON-WOVEN FILTER FABRIC	SF	8,000
02298-A	TURF REINFORCEMENT MAT & ASSEMBLY	SF	18,680
02367-A	PRESTRESSED CONCRETE SHEET PILES	SF	9,900
02368-A	PRESTRESSED CONCRETE WALERS	LF	300
03300-A	PILE CAP	CY	110
03300-D	EXPANSION JOINT REPAIRS	EA	21
03360-A	B2-A WALER REPAIRS	SF	650
03360-B	B2-B WALER REPAIRS	SF	75
05120-A	TIEBACK RODS AND CONNECTORS	EA	36
05120-B	WALER BOLTS	EA	4

Item No.	Description	Unit	Estimated Quantity
	<u>ADDITIVE ALTERNATE A BID:</u>		
01505-B	MOBILIZATION (ADDITIVE ALT. BID A)	LS	1
02050-C	REMOVAL OF EXISTING CONCRETE PAVEMENT	SY	790
02227-D	EXPLORATORY EXCAVATION (TIEBACK RODS)	EA	7
02227-E	EXPLORATORY EXCAVATION (TYPE B3-B WALER REPAIRS)	LF	500
02243-A	NON-WOVEN GEOTEXTILE FABRIC	SF	1,000
03300-C	CONCRETE TIEBACK REPAIRS	CY	10
03300-D	EXPANSION JOINT REPAIRS	EA	11
03360-A	B2-A - WALER REPAIRS	SF	150
03360-B	B2-B - WALER REPAIRS	SF	20
03360-C	B3-A - WALER REPAIRS	SF	2,700
03360-D	B3-B - WALER REPAIRS	SF	500
03360-F	REINFORCING STEEL	TON	2
03600-A	B1 - WALER REPAIRS (EPOXY INJECT)	LF	600
	<u>ADDITIVE ALTERNATE B BID:</u>		
01550-A	BASIN DREDGE MOBILIZATION	LS	1
01550-C	BASIN DREDGING & DISPOSAL	CY	33,942
02050-B	REMOVAL OF EXISTING BREAKWATER & PILING	LS	1
02050-F	REMOVAL OF SUBMERGED OBJECTS FROM MARINA BASIN	LS	1
02360-A	VINYL SHEET PILING	SF	3200
02369-A	18" X 18" PRESTRESSED CONCRETE PILING	LF	1,320
06102-A	TIMBER WALERS & CONNECTORS (BREAKWATER)	LS	1
	<u>ADDITIVE ALTERNATE C BID:</u>		
01550-B	CHANNEL DREDGE MOBILIZATION	LS	1
01550-D	CHANNEL DREDGING & DISPOSAL	CY	8,300
02875-A	DAY MARKERS ASSEMBLY	EA	6