

OFFICE OF STATE AID ROAD CONSTRUCTION  
MISSISSIPPI DEPARTMENT OF TRANSPORTATION  
AND  
SUNFLOWER COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Sunflower County, Mississippi at the Sunflower County Courthouse, Indianola, Mississippi, until 10:00 A.M. on the 17th day of June , 2019, and shortly thereafter publicly opened for the construction of 0.047 miles of REPLACE BRIDGE AND APPROACHES on the COLLEGE AVENUE being known as Project No. ERBR-BR-9641(1)BO in Sunflower County, Mississippi.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

ITEM	QUANTITY	UNIT
<u>ROADWAY ITEMS:</u>		
MOBILIZATION	Lump Sum	LS
CLEARING AND GRUBBING	Lump Sum	LS
REMOVAL OF BOX BRIDGE @ STA. 6+24	1.000	UN
REMOVAL OF EXISTING PAVEMENT	731.000	SY
UNCLASSIFIED EXCAVATION	182.000	CY
BORROW EXCAVATION (FME)		
(CONTRACTOR FURNISHED) (CLASS 9)	936.000	CY
EXCESS EXCAVATION (FM)	287.000	CY
CRUSHED STONE	828.000	TON
SIZE (I) STABILIZER AGGREGATE, COARSE	150.000	TON
MIXING, SHAPING AND COMPACTION	897.000	SY
HOT MIX ASPHALT, (ST) (12.5 MM)	247.000	TON
ASPHALT FOR PRIME COAT (EA-1)	359.000	GAL
CLASS "B" STRUCTURAL CONCRETE, MINOR		
STRUCTURES	4.332	CY
REINFORCING STEEL	280.000	LB
18" ALUMINIZED COATED CORRUGATED		
METAL PIPE, 12 GAGE, 2 2/3" X 7/8"	340.000	LF
18" ALUMINIZED COATED CORRUGATED		
METAL END SECTION, 12 GAGE	4.000	EA
CASTINGS	976.000	LB
GRATINGS	800.000	LB
ROADWAY CONSTRUCTION SURVEYING	Lump Sum	LS
BRIDGE CONSTRUCTION SURVEYING	Lump Sum	LS

SECTION 900  
PROJECT NO. ERBR-STP/BR-0722(7)BO  
SUNFLOWER COUNTY

---

CONCRETE SIDEWALK, WITHOUT REINFORCEMENT	284.000	SY
COMBINATION CONCRETE CURB AND GUTTER, TYPE I	510.000	LF
RIGHT-OF-WAY MARKERS (TYPE I)	8.000	EA
MAINTENANCE OF TRAFFIC	Lump Sum	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	0.780	TON
COMMERCIAL FERTILIZER (13:13:13)	0.120	TON
AMMONIUM NITRATE	0.040	TON
SEEDING	0.390	AC
SOLID SODDING	300.000	SY
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15 - 0.84)	610.000	LF
LOOSE RIPRAP, 200 LB	200.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.21 - 0.43	420.000	SY
TURBIDITY BARRIER	200.000	LF
WATTLES, 20"	300.000	LF

BRIDGE ITEMS:

BOX BRIDGE CONCRETE, CLASS "BB"	281.470	CY
REINFORCEMENT	45,361.000	LB

SECTION 900  
PROJECT NO. ERBR-BR-9641(1)BO  
SUNFLOWER COUNTY

---

NOTICE TO CONTRACTORS:

CONTRACT TIME                      90 WORKING DAYS

BASIS OF AWARD

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The attention of the BIDDER is directed to the State and Federal laws governing selection of and employment of labor.

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND PROPOSALS may be secured from Ronald W. Cassada, County Engineer for Sunflower County, Mississippi, P.O. Drawer A, Indianola. The Cost is fifty dollars (\$50.00) for plans and fifty dollars (\$50.00) for the proposal, non-refundable.

Certified check or bid bond for five percent (5%) of the total bid, made payable to Sunflower County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Glen Donald, President  
Sunflower County Board of Supervisors