



OFFICE OF STATE AID ROAD CONSTRUCTION  
AND  
COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Attala County Mississippi at the ATTALA COUNTY CHANCERY BUILDING, KOSCIUSKO, Mississippi, until 9:00 AM on the 4TH day of MARCH, 2024, and shortly thereafter publicly opened for the construction of 0.095 miles of BRIDGE & APPROACHES on the ATTALA ROAD 5210 being known as Project No. LSBP-04(23) in Attala County Mississippi.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS

ROADWAY ITEMS:

|  | QUANTITY   | UNIT |
|--|------------|------|
| MOBILIZATION   | 1.000      | LS   |
| CLEARING AND GRUBBING  | 1.000      | LS   |
| REMOVAL OF BRIDGE @ STA. 14+39.57                                | 1.000      | UN   |
| REMOVAL OF PIPE  | 102.000    | LF   |
| UNCLASSIFIED EXCAVATION (FM)                                     | 1,684.000  | CY   |
| BORROW EXCAVATION (CONTRACTOR FURNISHED, LVM, CLASS 9)           | 2,400.000  | CY   |
| GRANULAR MATERIAL, (CLASS 3, GROUP "B")                          | 450.000    | TON  |
| CLASS "A" STRUCTURAL CONCRETE                                    | 66.380     | CY   |
| REINFORCING STEEL  | 10,363.000 | LB   |
| ROADWAY CONSTRUCTION SURVEYING                                   | 1.000      | LS   |
| BRIDGE CONSTRUCTION SURVEYING                                    | 1.000      | LS   |
| RIGHT-OF-WAY MARKERS (TYPE I)                                    | 6.000      | EA   |
| MAINTENANCE OF TRAFFIC   | 1.000      | LS   |
| ADDITIONAL CONSTRUCTION SIGNS                                    | 0.000      | SF   |
| REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3) | 4.000      | EA   |

EROSION CONTROL ITEMS:

|   |           |     |
|---|-----------|-----|
| AGRICULTURAL LIMESTONE                                      | 1.600     | TON |
| COMMERCIAL FERTILIZER (13:13:13)                            | 0.240     | TON |
| AMMONIUM NITRATE  | 0.080     | TON |
| SEEDING   | 0.800     | AC  |
| VEGETATIVE MATERIALS FOR MULCH                              | 2.400     | TON |
| EXCELSIOR BLANKET   | 400.000   | SY  |
| TEMPORARY SILT FENCE (TYPE II) (AOS 0.15 - 0.84)            | 500.000   | LF  |
| WATTLES, 20"  | 600.000   | LF  |
| LOOSE RIPRAP, 200 LB.                                       | 680.000   | TON |
| GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.21 - 0.43, NON-WOVEN | 1,430.000 | SY  |

BRIDGE ITEMS:

|   |        |    |
|---|--------|----|
| CLASS "B" STRUCTURAL CONCRETE, MINOR STRUCTURES (FOR PILE ENCASEMENT) | 17.680 | CY |
|---|--------|----|

|   |            |     |
|---|------------|-----|
| REINFORCING STEEL                                     | 226.000    | LB  |
| TEST PILES  | 2.000      | EA  |
| CONVENTIONAL STATIC PILE LOAD TEST                    | 0.000      | EA  |
| 14" STEEL PILING                                      | 3,220.000  | LF  |
| 18" PRE-FORMED PILE HOLES                             | 200.000    | LF  |
| BRIDGE CONCRETE, CLASS "A"                            | 264.560    | CY  |
| 31' PRESTRESSED CONCRETE BEAM, TYPE I+2               | 307.500    | LF  |
| 40' PRESTRESSED CONCRETE BEAM, TYPE I+2               | 397.500    | LF  |
| 100' PRESTRESSED CONCRETE BEAM, TYPE IV               | 498.750    | LF  |
| REINFORCEMENT   | 47,616.000 | LB  |
| CONCRETE RAILING                                      | 484.000    | LF  |
| LOOSE RIPRAP, 300 LB.                                 | 225.000    | TON |
| GEOTEXTILE UNDER RIPRAP, TYPE V, AOS < 0.43 NON-WOVEN | 485.000    | SY  |

PROJECT NO.  
Attala

LSBP-04(23)  
COUNTY

NOTICE TO CONTRACTORS:

CONTRACT TIME: 150 Working Days

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The Board of Supervisors hereby notifies all bidders that it will affirmatively ensure that in any contract entered into pursuant to this advertisement; minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Attala County, CHRISTIAN GARDNER, the LSBP Engineer's office and the Office of the State Aid Engineer, 412 E. Woodrow Wilson Avenue, Jackson, Mississippi. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Christian Gardner, County Engineer for Attala County, Mississippi, P.O. Box 1197, Kosciusko, Mississippi. The cost is \$50 for plans and \$50 for proposal, non refundable.

Certified check or bid bond for five percent (5%) of the total bid, made payable to Attala County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

BILL JOE COFFEE, President  
Attala County Board of Supervisors