

OFFICE OF STATE AID ROAD CONSTRUCTION  
MISSISSIPPI DEPARTMENT OF TRANSPORTATION  
AND  
PEARL RIVER COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Pearl River County, Mississippi at the Pearl River County Courthouse, Poplarville, Mississippi, until 10:00 a.m. on the 3rd day of May, 2018 and shortly thereafter publicly opened for the construction of 0.037 miles of BRIDGE REPLACEMENT on the HARRY SONES ROAD being known as Project No. LSBP-55(32) in Pearl River County, Mississippi. Electronic bids can be submitted at [www.certralbidding.com](http://www.certralbidding.com). For any questions relating to the electronic bidding process, please call 225-810-4814.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

ITEM	QUANTITY	UNIT
<u>ROADWAY ITEMS:</u>		
MOBILIZATION	LUMP SUM	LS
CLEARING AND GRUBBING	LUMP SUM	LS
REMOVAL OF BRIDGE AT STATION 10+43	1.000	UN
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 7)	205.000	CY
CHANNEL EXCAVATION (FM)	100.000	CY
GRANULAR MATERIAL (LVM), (CLASS 6, GROUP C)	150.000	CY
RIGHT-OF-WAY MARKERS (TYPE I)	6.000	EA
MAINTENANCE OF TRAFFIC	LUMP SUM	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS)(TYPE 3)	4.000	EA
<u>EROSION CONTROL ITEMS:</u>		
AGRICULTURAL LIMESTONE	0.800	TON
COMMERCIAL FERTILIZER (13-13-13)	0.400	TON
SEEDING	0.400	AC
VEGETATIVE MATERIALS FOR MULCH	1.200	TON
SOLID SODDING	200.000	SY
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	525.000	LF
LOOSE RIPRAP, 200 LB.	100.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.21-0.43	185.000	SY
WATTLES, 20"	80.000	LF

SECTION 900  
PROJECT NO. LSBP-55(32)  
PEARL RIVER COUNTY

---

BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14" PRESTRESSED CONCRETE PILING	670.000	LF
40' PRECAST CONCRETE SLAB UNIT, 3'-6" INTERIOR	18.000	EA
40' PRECAST CONCRETE SLAB UNIT, 3'-6" EXTERIOR	6.000	EA
PRECAST CONCRETE BARRIER RAIL	240.000	LF
31.17' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE	2.000	EA
31.17' PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE	2.000	EA
9.17' PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP, 300 LB.	151.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.21-0.43	377.000	SY

NOTICE TO CONTRACTORS:

CONTRACT TIME: 45 Working Days

BASIS OF AWARD

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Pearl River County, the LSBP Engineer's office and the Office of the State Aid Engineer, 412 E. Woodrow Wilson Avenue, Jackson, Mississippi. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from H. Les Dungan, III, LSBP Engineer for Pearl River County, Mississippi, 925 Goodyear Blvd., Picayune. The Cost is fifty dollars (\$50.00) for plans and fifty dollars (\$50.00) for the proposal, non-refundable. Or official bid documents can be downloaded from Central Bidding at [www.centralbidding.com](http://www.centralbidding.com).

Certified check or bid bond for five percent (5%) of the total bid, made payable to Pearl River County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Sandy Kane Smith, President  
Pearl River County Board of Supervisors

Publish on:  
April 3, 2018  
April 10, 2018