

OFFICE OF STATE AID ROAD CONSTRUCTION
MISSISSIPPI DEPARTMENT OF TRANSPORTATION
AND
PEARL RIVER COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Pearl River County, Mississippi at the Pearl River County Courthouse, Poplarville, Mississippi, until 10:00 a.m. on the 12th day of June, 2018 and shortly thereafter publicly opened for the construction of 0.181 miles of BRIDGE REPLACEMENT on the OSCAR SMITH ROAD being known as Project No. SAP-55(58) in Pearl River County, Mississippi. Electronic bids can be submitted at www.centralbidding.com. For any questions relating to the electronic bidding process, please call 225-810-4814.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

ITEM	QUANTITY	UNIT
<u>ROADWAY ITEMS:</u>		
MOBILIZATION	LUMP SUM	LS
CLEARING AND GRUBBING	LUMP SUM	LS
REMOVAL OF BRIDGE AT STATION 49+99	1.000	UN
REMOVAL OF PIPE (ALL SIZES)	80.000	LF
UNCLASSIFIED EXCAVATION (FM)	875.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 7)	2,580.000	CY
STRUCTURE EXCAVATION	625.000	CY
GRANULAR MATERIAL (LVM), (CLASS 6, GROUP C)	1,225.000	CY
SIZE II STABILIZER AGGREGATE, COARSE	350.000	CY
HOT MIX ASPHALT, ST 9.5 MM	258.000	TON
HOT MIX ASPHALT, ST 19 MM	540.000	TON
ASPHALT FOR PRIME COAT (EA-1)	859.000	GAL
RIGHT-OF-WAY MARKERS (TYPE I)	14.000	EA
MAINTENANCE OF TRAFFIC	LUMP SUM	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 MILS)	0.364	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 MILS)	1,920.000	LF

SECTION 900
PROJECT NO. SAP-55(58)
PEARL RIVER COUNTY

TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	17.000	EA
TEMPORARY STREAM DIVERSION	1.000	EA

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	3.200	TON
COMMERCIAL FERTILIZER (13-13-13)	1.600	TON
AMMONIUM NITRATE	0.160	TON
SEEDING	1.600	AC
VEGETATIVE MATERIALS FOR MULCH	3.200	TON
SOLID SODDING	200.000	SY
EROSION CONTROL FABRIC	500.000	SY
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	2,000.000	LF
LOOSE RIPRAP, 200 LB.	210.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.21-0.43	410.000	SY
WATTLES, 20"	200.000	LF

BOX BRIDGE ITEMS:

BOX BRIDGE CONCRETE, CLASS "BB"	240.690	CY
REINFORCEMENT	51,770.000	LB

NOTICE TO CONTRACTORS:

CONTRACT TIME: 80 Working Days

BASIS OF AWARD

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Pearl River County, the County Engineer's office and the Office of the State Aid Engineer, 412 E. Woodrow Wilson Avenue, Jackson, Mississippi. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from H. Les Dungan, III, County Engineer for Pearl River County, Mississippi, 925 Goodyear Blvd, Picayune. The Cost is fifty dollars (\$50.00) for plans and fifty dollars (\$50.00) for the proposal, non-refundable. Or official bid documents can be downloaded from Central Bidding at www.centralbidding.com.

Certified check or bid bond for five percent (5%) of the total bid, made payable to Pearl River County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Sandy Kane Smith, President
Pearl River County Board of Supervisors

Publish on:
April 17, 2018
April 24, 2018