

OFFICE OF STATE AID ROAD CONSTRUCTION
MISSISSIPPI DEPARTMENT OF TRANSPORTATION
AND
JEFFERSON DAVIS COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Jefferson Davis County, Mississippi at the Jefferson Davis County Administrative Building, Prentiss, Mississippi, until 10:00 am on the 18th day of February, 2020 and shortly thereafter publicly opened for the construction of 0.047 miles of BRIDGE REPLACEMENT on the CLEM SCHOOL ROAD being known as Project No. SAP-33(49) in Jefferson Davis County, Mississippi.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

ITEM	QUANTITY	UNIT
<u>ROADWAY ITEMS</u>		
MOBILIZATION	LUMP SUM	LS
CLEARING AND GRUBBING	LUMP SUM	LS
REMOVAL OF BRIDGE AT STATION 194+95	1.000	UN
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 7)	395.000	CY
CHANNEL EXCAVATION (FM)	300.000	CY
GRANULAR MATERIAL (LVM), (CLASS 6, GROUP C)	435.000	CY
HOT MIX ASPHALT, ST 9.5 MM	43.000	TON
HOT MIX ASPHALT, ST 19 MM	89.000	TON
ASPHALT FOR PRIME COAT (EA-1)	142.000	GAL
GUARD RAIL, W-BEAM	50.000	LF
GUARD RAIL, BRIDGE END SECTION, TYPE I THRIE-BEAM	4.000	EA
GUARD RAIL, TERMINAL END SECTION	4.000	EA
RIGHT-OF-WAY MARKERS (TYPE I)	4.000	EA
MAINTENANCE OF TRAFFIC	LUMP SUM	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 MILS)	0.097	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 MILS)	510.000	LF
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	5.000	EA
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS)(TYPE 3)	4.000	EA

SECTION 900
PROJECT NO. SAP-33(49)
JEFFERSON DAVIS COUNTY

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	1.000	TON
COMMERCIAL FERTILIZER (13-13-13)	0.500	TON
AMMONIUM NITRATE	0.050	TON
SEEDING	0.500	AC
VEGETATIVE MATERIALS FOR MULCH	1.000	TON
SOLID SODDING	200.000	SY
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	700.000	LF
WATTLES, 20"	80.000	LF
LOOSE RIPRAP, 200 LB.	100.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.21-0.43	185.000	SY

BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14" PRESTRESSED CONCRETE PILING	520.000	LF
18" PRE-FORMED PILE HOLE	140.000	LF
31' PRECAST CONCRETE SLAB UNIT, 3'-6" INTERIOR, 30 DEG SKEW, RT. FWD.	18.000	EA
31' PRECAST CONCRETE SLAB UNIT, 3'-6" EXTERIOR, 30 DEG SKEW, RT. FWD.	6.000	EA
PRECAST CONCRETE BARRIER RAIL	186.000	LF
36' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE, 30 DEG SKEW, RT. FWD.	2.000	EA
36' PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE, 30 DEG SKEW, RT. FWD.	2.000	EA
11.33' PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP, 300 LB.	315.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.21-0.43	761.000	SY

NOTICE TO CONTRACTORS:

CONTRACT TIME: 75 Working Days

BASIS OF AWARD

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Jefferson Davis County, the County Engineer's office and the Office of the State Aid Engineer, 412 E. Woodrow Wilson Avenue, Jackson, Mississippi. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from H. Les Dungan, III, County Engineer for Jefferson Davis County, Mississippi, 1574 Highway 98 East, Columbia. The Cost is fifty dollars (\$50.00) for plans and fifty dollars (\$50.00) for the proposal, non-refundable

Certified check or bid bond for five percent (5%) of the total bid, made payable to Jefferson Davis County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Bobby R. Rushing, President
Jefferson Davis County Board of Supervisors

Publish on:
January 15, 2020
January 22, 2020