

OFFICE OF STATE AID ROAD CONSTRUCTION
MISSISSIPPI DEPARTMENT OF TRANSPORTATION
AND
JEFFERSON DAVIS COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Jefferson Davis County, Mississippi at the Jefferson Davis County Administrative Building, Prentiss, Mississippi, until 10:00 AM on the 7th day of January, 2021 and shortly thereafter publicly opened for the construction of 0.071 miles of MAINTENANCE (OTHER THAN BRIDGE) on the SITE "A": SUMRALL ROAD AND SITE "B": SONAT ROAD being known as Project No. SAP-33(20)M in Jefferson Davis County, Mississippi.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

<u>ITEM</u>	<u>QUANTITY</u>	<u>UNIT</u>
<u>ROADWAY ITEMS:</u>		
MOBILIZATION	LUMP SUM	LS
CLEARING AND GRUBBING	LUMP SUM	LS
REMOVAL OF PIPE (ALL SIZES)	168.000	LF
UNCLASSIFIED EXCAVATION (FM)	600.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 7)	350.000	CY
STRUCTURE EXCAVATION	600.000	CY
GRANULAR MATERIAL (LVM), (CLASS 6, GROUP C)	100.000	CY
CRUSHED STONE	140.000	TON
SIZE II STABILIZER AGGREGATE, COARSE	125.000	CY
HOT MIX ASPHALT, ST 9.5 MM	134.000	TON
COLD MILLING OF BITUMINOUS PAVEMENT, ALL DEPTHS	500.000	SY
CLASS "B" STRUCTURAL CONCRETE, MINOR STRUCTURES	43.950	CY
REINFORCING STEEL	2,092.000	LB
18" REINFORCED CONCRETE PIPE, CLASS III	56.000	LF
72" REINFORCED CONCRETE PIPE, CLASS III	120.000	LF
58" X 36" REINFORCED CONCRETE ARCH PIPE, CLASS III	40.000	LF

SECTION 900
PROJECT NO. SAP-33(20)M
JEFFERSON DAVIS COUNTY

58" X 36" REINFORCED CONCRETE ARCH PIPE, END SECTION	2.000	EA
ROADWAY CONSTRUCTION SURVEYING	LUMP SUM	LS
MAINTENANCE OF TRAFFIC	LUMP SUM	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 MILS)	0.144	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 MILS)	760.000	LF
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	10.000	EA
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS)(TYPE 3)	4.000	EA

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	0.300	TON
COMMERCIAL FERTILIZER (13-13-13)	0.150	TON
AMMONIUM NITRATE	0.020	TON
SEEDING	0.200	AC
VEGETATIVE MATERIALS FOR MULCH	0.400	TON
SOLID SODDING	100.000	SY
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	350.000	LF
WATTLES, 20"	100.000	LF
LOOSE RIPRAP, 200 LB.	100.000	TON
GEOTEXTILE UNDER RIPRAP NON-WOVEN, TYPE V, AOS <0.43	200.000	SY

NOTICE TO CONTRACTORS:

CONTRACT TIME: 75 Working Days

BASIS OF AWARD

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Jefferson Davis County, the County Engineer's office and the Office of the State Aid Engineer, 412 E. Woodrow Wilson Avenue, Jackson, Mississippi. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from H. Les Dungan, III, County Engineer for Jefferson Davis County, Mississippi, 1574 Highway 98 East, Columbia. The Cost is fifty dollars (\$50.00) for plans and fifty dollars (\$50.00) for the proposal, non-refundable

Certified check or bid bond for five percent (5%) of the total bid, made payable to Jefferson Davis County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Bobby Rushing, President
Jefferson Davis County Board of Supervisors

Publish on:
December 2, 2020
December 9, 2020