

OFFICE OF STATE AID ROAD CONSTRUCTION
MISSISSIPPI DEPARTMENT OF TRANSPORTATION
AND
JEFFERSON DAVIS COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Jefferson Davis County, Mississippi at the Jefferson Davis County Administrative Building, Prentiss, Mississippi, until 10:00 a.m. on the 19th day of April, 2021 and shortly thereafter publicly opened for the construction of 0.086 miles of BRIDGE & APPROACHES on the SOUTH PLEASANT HILL ROAD being known as Project No. LSBP-33(21) in Jefferson Davis County, Mississippi.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

ITEM	QUANTITY	UNIT
<u>ROADWAY ITEMS</u>		
MOBILIZATION	LUMP SUM	LS
CLEARING AND GRUBBING	LUMP SUM	LS
REMOVAL OF BRIDGE AT STATION 12+00	1.000	UN
UNCLASSIFIED EXCAVATION (FM)	200.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 7)	550.000	CY
CHANNEL EXCAVATION (FM)	380.000	CY
GRANULAR MATERIAL (LVM), (CLASS 6, GROUP C)	785.000	CY
CRUSHED STONE	100.000	TON
ROADWAY CONSTRUCTION SURVEYING	LUMP SUM	LS
RIGHT-OF-WAY MARKERS (TYPE I)	10.000	EA
MAINTENANCE OF TRAFFIC	LUMP SUM	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS)(TYPE 3)	4.000	EA
<u>EROSION CONTROL ITEMS:</u>		
AGRICULTURAL LIMESTONE	1.200	TON
COMMERCIAL FERTILIZER (13-13-13)	0.600	TON
SEEDING	0.600	AC
VEGETATIVE MATERIALS FOR MULCH	1.800	TON
SOLID SODDING	200.000	SY
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	1,000.000	LF
WATTLES, 20"	200.000	LF
LOOSE RIPRAP, 200 LB.	200.000	TON
GEOTEXTILE UNDER RIPRAP NON-WOVEN, TYPE V, AOS < 0.43	400.000	SY

SECTION 900
PROJECT NO. LSBP-33(21)
JEFFERSON DAVIS COUNTY

BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14" PRESTRESSED CONCRETE PILING	680.000	LF
18" PRE-FORMED PILE HOLE	180.000	LF
31' PRECAST CONCRETE SLAB UNIT, 3'-6" INTERIOR	16.000	EA
31' PRECAST CONCRETE SLAB UNIT, 4'-6" INTERIOR	4.000	EA
31' PRECAST CONCRETE SLAB UNIT, CURB	8.000	EA
BEAM TYPE RAILING WITH CONCRETE POSTS	248.000	LF
26'-6" PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE	3.000	EA
26'-6" PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE	2.000	EA
7.5' PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP, 300 LB.	75.000	TON
GEOTEXTILE UNDER RIPRAP NON-WOVEN, TYPE V, AOS < 0.43	199.000	SY

NOTICE TO CONTRACTORS:

CONTRACT TIME: 60 Working Days

BASIS OF AWARD

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Jefferson Davis County, the LSBP Engineer's office and the Office of the State Aid Engineer, 412 E. Woodrow Wilson Avenue, Jackson, Mississippi. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from H. Les Dungan, III, LSBP Engineer for Jefferson Davis County, Mississippi, 1574 Highway 98 East, Columbia. The Cost is fifty dollars (\$50.00) for plans and fifty dollars (\$50.00) for the proposal, non-refundable.

Certified check or bid bond for five percent (5%) of the total bid, made payable to Jefferson Davis County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Bobby Rushing, President
Jefferson Davis County Board of Supervisors

Publish on:
March 10, 2021
March 17, 2021