

OFFICE OF STATE AID ROAD CONSTRUCTION
MISSISSIPPI DEPARTMENT OF TRANSPORTATION
AND
WALTHALL COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Walthall County, Mississippi at the Walthall County Courthouse, Tylertown, Mississippi, until 10:00 AM on the 18th day of January 2018 and shortly thereafter publicly opened for the construction of 0.113 miles of BRIDGE, BOX BRIDGE, AND APPROACHES on the SITE "A": N. SANDIFER ST. SITE "B": PAYNE ROAD being known as Project No. LSBP-74(21) in Walthall County, Mississippi.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

ITEM	QUANTITY	UNIT
<u>ROADWAY ITEMS:</u>		
MOBILIZATION	LUMP SUM	LS
CLEARING AND GRUBBING	LUMP SUM	LS
REMOVAL OF BRIDGE @ STATION 10+15	1.000	UN
REMOVAL OF BRIDGE @ STATION 13+44	1.000	UN
REMOVAL OF BRIDGE END PAVEMENT	1.000	UN
REMOVAL OF CONCRETE FLUME	10.000	SY
UNCLASSIFIED EXCAVATION (FM)	101.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 7)	1,361.000	CY
EXCESS EXCAVATION (FM)	169.000	CY
STRUCTURE EXCAVATION	240.000	CY
GRANULAR MATERIAL (LVM), (CLASS 6, GROUP C)	480.000	CY
SIZE (II) STABILIZER AGGREGATE, COARSE	240.000	CY
CLASS B STRUCTURAL CONCRETE, MINOR STRUCTURES	0.740	CY
12" REINFORCED CONCRETE PIPE, CLASS III	48.000	LF
15" REINFORCED CONCRETE PIPE, CLASS III	24.000	LF
RIGHT-OF-WAY MARKERS (TYPE I)	20.000	EA
MAINTENANCE OF TRAFFIC	LUMP SUM	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA
TEMPORARY STREAM DIVERSION	1.000	EA
<u>EROSION CONTROL ITEMS:</u>		
AGRICULTURAL LIMESTONE	1.600	TON
COMMERCIAL FERTILIZER (13-13-13)	0.800	TON

SECTION 900
PROJECT NO. LSBP-74(21)
WALTHALL COUNTY

SEEDING	0.800	AC
VEGETATIVE MATERIALS FOR MULCH	1.600	TON
SOLID SODDING	200.000	SY
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	1,200.000	LF
LOOSE RIPRAP, 200 LB.	175.000	TON
WATTLES, 20"	105.000	LF

BRIDGE ITEMS:

SITE "A" ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14" PRESTRESSED CONCRETE PILING	840.000	LF
14" PRE-FORMED PILE HOLES	240.000	LF
19' PRECAST CONCRETE SLAB UNIT, 3'-6" INTERIOR	12.000	EA
31' PRECAST CONCRETE SLAB UNIT, 3'-6" INTERIOR	18.000	EA
19' PRECAST CONCRETE SLAB UNIT, 3'-6" EXTERIOR	4.000	EA
31' PRECAST CONCRETE SLAB UNIT, 3'-6" EXTERIOR	6.000	EA
PRECAST CONCRETE BARRIER RAIL	262.000	LF
31' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE	4.000	EA
31' PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE	2.000	EA
9.25' PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP, 300 LB.	125.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.21-0.43	230.000	SY

BOX BRIDGE ITEMS:

SITE "B" ITEMS:

BOX BRIDGE CONCRETE, CLASS "BB"	320.440	CY
REINFORCEMENT	59,371.000	LB

PROJECT NO. LSBP-74 (21)
WALTHALL COUNTY

NOTICE TO CONTRACTORS:

CONTRACT TIME: 90 Working Days

BASIS OF AWARD

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Walthall County, the LSBP Engineer's office and the Office of the State Aid Engineer, 412 E. Woodrow Wilson Avenue, Jackson, Mississippi. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Jeff J. Dungan, LSBP Engineer for Walthall County, Mississippi, 1574 Highway 98 East, Columbia. The Cost is fifty dollars (\$50.00) for plans and fifty dollars (\$50.00) for the proposal, non-refundable.

Certified check or bid bond for five percent (5%) of the total bid, made payable to Walthall County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Larry Montgomery, President
Walthall County Board of Supervisors

Publish: November 30, 2017
December 7, 2017