

OFFICE OF STATE AID ROAD CONSTRUCTION
MISSISSIPPI DEPARTMENT OF TRANSPORTATION
AND
MARION COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Marion County, Mississippi at the Marion County Board Office 215 Broad St, Columbia, Mississippi, until 10:00 AM on the 10th day of December, 2019 and shortly thereafter publicly opened for the construction of 0.084 miles of BRIDGE AND APPROACHES on the OLD HIGHWAY 35 S being known as Project No. LSBP-46(16) in Marion County, Mississippi. Electronic bids can be submitted at www.centralbidding.com. For any questions relating to the electronic bidding process, please call 225-810-4814.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

ITEM	QUANTITY	UNIT
<u>ROADWAY ITEMS:</u>		
MOBILIZATION	LUMP SUM	LS
CLEARING AND GRUBBING	LUMP SUM	LS
REMOVAL OF BRIDGE AT STATION 12+03	1.000	UN
UNCLASSIFIED EXCAVATION (FM)	55.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 7)	160.000	CY
GRANULAR MATERIAL (LVM), (CLASS 6, GROUP C)	300.0	CY
ROADWAY CONSTRUCTION SURVEYING	LUMP SUM	LS
RIGHT-OF-WAY MARKERS (TYPE I)	8.000	EA
MAINTENANCE OF TRAFFIC	LUMP SUM	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA
<u>EROSION CONTROL ITEMS:</u>		
AGRICULTURAL LIMESTONE	1.400	TON
COMMERCIAL FERTILIZER (13-13-13)	0.700	TON
SEEDING	0.700	AC
VEGETATIVE MATERIALS FOR MULCH	2.100	TON
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	800.000	LF
WATTLES, 20"	90.000	LF
LOOSE RIPRAP, 200 LB.	50.000	TON
<u>BRIDGE ITEMS:</u>		
TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14" PRESTRESSED CONCRETE PILING	1,270.000	LF
18" PRE-FORMED PILE HOLES	320.000	LF
19' PRECAST CONCRETE SLAB UNIT,	12.000	EA

SECTION 900
PROJECT NO. LSBP-46(16)
MARION COUNTY

31-6" INTERIOR		
31' PRECAST CONCRETE SLAB UNIT, 31-6" INTERIOR	30.000	EA
19' PRECAST CONCRETE SLAB UNIT, CURB	4.000	EA
31' PRECAST CONCRETE SLAB UNIT, CURB	10.000	EA
BEAM TYPE RAILING WITH CONCRETE POSTS	386.000	LF
29' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE	6.000	EA
29' PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE	2.000	EA
7.5' PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP, 300 LB.	90.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.21-0.43, NON-WOVEN	185.000	SY

NOTICE TO CONTRACTORS:

CONTRACT TIME: 60 Working Days

BASIS OF AWARD

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Marion County, the LSBP Engineer's office and the Office of the State Aid Engineer, 412 E. Woodrow Wilson Avenue, Jackson, Mississippi. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Jeff J. Dungan, LSBP Engineer for Marion County, Mississippi, 1574 Highway 98 East, Columbia. The Cost is fifty dollars (\$50.00) for plans and fifty dollars (\$50.00) for the proposal, non-refundable. Or official bid documents can be downloaded from Central Bidding at www.centralbidding.com.

Certified check or bid bond for five percent (5%) of the total bid, made payable to Marion County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Terry Broome, President
Marion County Board of Supervisors

Publish: November 7, 2019
November 14, 2019