

LEGAL NOTICE

Notice is hereby given that the Lee County Board of Supervisors will at the Board of Supervisors Center located at 300 West Main Street, in the City of Tupelo, Mississippi, at 10:00 A.M. on the 4th of April, 2019 accept sealed bids for Roof replacement for the Lee County Justice Center according to specifications on file with the Clerk of the Board. Sealed bids should be filed with the Clerk of the Board on or before said time. The Board reserves the right to reject any and all bids and to waive informalities. Bids may be submitted as follows:

Hand-deliver- 300 West Main Street, Tupelo, MS 38804

Mailing- P. O. Box 1785, Tupelo, MS 38802-1785

Electronic Bid-Official Bid documents can be downloaded from Central Bidding at www.centralbidding.com.

Electronic bids can also be submitted through www.centralbidding.com. For technical questions relating to the electronic bidding process on Central Bidding, please call Central Bidding Support at 225-810-4814

Done by unanimous vote of the Board of Supervisors of Lee County, Mississippi, this the 19th day of November 2018.

/Mike Smith/
President

/Bill Benson/
Clerk

LEE COUNTY JUSTICE CENTER ROOF REPLACEMENT SPECIFICATIONS
200 JEFFERSON STREET, TUPELO MS 38801

Option 1

1. Remove and dispose of gravel from EPDM roof. Gravel shall be taken to the Lee County Central Road Maintenance Facility located at 369 North Eason Blvd., Tupelo, MS 38804
2. Remove and dispose of EPDM roof membrane
3. Install 45 mil or greater white TPO roof system mechanically fastened to concrete roof
4. Install new scuppers, drain boots and strainers
5. Install new protector pads around roof hatch and equipment on roof
6. Install new flashings
7. Clean and haul off debris daily
8. State warranty information in writing on bid
9. Approximate Square footage is 20,000 sq. ft.

Option 2

1. Remove gravel and take to Lee County Central Road Maintenance Facility as per option 1
2. Install separator sheathing on top of old EPDM roof
3. Install 45 mil or greater TPO roof system mechanically attached to concrete roof
4. Install new scuppers, drain boots and strainers
5. Install new protector pads around roof hatch and equipment on roof
6. Install new flashings
7. Clean and haul off debris daily
8. State warranty information in writing on bid
9. Approximate Square footage is 20,000 sq. ft.