

OFFICE OF STATE AID ROAD CONSTRUCTION  
AND  
COUNTY BOARD OF SUPERVISORS  
  
SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Sharkey County Mississippi at the Sharkey County Courthouse, Rolling Fork, Mississippi, until 10:00 AM on the 24<sup>th</sup> day of January, 2024 and shortly thereafter publicly opened for the construction of 0.044 miles of BRIDGE & APPROACHES on the Coleho Road being known as Project No. LSBP-63-(14) in Sharkey County Mississippi.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS

<u>ROADWAY ITEMS:</u>	QUANTITY	UNIT
MOBILIZATION	LS	LS
CLEARING AND GRUBBING	LS	LS
REMOVAL OF BRIDGE (1+89.51)	1	UN
REMOVAL OF PIPE (ALL SIZES)	110	LF
UNCLASSIFIED EXCAVATION (FM)	202	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9 )	576	CY
CHANNEL EXCAVATION (FM)	170	CY
CRUSHED STONE No. 825 B	252	TON
36" POLYMERIC COATED CORRUGATED METAL PIPE, 14 GAGE, 2-2/3" x 1/2" CORRUGATION	160	LF
RIGHT-OF-WAY MARKERS (TYPE II )	6	EA
MAINTENANCE OF TRAFFIC	1	LS
ADDITIONAL CONSTRUCTION SIGNS	0	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3 )	4	EA
 <u>EROSION CONTROL ITEMS:</u>		
AGRICULTURAL LIMESTONE	0.70	TON
COMMERCIAL FERTILIZER ( 13:13:13 )	0.35	TON
SEEDING	0.35	AC
VEGETATIVE MATERIALS FOR MULCH	1.05	TON
TEMPORARY SILT FENCE (TYPE II ) (AOS 0.15 - 0.84 )	450	LF
WATTLES, 20" DIAMETER	100	LF
LOOSE RIPRAP, 300 LB.	63	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.12 - 0.43	125	SY
 <u>BRIDGE ITEMS:</u>		
TEST PILE	2	EA
CONVENTIONAL STATIC PILE LOAD TEST	0	EA
14" PRESTRESSED CONCRETE PILING	830	LF
18" PRE-FORMED PILE HOLES	200	LF
19' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR, 30 DEG SKEW, RT FWD	8	EA
19' PRECAST CONCRETE SLAB UNIT, 4.5' INTERIOR, 30 DEG SKEW, RT FWD	4	EA

PROJECT NO. LSBP-63(14)  
Sharkey COUNTY

31' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR, 30 DEG SKEW, RT FWD	4	EA
31' PRECAST CONCRETE SLAB UNIT, 4.5' INTERIOR, 30 DEG SKEW, RT FWD	2	EA
19' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR, 30 DEG SKEW, RT FWD	4	EA
31' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR, 30 DEG SKEW, RT FWD	2	EA
PRECAST CONCRETE BARRIER RAIL	138	LF
38' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE, 30 DEG SKEW, RT FWD.	2	EA
38' PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE, 30 DEG SKEW, RT FWD.	2	EA
11.33' PRECAST CONCRETE WING	4	EA
LOOSE RIPRAP, 300 LB.	141	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, NON-WOVEN, AOS<0.43	285	SY

NOTICE TO CONTRACTORS:

CONTRACT TIME: 120 Working Days

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The Board of Supervisors hereby notifies all bidders that it will affirmatively ensure that in any contract entered into pursuant to this advertisement; minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Sharkey County, Marcus E. Hooker, Sr., PE, PLS, the LSBP Engineer's office and the Office of the State Aid Engineer, 412 E. Woodrow Wilson Avenue, Jackson, Mississippi. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

Certified check or bid bond for five percent (5%) of the total bid, made payable to Sharkey County and the State of Mississippi must accompany each proposal.

PLANS AND PROPOSALS may be secured from Marcus E. Hooker, Sr., LSBP Engineer for Sharkey County, Mississippi, P.O. Box 368 Greenville, MS 38701. The Cost is fifty dollars (\$50.00) for plans and fifty dollars (\$50.00) for the proposal, non-refundable.

The Bid Schedule may be examined at the following location: Mississippi Procurement Technical Assistance Program (MPTAP), Mississippi Development Authority, Minority & Small Business Development Woolfolk Building, 501 North West Street, Suite B 01, Jackson, MS 39201, 601-359-3448 and Northwest MS Contract Procurement Office, 7075 Golden Oaks

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

William Newsom, President  
Sharkey County Board of Supervisors