

OFFICE OF STATE AID ROAD CONSTRUCTION
MISSISSIPPI DEPARTMENT OF TRANSPORTATION
AND
RANKIN COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Rankin County, Mississippi at the Rankin County Administrative Building, Brandon, Mississippi, until 10:00 am on the 21st day of April, 2023 and shortly thereafter publicly opened for the construction of 0.079 miles of BRIDGE AND APPROACHES on the SITE "A" PLEASANT STREET AND SITE "B" KERSH ROAD being known as Project No. LSBP-61(6) in Rankin County, Mississippi.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

ITEM	QUANTITY	UNIT
<u>ROADWAY ITEMS:</u>		
MOBILIZATION	LUMP SUM	LS
CLEARING AND GRUBBING	LUMP SUM	LS
REMOVAL OF PRECAST BRIDGE STA. 11+35.50 SITE "A"	1.000	EA
REMOVAL OF PRECAST BRIDGE STA. 1+89.15 SITE "B"	1.000	EA
REMOVAL OF ASPHALT PAVEMENT (ALL DEPTHS)	772.000	SY
UNCLASSIFIED EXCAVATION (FM)	385.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	110.000	CY
EXCESS EXCAVATION (FM)	353.000	CY
GRANULAR MATERIAL (LVM), (CLASS 5, GROUP C)	462.000	CY
GUARD RAIL, "W" BEAM, COMPLETE IN PLACE	50.000	LF
GUARD RAIL, BRIDGE END SECTION, TYPE "I", THRIE BEAM	4.000	EA
GUARD RAIL, TERMINAL END SECTION	4.000	EA
RIGHT-OF-WAY MARKERS (TYPE I)	9.000	EA
MAINTENANCE OF TRAFFIC	LUMP SUM	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	8.000	EA
<u>EROSION CONTROL ITEMS:</u>		
AGRICULTURAL LIMESTONE	0.400	TON
COMMERCIAL FERTILIZER (13-13-13)	0.190	TON
AMMONIUM NITRATE	0.020	TON
SEEDING	0.190	AC
VEGETATIVE MATERIALS FOR MULCH	0.570	TON

SECTION 900
PROJECT NO. LSBP-61(6)
RANKIN COUNTY

SOLID SODDING	100.000	SY
TEMPORARY SILT FENCE (TYPE I) (AOS 0.15MM-0.84MM)	1,950.000	LF
WATTLES, 20 INCH	240.000	LF
LOOSE RIPRAP, 300 LB.	80.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.21-0.43	155.000	SY

BRIDGE ITEMS:

SITE "A" ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
10" STEEL PILING	320.000	LF
18" PRE-FORMED PILE HOLES	100.000	LF
40' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR, 30 DEG SKEW, RT FWD	6.000	EA
40' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR, 30 DEG SKEW, RT FWD	2.000	EA
PRECAST CONCRETE BARRIER RAIL	80.000	LF
36.00' PRECAST CONCRETE CAP, END UNIT, STEEL PILE, 30 DEG SKEW, RT. FWD.	2.000	EA
11.00' PRECAST CONCRETE WING	4.000	EA
GROUTED RIPRAP	145.000	SY
GEOTEXTILE UNDER RIPRAP, TYPE V NON-WOVEN, AOS<0.21-0.43	183.000	SY

SITE "B" ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14" PRESTRESSED CONCRETE PILING	590.000	LF
18" PRE-FORMED PILE HOLES	200.000	LF
31' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	18.000	EA
31' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	6.000	EA
PRECAST CONCRETE BARRIER RAIL	186.000	LF
31' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE,	2.000	EA
31' PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE,	2.000	EA
9.25' PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP, 300 LB.	970.000	TON
GEOTEXTILE UNDER RIPRAP,	1,780.000	SY

SECTION 900
PROJECT NO. LSBP-61(6)
RANKIN COUNTY

TYPE V NON-WOVEN, AOS<0.21-0.43

NOTICE TO CONTRACTORS:

CONTRACT TIME: 100 Working Days

BASIS OF AWARD

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Rankin County, the County Engineer's office, and the Office of the State Aid Engineer, 412 E. Woodrow Wilson Avenue, Jackson, Mississippi. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Plan House Printing. Those interested in viewing or obtaining documents or submitting an electronic bid are required to register for an account at www.engserviceplans.com. Registration requires a valid email address. Bid Documents may be obtained upon payment of \$200 (which is non-refundable) and must be purchased through the website or by phone. Call Plan House Printing at (662)407-0193 regarding questions about registration or placing orders.

ELECTRONIC BIDS shall be submitted in pdf format to www.engserviceplans.com. Electronic bid submittals shall include a cover sheet with the information required for envelopes containing paper bid submittals. The Bidder is fully responsible for on time delivery of bids regardless of bid submittal method chosen. In the event that an electronically submitted bid has a corrupted attachment, the bid will be considered null and void.

Certified check or bid bond for five percent (5%) of the total bid, made payable to Rankin County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Brad Calhoun, President
Rankin County Board of Supervisors