

OFFICE OF STATE AID ROAD CONSTRUCTION  
MISSISSIPPI DEPARTMENT OF TRANSPORTATION  
AND  
CHICKASAW COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Chickasaw County, Mississippi at the Chickasaw County Courthouse, One Pinson Square, Houston, Mississippi, until 10:00 AM on the 27th day of March, 2019 and shortly thereafter publicly opened for the construction of 1.465 miles of GRADE, DRAIN, BASE AND DBST on COUNTY ROAD 93 being known as Project No. LSRP-09(3) in Chickasaw County, Mississippi.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

<u>ITEM</u>	<u>QUANTITY</u>	<u>UNIT</u>
<u>ROADWAY ITEMS:</u>		
MOBILIZATION	LUMP SUM	LS
CLEARING AND GRUBBING	LUMP SUM	LS
UNCLASSIFIED EXCAVATION (PM)	7,865.000	CY
BORROW EXCAVATION (F.M.E.)	408.000	CY
(CONTRACTOR FURNISHED) (CLASS 9)		
GRANULAR MATERIAL (LVM),	130.000	CY
(CLASS 5, GROUP "C")		
GRANULAR MATERIAL (LVM),	13,488.000	CY
(CLASS 9, GROUP "B")		
PORTLAND CEMENT	6,723.000	CWT
SOIL-CEMENT-WATER MIXING	19,867.000	SY
(MULTIPLE PASS MIXERS)		
HOT MIX ASPHALT, (ST) (9.5 MM)	20.000	TON
POLYMERIZED-EMULSIFIED ASPHALT,	15,660.000	GAL
GRADE CRS-2P		
COARSE AGGREGATE COVER MATERIAL,	350.000	CY
SIZE 6		
SEAL AGGREGATE COVER MATERIAL,	188.000	CY
SIZE 7		
BLOTTER MATERIAL	27.000	CY
CLASS "B" STRUCTURAL CONCRETE,	1.964	CY
MINOR STRUCTURES		
24" REINFORCED CONCRETE PIPE,	72.000	LF
CLASS III		
36" REINFORCED CONCRETE PIPE,	32.000	LF
CLASS III		
42" REINFORCED CONCRETE PIPE,	40.000	LF
CLASS III		
48" REINFORCED CONCRETE PIPE,	64.000	LF
CLASS III		
60" REINFORCED CONCRETE PIPE,	32.000	LF
CLASS III		
24" REINFORCED CONCRETE PIPE,	4.000	EA
END SECTION		

SECTION 900  
PROJECT NO. LSRP-09(3)  
CHICKASAW COUNTY

---

36" REINFORCED CONCRETE PIPE, END SECTION	2.000	EA
42" REINFORCED CONCRETE PIPE, END SECTION	2.000	EA
48" REINFORCED CONCRETE PIPE, END SECTION	4.000	EA
60" REINFORCED CONCRETE PIPE, END SECTION	2.000	EA
36" X 23" REINFORCED CONCRETE ARCH PIPE, CLASS A-III	32.000	LF
36" X 23" REINFORCED CONCRETE ARCH PIPE, END SECTION	2.000	EA
15" CORRUGATED POLYETHYLENE PIPE	48.000	LF
18" CORRUGATED POLYETHYLENE PIPE	208.000	LF
24" CORRUGATED POLYETHYLENE PIPE	60.000	LF
RIGHT-OF-WAY MARKERS (TYPE II)	106.000	EA
MAINTENANCE OF TRAFFIC	LUMP SUM	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 MIL)	2.909	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 MIL)	15,460.000	LF
THERMOPLASTIC LEGEND (WHITE) (120 MIL)	288.000	LF
REFLECTORIZED TRAFFIC WARNING SIGN (ENCAPSULATED LENS)	8.000	EA
REFLECTORIZED TRAFFIC REGULATORY SIGN (ENCAPSULATED LENS)	3.000	EA
REFLECTORIZED TRAFFIC WARNING SIGN WITH SUPP. PLATE (ENCAPSULATED LENS)	5.000	EA
<u>EROSION CONTROL ITEMS:</u>		
AGRICULTURAL LIMESTONE	11.140	TON
COMMERCIAL FERTILIZER (13-13-13)	5.570	TON
AMMONIUM NITRATE	1.390	TON
SEEDING	5.570	AC
VEGETATIVE MATERIALS FOR MULCH	11.140	TON
SOLID SODDING	2,075.000	SY
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	3,500.000	LF
WATTLES, 20"	1,200.000	LF
LOOSE RIPRAP, 200 LB.	60.000	TON

NOTICE TO CONTRACTORS:

CONTRACT TIME: 140 Working Days

BASIS OF AWARD

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Chickasaw County, the County Engineer's office and the Office of the State Aid Engineer, 412 E. Woodrow Wilson Avenue, Jackson, Mississippi. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Carrson Neal, County Engineer for Chickasaw County, Mississippi, P. O. Box 1526, Tupelo. The Cost is fifty dollars (\$50.00) for plans and fifty dollars (\$50.00) for the proposal, non-refundable

Certified check or bid bond for five percent (5%) of the total bid, made payable to Chickasaw County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Bill Blissard, President  
Chickasaw County Board of Supervisors