









SIDEWALK & ADA RAMP DETAILS

TP BE 9-29-21 ISSUED FOR ADDENDUM #1

PROJECT NOTES

- UNLESS STATED WITHIN THE CONTRACT SPECIFICATIONS OR SHOWN ON THE CONSTRUCTION PLANS ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE MISSISSIPPI DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION, CURRENT EDITION.
- THE CONTRACTOR SHALL USE BEST MANAGEMENT PRACTICES TO CONTROL RUNOFF VELOCITIES AND TO REDUCE EROSION BY EMPLOYING HAY BALES, SILT FENCING AND TEMPORARY SEEDING AND TEMPORARY MULCHING. REFER TO THE MISSISSIPPI PLANNING AND DESIGN MANUAL FOR THE CONTROL OF EROSION, SEDIMENT AND STORMWATER
- 3 IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO ADEQUATELY SCHEDULE CONSTRUCTION ACTIVITIES AS TO IMMEDIATLEY COVER (UPON APPROVAL) THE SUBGRADE WITH THE BASE COURSE SHOWN IN THE CONSTRUCTION PLANS. IN ANY EVENT SHOULD CONTRACTOR LET THE SUBGRADE BECOME UNSUITABLE TO ALLOW FOR THE INSTALLATION OF THE BASE MATERIAL DUE TO WEATHER EVENTS THE CONTRACTOR SHALL IMPROVE THE SUBGRADE BY MEANS RECOMMENDED BY THE TESTING LABORATORY AT NO EXPENSE TO THE OWNER.
- UPON COMPLETION OF CONSTRUCTION OF THE ROADWAY THE CONTRACTOR SHALL DRESS THE PERIMETER OF THE ROADWAY AREA WITH ON SITE MATERIAL. THIS SHAPING AROUND THE ROADWAY SHALL NOT CAUSE IMPEDMENT TO THE STORMWATER RUNOFF FROM THE ROADWAY.
- 5. THE LOCATIONS SHOWN FOR UNDERGROUND UTILITIES ARE APPROXIMATE. THE CONTRACTOR SHALL DETERMINE THE EXACT LOCATION OF ALL EXISTING UTILITIES BEFORE COMMENCING WORK IN EACH AREA. THE CONTRACTOR AGREES TO BE COMPLETELY RESPONSIBLE FOR ANY AND ALL DAMAGES WHICH MIGHT OCCUR BY HIS FAILURE TO EXACTLY LOCATE AND PRESERVE ANY AND ALL UTILITIES.
- ALL ROADS DAMAGED BY CONSTRUCTION OPERATIONS ARE TO BE PATCHED OR RECONSTRUCTED AS DIRECTED BY THE CITY/COUNTY ENGINEER.
- ANY NECESSARY PERMITS ARE THE RESPONSIBILITY OF THE CONTRACTOR.
- 8. THE CONTRACTOR IS CAUTIONED TO VISIT THE SITE AND FAMILIARIZE HIMSELF WITH THE PROJECT PRIOR TO BIDDING AND / OR CONSTRUCTION.
- IT SHALL BE THE CONTRACTORS RESPONSIBILITY TO PRESERVE OR RELOCATE ALL BENCHMARKS AS NEEDED DURING CONSTRUCTION. ANY PUBLIC LAND CORNER MONUMENTS WITHIN THE LIMITS OF CONSTRUCTION SHALL BE PROTECTED. IF A CORNER MONUMENT IS IN DANGER OF BEING DESTROYED AND HAS NOT BEEN PROPERLY REFERENCED, THE CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY.
- 10. EXISTING DRAINAGE FEATURES WITHIN CONSTRUCTION LIMITS SHALL REMAIN UNLESS OTHERWISE NOTED.
- 11. THE CONTRACTOR IS TO USE CAUTION WHEN WORKING IN OR AROUND AREAS OF OVERHEAD TRANSMISSION LINES AND UNDERGROUND UTILITIES.
- 12. THE CONTRACTOR SHALL MATCH EXISTING GRADES AT THE BEGINNING AND END OF CONSTRUCTION AS DIRECTED BY THE ENGINEER.
- 13. EXISTING STREETS AND DRIVES SHALL BE MAINTAINED TO LOCAL TRAFFIC AND PROPERTY OWNERS.
- 14. EXISTING STREET AND ROAD NAME SIGNS ON THE PROJECT SHALL BE KEPT VISIBLE AT ALL TIMES FOR THE FACILITATION OF ACCESS BY EMERGENCY VEHICLES. ALL OTHER SIGNS THAT CONFLICT WITH THE CONSTRUCTION OPERATIONS SHALL BE TAKEN DOWN AND STOCKPILED WITHIN THE R/W LIMITS BY THE CONTRACTOR AS DIRECTED BY THE ENGINEER. ANY EXISTING SIGNS THAT ARE TO BE RESET AND ARE DAMAGED BEYOND USE BY THE CONTRACTOR SHALL BE REPLACED BY THE CONTRACTOR AT HIS EXPENSE.
- 15. THE CONTRACTOR SHALL MAINTAIN AT LEAST ONE 10' OPEN LANE AT ALL TIMES. NO EXCAVATION SHALL REMAIN OVERNIGHT.
- 16. IN THE EVENT THAT SURVEY MONUMENTATION OR REFERENCE POINTS ARE MISSING OR HAVE BEEN DESTROYED, PLEASE CONTACT THE ENGINEER.
- 17. VEGETATION ON R/W SHALL BE RESTORED TO ORIGINAL CONDITION UNLESS OTHERWISE
- 18. UTILITIES ARE TO REMAIN AND BE PROTECTED DURING CONSTRUCTION. NECESSARY REPAIRS SHALL BE CONSIDERED INCIDENTAL TO OTHER PAY ITEMS AND SHALL BE TO THE SATISFACTION OF THE UTILITY OWNERS
- 19. FOR ITEMS INCLUDING, BUT NOT LIMITED TO 2" DOMESTIC WATER PIPE, 4" SEWER SERVICE LINE, CONCRETE SIDEWALK AND UNDERDRAIN: ALL WORK NECESSARY TO THE COMPLETION OF THE BID ITEM (EXCAVATION, STONE BACKFILL, STRUCTURAL BACKFILL, FILTER FABRIC, ETC.) SHALL BE CONSIDERED A SUBSIDIARY OBLIGATION OF THE RESPECTIVE BID ITEM.
- 20. FILL SHALL BE PROPERLY PLACED, COMPACTED, AND PREPARED. SOD, SEED OR MULCH THE DISTURBED AREA.
- 21. ANY MAILBOXES WHICH ARE DAMAGED DUE TO RELOCATION OR CONSTRUCTION OPERATIONS SHALL BE REPLACED BY THE CONTRACTOR AT HIS EXPENSE.
- 22. IF NO PAY ITEM IS LISTED FOR MAILBOX RELOCATION, THE COST THEREOF SHALL BE INCLUDED IN OTHER ITEMS BID.
- 23. ALL LABOR, EQUIPMENT AND MATERIALS (INCULDING VALVES, FITTINGS, ETC.) REQUIRED FOR INSTALLATION OF THE POTABLE WATER AND SEWER LINES SHALL BE INCLUDED IN THE UINIT PRICING.
- 24. OWNER WILL FURNISH TESTING LABORATORY SERVICES, CONSTRUCTION BEST MANAGEMENT PLAN AND INSPECTION SERVICES.
- 25. CONTRACTOR SHALL FURNISH HIS OWN CONSTRUCTION SURVEY SERVICES. OWNER WILL FURNISH PROFESSIONAL LAND SURVEYOR TO PERFORM QUALITY ASSURANCE CHECKING OF GRADES, LAYOUTS AND TO INSTALL CONSTRUCTION SURVEY CONTROL MONUMENTS ON—SITE (1st SET). CONTRACTOR SHALL BE RESPONSIBLE TO RE—INSTALL ANY DAMAGED CONSTRUCTION SURVEY CONTROL MONUMENTS AT HIS OWN COST AND BY A PROFESSIONAL LAND SURVEYOR REGISTERED IN THE STATE OF MISSISSIPPI

Z Ö, EERIN(

5, SURVEYING & ENVIRONMENTAL SI OULA • BILOXI • BAY ST. LO -3970 228-432-2133 228-467-27 www.comptonengineering.com GIN CAGOULA 762-3970

COMPTON



DETAIL

CURBING

PAVEMENT

NOTES,

REPAIRS SS CHRISTIAN REAST HARBOR F PAS BOR OF I **SMALL**

AS NOTED 221-018.003 B. ESCHER B. LADNER SCALE:
JOB NO.
DATE:
DSGN.:
DWG. BY
CHK.:

C4.4

A 9-29-21 ISSUED FOR ADDENDUM #1

TP BE