

ADDENDUM #1

Option 3

1. Remove gravel from roof and take to Central Shop as per option 1
2. Remove and dispose of EPDM roof membrane
3. Install 45 mil or greater white TPO roof system fully adhered to concrete deck
4. Install new scuppers ,drain boots and strainers
5. Install new protector pads around roof hatch and equipment on roof
6. Install new flashings
7. Clean and haul off debris daily
8. State warranty information in writing on bid
9. Approximate Square footage 20,000 sq. ft.