

**HANCOCK COUNTY UTILITY AUTHORITY
WESTERN REGIONAL WWTF OUTFALL RELOCATION PROJECT
BID SCHEDULE**

Item No.	Description	Unit	Estimated Quantity
01030-A	SPECIAL \$50,000 MDOT PERFORMANCE BOND	LS	1
01505-A	MOBILIZATION	LS	1
02050-A	REMOVAL OF EXISTING AIR RELEASE VALVES	EA	3
02221-A	SELECT BEDDING MATERIAL	CY	200
02221-B	SELECT SANDY BACKFILL	CY	500
02295-A	STORMWATER MANAGEMENT	LS	1
02311-A	8" ID MINIMUM HDPE, SDR 11, SEWER FORCE MAIN (HDD METHODS)	LF	650
02311-B	8" ID MINIMUM HDPE, SDR 11, SEWER FORCE MAIN (HDD METHODS)(RIVER DISCHARGE)	LF	450
02575-A	GRANULAR SURFACE REPAIR	CY	2,500
02668-A	16" STEEL CASING (BORE AND JACK)	LF	50
02732-A	8" PVC SEWER FORCE MAIN	LF	25,000
02732-B	8" DUCTILE IRON RESTRAINED JOINT SEWER FORCE MAIN (CARRIER PIPE INSTALLED INSIDE OF CASING PIPE)	LF	60
02732-C	DUCTILE IRON FITTINGS	TON	3.00
02732-D	LOCATE AND CONNECT TO EXISTING 8" SEWER FORCE MAIN	EA	1
02732-E	LOCATOR WIRE ASSEMBLY	EA	13
02733-A	8" GATE VALVE WITH BOX AND PAD	EA	2
02733-B	AIR RELEASE VALVE WITH VAULT	EA	2
02831-A	CHAIN LINK FENCE AND GATES	LF	52
02841-A	MAINTENANCE OF TRAFFIC	LS	1
02931-A	PLANT ESTABLISHMENT	LS	1
11214-A	REMOVE AND REPLACE VERTICAL TURBINE PUMPS (2)	LS	1