This solicitation amendment modifies the specifications for the renovation/construction at McIvor Creek Shooting Range. All bidders should note these changes made to the previous specifications found in the original bid packet. **Exterior:**

- 1.1 Remove existing column covers and install a new 12" square wood column wrap using rough sawn cypress material and a 1'4" square base utilizing the same materials. This work would be installed on the two (2) front entry columns and the seven (7) columns at the back porch for a total of nine (9). Exterior columns and base are to be stained using READY SEAL (Stain and Sealer for wood) color to be Dark Walnut.
- 1.2 Handrails are to be removed at entrance of building.

New Interior Finishes:

- 6.1 Add new 8" x 4" Rough Sawn Cedar Wrapped False Beams at (2) locations in new Community Room Ceiling.
- 8.2 All walls including hallway and office to remain drywall finished and be painted with colors selected By owner from manufacturer's standard color palette and be complimentary with the new wood ceilings and floor
- 11.1 Install new Rough sawn cedar 1x3 squared on four (4) sides, field stained and sealed chair rail. Chair rail will be mounted at standard building height of 34" above the finished floor.

Delete # 12

-	
AUTHORIZED SIGNATURE:	
NAME AND TITLED (TYPED):	
DATE:	