



OSARC
OFFICE OF
STATE AID ROAD CONSTRUCTION



Harry Lee James, P.E.
State Aid Engineer
P.O. Box 1850

412 E. Woodrow Wilson Ave.
Jackson, Mississippi 39216
Fax (601) 373-7141

March 3, 2021

Board of Supervisors
Amite County
c/o Chancery Clerk
Liberty, MS 39645

Gentlemen:

RE: **LOCAL SYSTEM BRIDGE PROGRAM**
PROJECT NO. LSBP-03(23)
AMITE COUNTY

The Plans and specifications for the above numbered project have been reviewed and are herewith approved. You are, therefore, authorized to advertise this project for bids. The work to be done under this project consists of **Concrete Bridge, Box Culvert and Gravel Approaches**.

The date for opening these bids has been set for **Monday, April 5, 2021 at 10:00 a.m.** in the **Boardroom at Liberty**.

In accordance with the Provisions of Section 31-7-13, Mississippi Code of 1972 as amended by House Bills numbered 901 and 1306 of the 1991 regular Legislative Session, the advertisement for receipt of bids on this project must be made once each week for two (2) consecutive weeks in a regular newspaper published in your county and, further, that the date as published for the bid opening shall not be less than fifteen (15) working days after the last published notice. The date, as set above, should be no sooner than the sixteenth working day after the last advertisement appears in the newspaper.

We are returning herewith an approved copy of the Plans and Proposal Documents to be filed by your Clerk when advertisement is begun.

Sincerely,

Harry Lee James, P. E.
State Aid Engineer

Evelyn Hollins

By: Evelyn Hollins
Administrative Assistant

pc: David Cothren, P.E., Co. Eng./Project Eng.
Supervisor District(s) 2
Chris Dixon, P.E.
F.H.W.A., **00-01 (if Federal)**
System Consultants Associates
McGraw Hill Construction Dodge
MS Procurement Technical Assistance Program
Associated General Contractors of Mississippi, Inc.
M.R.B.A.
Project File

OFFICE OF STATE AID ROAD CONSTRUCTION
MISSISSIPPI DEPARTMENT OF TRANSPORTATION
AND
AMITE COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Amite County, Mississippi at the Amite County Courthouse, Liberty, Mississippi, until on the day of , and shortly thereafter publicly opened for the construction of 0.241 miles of BRIDGE, BOX CULVERT AND APPROACHES on the KAHNVILLE ROAD being known as Project No. LSBP-03(23) in Amite County, Mississippi.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

ITEM	QUANTITY	UNIT
<u>ROADWAY ITEMS:</u>		
MOBILIZATION	LUMP SUM	LS
CLEARING AND GRUBBING	LUMP SUM	LS
REMOVAL OF BRIDGE STA. 9+99	1.000	UN
REMOVAL OF PIPE (ALL SIZES)	40.000	LF
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	6,650.000	CY
STRUCTURE EXCAVATION	423.000	CY
TEMPORARY STREAM DIVERSION	1.000	EA
GRANULAR MATERIAL (LVM), (CLASS 5, GROUP B)	2,945.000	CY
SIZE (II) STABILIZER AGGREGATE, COARSE	35.000	CY
ASPHALT FOR PRIME COAT (EA-1 OR (AE-P)	1,062.000	GAL
EMULSIFIED ASPHALT, GRADE CRS-2P	2,276.000	GAL
COARSE AGGREGATE COVER MATERIAL, SIZE 56, (CRUSHED STONE)	59.000	CY
SEAL AGGREGATE COVER MATERIAL, SIZE 7, (CRUSHED STONE)	32.000	CY
BLOTTER MATERIAL	4.000	CY
CLASS "B" STRUCTURAL CONCRETE	156.110	CY
REINFORCING STEEL	30,441.000	LB
24" REINFORCED CONCRETE PIPE, CLASS III	32.000	LF
GUARD RAIL, W-BEAM	225.000	LF
GUARD RAIL, BRIDGE END SECTION, TYPE "I" THRIE BEAM	4.000	EA
GUARD RAIL, TERMINAL END SECTION (NON-FLARED)	4.000	EA
RIGHT-OF-WAY MARKERS (TYPE II)	14.000	EA
MAINTENANCE OF TRAFFIC	LUMP SUM	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE COLD PLASTIC EDGE STRIPE	0.046	MI

SECTION 900
PROJECT NO. LSBP-03(23)
AMITE COUNTY

(CONTINUOUS WHITE)		
4" WIDE COLD PLASTIC TRAFFIC STRIPE (SKIP YELLOW)	0.023	MI
4" WIDE COLD PLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW)	122.000	LF
4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 MIL)	0.436	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (SKIP YELLOW) (90 MIL)	0.218	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 MIL)	1,153.000	LF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA

EROSION ITEMS:

AGRICULTURAL LIMESTONE	4.880	TON
COMMERCIAL FERTILIZER (13-13-13)	0.730	TON
SEEDING	2.440	AC
VEGETATIVE MATERIALS FOR MULCH	7.320	TON
SOLID SODDING	42.200	SY
EXCELSIOR BLANKET	533.000	SY
EROSION MAT	238.000	SY
PORTLAND CEMENT CONCRETE	3.860	CY
PAVED DITCH		
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	2,280.000	LF
WATTLES 20"	150.000	LF
LOOSE RIPRAP, 100 LB.	20.000	TON
LOOSE RIPRAP, 300 LB.	208.000	TON
GEOTEXTILE UNDER RIPRAP, (TYPE V), (NON-WOVEN) (AOS < 0.43)	386.000	SY

BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14" PRESTRESSED CONCRETE PILING	1,710.000	LF
18" PRE-FORMED PILE HOLES	810.000	LF
BRIDGE CONCRETE, CLASS "A"	153.460	CY
31' PRESTRESSED CONCRETE BEAM TYPE I+2	307.500	LF
60' PRESTRESSED CONCRETE BEAM TYPE III	298.750	LF
REINFORCEMENT	26,111.000	LB
CONCRETE RAILING	244.000	LF
LOOSE RIPRAP, 300 LB.	260.000	TON
GEOTEXTILE UNDER RIPRAP,	538.000	SY

SECTION 900
PROJECT NO. LSBP-03(23)
AMITE COUNTY

(TYPE V), (NON-WOVEN)
(AOS < 0.43)

NOTICE TO CONTRACTORS:

CONTRACT TIME: 120 Working Days

BASIS OF AWARD

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Amite County, the LSBP Engineer's office and the Office of the State Aid Engineer, 412 E. Woodrow Wilson Avenue, Jackson, Mississippi. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from David Cothren, LSBP Engineer for Amite County, Mississippi, 4097 Robinson Road, Liberty. The Cost is one hundred dollars (\$100.00) for plans and one hundred dollars (\$100.00) for the proposal, non-refundable

Certified check or bid bond for five percent (5%) of the total bid, made payable to Amite County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Jackie Whittington, President
Amite County Board of Supervisors