



OSARC

OFFICE OF
STATE AID ROAD CONSTRUCTION

Harry Lee James, P.E.

State Aid Engineer

P.O. Box 1850

412 E. Woodrow Wilson Ave.

Jackson, Mississippi 39216

Fax (601) 379-7141

April 1, 2021

Board of Supervisors
Copiah County
c/o Chancery Clerk
Hazlehurst, MS 39083

Gentlemen:

RE: **LOCAL SYSTEM BRIDGE PROGRAM**
PROJECT NO. LSBP-15(18)
COPIAH COUNTY

The Plans and specifications for the above numbered project have been reviewed and are herewith approved. You are, therefore, authorized to advertise this project for bids. The work to be done under this project consists of **Bridge Replacement**.

The date for opening these bids has been set for **Monday, May 10, 2021 at 10:00 a.m.** in the **Boardroom at Hazlehurst**.

In accordance with the Provisions of Section 31-7-13, Mississippi Code of 1972 as amended by House Bills numbered 901 and 1306 of the 1991 regular Legislative Session, the advertisement for receipt of bids on this project must be made once each week for two (2) consecutive weeks in a regular newspaper published in your county and, further, that the date as published for the bid opening shall not be less than fifteen (15) working days after the last published notice. The date, as set above, should be no sooner than the sixteenth working day after the last advertisement appears in the newspaper.

We are returning herewith an approved copy of the Plans and Proposal Documents to be filed by your Clerk when advertisement is begun.

Sincerely,

Harry Lee James, P. E.
State Aid Engineer

Evelyn Hollins

By: Evelyn Hollins
Administrative Assistant

pc: Ron McMaster, P.E., Co. Eng./Project Eng.
Supervisor District(s) 3
Ed Holland, P.E.
F.H.W.A., **00-01 (if Federal)**
System Consultants Associates
McGraw Hill Construction Dodge
MS Procurement Technical Assistance Program
Associated General Contractors of Mississippi, Inc.
M.R.B.A.
Project File

**OFFICE OF STATE AID ROAD CONSTRUCTION
MISSISSIPPI DEPARTMENT OF TRANSPORTATION
BOARD OF SUPERVISORS OF COPIAH COUNTY**

**SECTION 900
NOTICE TO CONTRACTORS**

Bidders shall submit their bids either in a sealed envelope or electronically. Electronic bids will be received at www.copiahcountybids.org and shall include a copy of their Certificate of Responsibility as an attachment to the electronic bid. Sealed bids and electronic bids will be received by the Board of Supervisors of Copiah County in Hazlehurst, Mississippi, until 10:00 O'Clock A.M., February 10, 2021, and shortly thereafter publicly opened for the construction of 0.179 miles of Bridge and Approaches on and John I. Hay Road in Copiah County, also known as Local System Bridge Project No. LSBP-15(18).
Entire Project - 60 Working Days

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS

ITEM	QUANTITY	UNIT
<u>ROADWAY ITEMS:</u>		
Mobilization	Lump Sum	L.S.
Clearing and Grubbing	Lump Sum	L.S.
Removal of Bridge at Sta. 14+00.00	1	UNIT
Removal of Pipe (All Sizes)	45.0	L.F.
Unclassified Excavation (F.M.)	1,943.0	C.Y.
Borrow Excavation (F.M.E.) (Contractor Furnished) (Class 9)	1,454.0	C.Y.
Granular Material (LVM) (Class 4, Group "B")	760.0	C.Y.
Right-of-Way Markers (Type II)	23.0	Each
Maintenance of Traffic	Lump Sum	L.S.
Additional Construction Signs	0.0	S.F.
Reflectorized Traffic Object Marker (Encapsulated Lens) (Type 3)	4.0	Each
<u>EROSION CONTROL ITEMS:</u>		
Agricultural Limestone	4.20	Ton
Commercial Fertilizer (13-13-13)	2.10	Ton
Seeding	2.10	Acre
Vegetative Materials for Mulch	6.30	Ton
Solid Sodding	200.0	S.Y.
Temporary Silt Fence (Type I) (AOS 0.15-0.84)	2,025.0	L.F.
Wattles, 20"	415.0	L.F.
Loose Riprap, 300 LB.	332.0	Ton
Geotextile Under Riprap, Type V, AOS 0.21-0.43	615.0	S.Y.
<u>BRIDGE ITEMS:</u>		
Test Pile	2	Each
Conventional Static Pile Load Test	0	Each
14" Prestressed Concrete Piling	800.0	L.F.
18" Pre-Formed Pile Hole	400.0	L.F.
31' Precast Concrete Slab Unit, 3.5' Interior	18.0	Each
40' Precast Concrete Slab Unit, 3.5' Interior	6.0	Each
31' Precast Concrete Slab Unit, 3.5' Exterior	6.0	Each
40' Precast Concrete Slab Unit, 3.5' Exterior	2.0	Each
Precast Concrete Barrier Rail	266.0	L.F.
31' Precast Concrete Cap, Intermediate Unit, Concrete Pile	1.0	Each
31.33' Precast Concrete Cap, Intermediate Unit, Concrete Pile	2.0	Each
31' Precast Concrete Cap, End Unit, Concrete Pile	2.0	Each
9.25' Precast Concrete Wing	4.0	Each
Loose Riprap, 300 LB.	298.0	Ton
Geotextile Under Riprap, Type V, AOS 0.21-0.43	552.0	S.Y.

BASIS OF AWARD: The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The attention of the BIDDER is directed to the State and Federal laws governing selection of and employment of labor.

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into, pursuant to this advertisement, minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

Total Contract Time as Advertised: 60 working Days

Plans and Specifications are on file in the Office of the Chancery Clerk, Copiah County, Hazlehurst, Mississippi, and in the Office of the State Aid Engineer, 412 Woodrow Wilson Avenue, Jackson, Mississippi. Paper and electronic copies of the plans and proposals may be ordered at www.copiahcountybids.org

Certified check or bid bond for five percent (5%) of the total bid, made payable to Copiah County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letter qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid, and such proposals will not be considered in making the award.

Publish dates:

Terry Channell, President
COPIAH COUNTY BOARD
OF SUPERVISORS