

**OFFICE OF  
STATE AID ROAD CONSTRUCTION**

P.O. BOX 1850  
JACKSON, MISSISSIPPI 39215-1850

**Harry Lee James, P.E.**  
State Aid Engineer  
Telephone (601)359-7150  
www.msstateaidroads.us

412 Woodrow Wilson Avenue  
Jackson, Mississippi 39216  
Fax (601)359-7141  
mail@osarc.ms.gov

September 17, 2018

Board of Supervisors  
Coahoma County  
c/o Chancery Clerk  
Clarksdale, MS 38614

Gentlemen:

**RE: STATE AID PROJECT  
PROJECT NO. SAP-14(80)  
COAHOMA COUNTY**

The Plans and specifications for the above numbered project have been reviewed and are herewith approved. You are, therefore, authorized to advertise this project for bids. The work to be done under this project consists of **Replace 2 Bridges with Box Culvert and Box Bridge.**

The date for opening these bids has been set for **Friday, October 26, 2018 at 10:00 a.m.** in the **Courthouse at Clarksdale.**

In accordance with the Provisions of Section 31-7-13, Mississippi Code of 1972 as amended by House Bills numbered 901 and 1306 of the 1991 regular Legislative Session, the advertisement for receipt of bids on this project must be made once each week for two (2) consecutive weeks in a regular newspaper published in your county and, further, that the date as published for the bid opening shall not be less than fifteen (15) working days after the last published notice. The date, as set above, should be no sooner than the sixteenth working day after the last advertisement appears in the newspaper.

We are returning herewith an approved copy of the Plans and Proposal Documents to be filed by your Clerk when advertisement is begun.

Sincerely,

Harry Lee James, P. E.  
State Aid Engineer

*Evelyn Hollins*

By: Evelyn Hollins  
Administrative Assistant

pc: Kenneth L. Weiland, P.E., Co. Eng./Project Eng.  
Supervisor District(s) 2  
Stephen Johnson, P.E.  
F.H.W.A. , 00-01 (*if Federal*)  
System Consultants Associates  
McGraw Hill Construction Dodge  
**MS Procurement Technical Assistance Program**  
Associated General Contractors of Mississippi, Inc.  
M.R.B.A.  
Project File



OFFICE OF STATE AID ROAD CONSTRUCTION  
MISSISSIPPI DEPARTMENT OF TRANSPORTATION  
AND  
COAHOMA COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Coahoma County, Mississippi at the Coahoma County Courthouse, Clarksdale, Mississippi, until on the            day of            ,            and shortly thereafter publicly opened for the construction of 0.128 miles of REPLACE BRIDGES WITH ONE BOX CULVERT AND ONE BOX BRIDGE. on the HIGHWAY 316 being known as Project No. SAP-14(80) in Coahoma County, Mississippi.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

| ITEM                               | QUANTITY   | UNIT |
|------------------------------------|------------|------|
| <u>ROADWAY ITEMS:</u>              |            |      |
| MOBILIZATION                       | LUMP SUM   | LS   |
| CLEARING AND GRUBBING              | LUMP SUM   | LS   |
| REMOVAL OF BRIDGE (STA. 316+32.30) | 1.000      | UN   |
| REMOVAL OF BRIDGE (STA. 372+50.25) | 1.000      | UN   |
| REMOVAL OF PIPE                    | 80.000     | LF   |
| UNCLASSIFIED EXCAVATION (FM)       | 2,808.000  | CY   |
| BORROW EXCAVATION (F.M.E.)         | 1,765.000  | CY   |
| (CONTRACTOR FURNISHED) (CLASS 9 )  |            |      |
| GRANULAR MATERIAL (LVM),           | 225.000    | CY   |
| (CLASS 3, GROUP B)                 |            |      |
| HOT MIX ASPHALT, (ST) (9.5MM)      | 317.000    | TON  |
| HOT MIX ASPHALT, ST, 19MM          | 103.000    | TON  |
| HOT MIX ASPHALT (ST) (9.5MM),      | 82.000     | TON  |
| LEVELING                           |            |      |
| HOT MIX ASPHALT, (ST) (19 MM),     | 31.000     | TON  |
| TRENCH WIDENING (BASE COURSE)      |            |      |
| CLASS B STRUCTURAL CONCRETE        | 139.800    | CY   |
| REINFORCING STEEL                  | 28,769.000 | LB   |
| 48" REINFORCED CONCRETE PIPE,      | 48.000     | LF   |
| CLASS III                          |            |      |
| 54" REINFORCED CONCRETE PIPE,      | 144.000    | LF   |
| CLASS III                          |            |      |
| 48" REINFORCED CONCRETE PIPE,      | 2.000      | EA   |
| END SECTION                        |            |      |
| 54" REINFORCED CONCRETE PIPE,      | 2.000      | EA   |
| END SECTION                        |            |      |
| RIGHT-OF-WAY MARKERS (TYPE I)      | 21.000     | EA   |
| MAINTENANCE OF TRAFFIC             | LUMP SUM   | LS   |
| ADDITIONAL CONSTRUCTION SIGNS      | 0.000      | SF   |
| 4" WIDE THERMOPLASTIC EDGE STRIPE  | 0.261      | MI   |
| (CONTINUOUS WHITE) (60MIL)         |            |      |
| 4" WIDE THERMOPLASTIC TRAFFIC      | 0.130      | MI   |

SECTION 900  
PROJECT NO. SAP-14(80)  
COAHOMA COUNTY

---

|                                    |            |     |
|------------------------------------|------------|-----|
| STRIPE (SKIP YELLOW) (90MIL)       | 60.000     | LF  |
| THERMOPLASTIC LEGEND               |            |     |
| (WHITE) (120 MIL)                  | 16.000     | EA  |
| TWO-WAY YELLOW REFLECTIVE HIGH     |            |     |
| PERFORMANCE RAISED MARKERS         | 2.000      | EA  |
| REFLECTORIZED TRAFFIC REGULATORY   |            |     |
| SIGN (ENCAPSULATED LENS)           | 3.000      | EA  |
| REFLECTORIZED TRAFFIC WARNING      |            |     |
| SIGN (ENCAPSULATED LENS)           | 2.000      | EA  |
| TEMPORARY STREAM DIVERSION         |            |     |
| <br><u>EROSION CONTROL ITEMS:</u>  |            |     |
| COMMERCIAL FERTILIZER ( 13-13-13 ) | 3.000      | TON |
| SEEDING                            | 3.000      | AC  |
| VEGETATIVE MATERIALS FOR MULCH     | 6.000      | TON |
| TEMPORARY SILT FENCE               | 150.000    | LF  |
| (TYPE I) (AOS 0.15-0.84)           |            |     |
| LOOSE RIPRAP, 300 LB.              | 253.400    | TON |
| WATTLES, 20 INCH                   | 450.000    | LF  |
| <br><u>BOX BRIDGE ITEMS:</u>       |            |     |
| BRIDGE CONCRETE, CLASS "BB"        | 161.630    | CY  |
| REINFORCEMENT                      | 33,334.000 | LB  |

NOTICE TO CONTRACTORS:

CONTRACT TIME: 60 Working Days

BASIS OF AWARD

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Coahoma County, the County Engineer's office and the Office of the State Aid Engineer, 412 E. Woodrow Wilson Avenue, Jackson, Mississippi. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Kenneth L. Weiland, County Engineer for Coahoma County, Mississippi, 337 Delta Avenue, Clarksdale. The Cost is seventy-five dollars (\$75.00) for plans and seventy-five dollars (\$75.00) for the proposal, non-refundable

Certified check or bid bond for five percent (5%) of the total bid, made payable to Coahoma County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Paul Pearson, President  
Coahoma County Board of Supervisors