



**OSARC**  
OFFICE OF  
STATE AID ROAD CONSTRUCTION



Harry Lee James, P.E.

State Aid Engineer

P.O. Box 1850

412 E. Woodrow Wilson Ave.

Jackson, Mississippi 39216

Fax (601) 379-7141

May 4, 2021

Board of Supervisors  
Franklin County  
c/o Chancery Clerk  
Meadville, MS 39653

Gentlemen:

RE: **EASTERN FEDERAL LAND  
PROJECT NO. EFL-0019(13)B  
FRANKLIN COUNTY**

The Plans and specifications for the above numbered project have been reviewed and are herewith approved. You are, therefore, authorized to advertise this project for bids. The work to be done under this project consists of **Bridge Replacement**.

The date for opening these bids has been set for **Friday, May 28, 2021 at 10:00 a.m.** in the **Boardroom at Meadville**.

In accordance with the Provisions of Section 31-7-13, Mississippi Code of 1972 as amended by House Bills numbered 901 and 1306 of the 1991 regular Legislative Session, the advertisement for receipt of bids on this project must be made once each week for two (2) consecutive weeks in a regular newspaper published in your county and, further, that the date as published for the bid opening shall not be less than fifteen (15) working days after the last published notice. The date, as set above, should be no sooner than the sixteenth working day after the last advertisement appears in the newspaper.

We are returning herewith an approved copy of the Plans and Proposal Documents to be filed by your Clerk when advertisement is begun.

Sincerely,

Harry Lee James, P. E.  
State Aid Engineer

*Evelyn Hollins*

By: Evelyn Hollins  
Administrative Assistant

pc: Mike McKenzie, P.E., Co. Eng./Project Eng.  
Supervisor District(s) 5  
Chris Dixon, P.E.  
F.H.W.A., 00-01 (if Federal)  
System Consultants Associates  
McGraw Hill Construction Dodge  
**MS Procurement Technical Assistance Program**  
Associated General Contractors of Mississippi, Inc.  
M.R.B.A.  
Project File

OFFICE OF STATE AID ROAD CONSTRUCTION  
MISSISSIPPI DEPARTMENT OF TRANSPORTATION  
AND  
FRANKLIN COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Franklin County, Mississippi at the Franklin County Courthouse, Meadville, Mississippi, until on the            day of            ,            and shortly thereafter publicly opened for the construction of 0.212 miles of BRIDGE REPLACEMENT on the MIDDLETON CREEK ROAD being known as Project No. EFL-0019(13)B in Franklin County, Mississippi.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

| ITEM  | QUANTITY  | UNIT |
|---|-----------|------|
| <u>ROADWAY ITEMS:</u>   |           |      |
| MOBILIZATION  | LUMP SUM  | LS   |
| CLEARING AND GRUBBING   | LUMP SUM  | LS   |
| REMOVAL OF BRIDGE AT STA. 15+88.05                                  | 1.000     | UN   |
| REMOVAL OF PAVEMENT (ALL TYPES)<br>(ALL DEPTHS)                     | 1,693.000 | SY   |
| REMOVAL OF PIPE (ALL SIZES)   | 62.000    | LF   |
| UNCLASSIFIED EXCAVATION (FM)  | 1,035.000 | CY   |
| BORROW EXCAVATION (AH) (F.M.E.)<br>(CONTRACTOR FURNISHED) (CLASS 9) | 548.000   | CY   |
| GRANULAR MATERIAL (LVM)<br>(CLASS 4, GROUP E)                       | 1,379.000 | CY   |
| HOT MIX ASPHALT, (ST) ( 9.5 mm)                                     | 197.000   | TON  |
| HOT MIX ASPHALT, (ST) (19 mm)                                       | 622.000   | TON  |
| ASPHALT FOR PRIME COAT<br>(EA-1)                                    | 838.000   | GAL  |
| 18" REINFORCED CONCRETE PIPE,<br>CLASS III                          | 80.000    | LF   |
| 24" REINFORCED CONCRETE PIPE,<br>CLASS III                          | 40.000    | LF   |
| 24" REINFORCED CONCRETE PIPE,<br>END SECTION                        | 2.000     | EA   |
| RIGHT-OF-WAY MARKERS (TYPE I)                                       | 21.000    | EA   |
| RIGHT-OF-WAY MARKERS (TYPE II)                                      | 3.000     | EA   |
| MAINTENANCE OF TRAFFIC  | LUMP SUM  | LS   |
| ADDITIONAL CONSTRUCTION SIGNS                                       | 0.000     | SF   |
| 4" WIDE COLD PLASTIC EDGE STRIPE<br>(CONTINUOUS WHITE)              | 0.031     | MI   |
| 4" WIDE COLD PLASTIC TRAFFIC<br>STRIPE (CONTINUOUS YELLOW)          | 162.000   | LF   |
| 4" WIDE THERMOPLASTIC EDGE STRIPE<br>(CONTINUOUS WHITE) (60 MILS)   | 0.395     | MI   |
| 4" WIDE THERMOPLASTIC TRAFFIC<br>STRIPE (CONTINUOUS YELLOW)         | 2,088.000 | LF   |

SECTION 900  
PROJECT NO. EFL-0019(13)B  
FRANKLIN COUNTY

---

(90 MILS)

|  |        |    |
|--|--------|----|
| TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS        | 28.000 | EA |
| REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3) | 4.000  | EA |

EROSION CONTROL ITEMS:

|  |           |     |
|--|-----------|-----|
| AGRICULTURAL LIMESTONE                                 | 4.300     | TON |
| COMMERCIAL FERTILIZER (13:13:13)                       | 0.650     | TON |
| AMMONIUM NITRATE                                       | 0.220     | TON |
| SEEDING  | 2.150     | AC  |
| VEGETATIVE MATERIALS FOR MULCH                         | 4.300     | TON |
| EXCELSIOR BLANKET                                      | 200.000   | SY  |
| TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)         | 3,100.000 | LF  |
| LOOSE RIPRAP, 100 LB.                                  | 120.000   | TON |
| LOOSE RIPRAP, 200 LB.                                  | 300.000   | TON |
| GEOTEXTILE UNDER LOOSE RIP RAP (TYPE V, AOS 0.21-0.43) | 318.000   | SY  |
| TEMPORARY GRASSING                                     | 2.150     | AC  |
| WATTLES, 12"   | 1,800.000 | LF  |
| WATTLES, 20"   | 1,200.000 | LF  |

BRIDGE ITEMS:

|   |         |     |
|---|---------|-----|
| TEST PILE   | 2.000   | EA  |
| CONVENTIONAL STATIC PILE LOAD TEST  | 0.000   | EA  |
| 14" PRESTRESSED CONCRETE PILING   | 590.000 | LF  |
| 19' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR, 30 DEG SKEW, LEFT FWD              | 6.000   | EA  |
| 31' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR, 30 DEG SKEW, LEFT FWD              | 12.000  | EA  |
| 19' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR, 30 DEG SKEW, LEFT FWD              | 2.000   | EA  |
| 31' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR, 30 DEG SKEW, LEFT FWD              | 4.000   | EA  |
| PRECAST CONCRETE BARRIER RAIL   | 162.000 | LF  |
| 36' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE 30 DEG SKEW, LEFT FWD. | 2.000   | EA  |
| 36' PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE, 30 DEG SKEW, LEFT FWD.         | 2.000   | EA  |
| 11.33' PRECAST CONCRETE WING  | 4.000   | EA  |
| LOOSE RIPRAP, 300 LB.   | 260.000 | TON |

SECTION 900  
PROJECT NO. EFL-0019(13)B  
FRANKLIN COUNTY

---

GEOTEXTILE UNDER LOOSE RIP RAP  
TYPE V, AOS 0.21-0.43)

540.000

SY

NOTICE TO CONTRACTORS:

CONTRACT TIME: 90 Working Days

BASIS OF AWARD

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The attention of the BIDDER is directed to the State and Federal laws governing selection of and employment of labor.

MINIMUM WAGE RATES for this project have been predetermined by the Secretary of the the Department of Labor in accordance with the requirements of Federal regulations governing the expenditure of FEDERAL AID HIGHWAY FUNDS and are set out in the labor regulations contained in the proposal.

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Franklin County, the County Engineer's office and the Office of the State Aid Engineer, 412 E. Woodrow Wilson Avenue, Jackson, Mississippi. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Mike McKenzie, County Engineer for Franklin County, Mississippi, P. O. Box 318, Clinton. The Cost is seventy five dollars (\$75.00) for plans and seventy five dollars (\$75.00) for the proposal, non-refundable

Certified check or bid bond for five percent (5%) of the total bid, made payable to Franklin County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Jerry Lynn Howell, President  
Franklin County Board of Supervisors