



# OSARC

OFFICE OF  
STATE AID ROAD CONSTRUCTION

Harry Lee James, P.E.

State Aid Engineer

P.O. Box 1850

412 E. Woodrow Wilson Ave.

Jackson, Mississippi 39216

Fax (601) 339-7141

September 13, 2022

Board of Supervisors  
Greene County  
c/o Chancery Clerk  
Leakesville, MS 39451

Gentlemen:

RE: **STATE AID PROJECT**  
**PROJECT NO. SAP-21(82)**  
**GREENE COUNTY**

The Plans and specifications for the above numbered project have been reviewed and are herewith approved. You are, therefore, authorized to advertise this project for bids. The work to be done under this project consists of **Bridge & Approaches**.

The date for opening these bids has been set for **Tuesday, November 1, 2022 at 10:00 a.m.** in the **Boardroom at Leakesville**.

In accordance with the Provisions of Section 31-7-13, Mississippi Code of 1972 as amended by House Bills numbered 901 and 1306 of the 1991 regular Legislative Session, the advertisement for receipt of bids on this project must be made once each week for two (2) consecutive weeks in a regular newspaper published in your county and, further, that the date as published for the bid opening shall not be less than fifteen (15) working days after the last published notice. The date, as set above, should be no sooner than the sixteenth working day after the last advertisement appears in the newspaper.

We are returning herewith an approved copy of the Plans and Proposal Documents to be filed by your Clerk when advertisement is begun.

Sincerely,

Harry Lee James, P. E.  
State Aid Engineer

*Evelyn Hollins*

By: Evelyn Hollins  
Administrative Assistant

pc: Jason Lamb, P.E., Co. Eng./Project Eng.  
Supervisor District(s) 1,4,5  
Jonathan Dixon, P.E.  
F.H.W.A. , 00-01 (if Federal)  
System Consultants Associates  
McGraw Hill Construction Dodge  
**MS Procurement Technical Assistance Program**  
Associated General Contractors of Mississippi, Inc.  
M.R.B.A.  
Project File

OFFICE OF STATE AID ROAD CONSTRUCTION  
MISSISSIPPI DEPARTMENT OF TRANSPORTATION  
AND  
GREENE COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Greene County, Mississippi at the Greene County Courthouse, Leakesville, Mississippi, until on the            day of            ,            and shortly thereafter publicly opened for the construction of 0.632 miles of BRIDGE AND APPROACHES on the SITES "A" THRU "C" being known as Project No. SAP-21(82) in Greene County, Mississippi.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

ITEM	QUANTITY	UNIT
<u>ROADWAY ITEMS:</u>		
MOBILIZATION	LUMP SUM	LS
CLEARING AND GRUBBING	0.100	AC
REMOVAL OF BRIDGE AT STATION 460+82.50	1.000	UN
REMOVAL OF BRIDGE AT STATION 648+54.48	1.000	UN
REMOVAL OF BRIDGE AT STATION 113+07	1.000	UN
REMOVAL OF PIPE (ALL SIZES)	148.000	LF
UNCLASSIFIED EXCAVATION (FM)	255.000	CY
CHANNEL EXCAVATION (FM)	1,490.000	CY
EXCESS EXCAVATION (FM)	240.000	CY
GRANULAR MATERIAL (LVM), (CLASS 9, GROUP B)	450.000	CY
CRUSHED STONE	340.000	TON
HOT MIX ASPHALT, ST 9.5MM	679.000	TON
HOT MIX ASPHALT, ST 9.5MM, LEVELING	280.000	TON
COLD MILLING OF BITUMINOUS PAVEMENT, ALL DEPTHS	600.000	SY
ULTRA THIN ASPHALT PAVEMENT, UHMA, LEVELING	278.000	TON
CLASS B STRUCTURAL CONCRETE, MINOR STRUCTURES	1.816	CY
24" REINFORCED CONCRETE PIPE, CLASS III	152.000	LF
24" REINFORCED CONCRETE PIPE, END SECTION	12.000	EA
GUARD RAIL, W-BEAM	300.000	LF
GUARD RAIL, BRIDGE END SECTION, TYPE I THRIE-BEAM	12.000	EA
GUARD RAIL, TERMINAL END SECTION, NON-FLARED	12.000	EA
ROADWAY CONSTRUCTION SURVEYING	LUMP SUM	LS

SECTION 900  
PROJECT NO. SAP-21(82)  
GREENE COUNTY

---

MAINTENANCE OF TRAFFIC	LUMP SUM	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIPE	1.269	MI
(CONTINUOUS WHITE) (60 MILS)		
4" WIDE THERMOPLASTIC TRAFFIC	0.426	MI
STRIPE (SKIP YELLOW) (90 MILS)		
4" WIDE THERMOPLASTIC TRAFFIC	3,300.000	LF
STRIPE (CONTINUOUS YELLOW)		
(90 MILS)		
TWO-WAY YELLOW REFLECTIVE HIGH	60.000	EA
PERFORMANCE RAISED MARKERS		
REFLECTORIZED TRAFFIC OBJECT MARKER	12.000	EA
(ENCAPSULATED LENS) (TYPE 3)		
GEOTEXTILE UNDER BRIDGE ABUTMENT	300.000	SY
NON-WOVEN, TYPE V, AOS < 0.43		

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	2.400	TON
COMMERCIAL FERTILIZER (13-13-13)	1.200	TON
AMMONIUM NITRATE	0.120	TON
SEEDING	1.200	AC
VEGETATIVE MATERIALS FOR MULCH	2.400	TON
SOLID SODDING	200.000	SY
TEMPORARY SILT FENCE	1,200.000	LF
(TYPE II) (AOS 0.15-0.84)		
WATTLES, 20"	180.000	LF
REMOVE AND RESET RIPRAP	150.000	CY
LOOSE RIPRAP, 200 LB.	300.000	TON
GEOTEXTILE UNDER RIPRAP NON-WOVEN,	600.000	SY
TYPE V, AOS < 0.43		

BRIDGE ITEMS:

SITE "A" BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14" PRESTRESSED CONCRETE PILING	730.000	LF
18" PRE-FORMED PILE HOLE	140.000	LF
19' PRECAST CONCRETE SLAB UNIT,	6.000	EA
3'-6" INTERIOR		
31' PRECAST CONCRETE SLAB UNIT,	12.000	EA
3'-6" INTERIOR		
19' PRECAST CONCRETE SLAB UNIT,	2.000	EA
3'-6" EXTERIOR		
31' PRECAST CONCRETE SLAB UNIT,	4.000	EA
3'-6" EXTERIOR		
PRECAST CONCRETE BARRIER RAIL	162.000	LF

SECTION 900  
PROJECT NO. SAP-21(82)  
GREENE COUNTY

---

31' PRECAST CONCRETE CAP,	2.000	EA
INTERMEDIATE UNIT, CONCRETE PILE		
31' PRECAST CONCRETE CAP,	2.000	EA
END UNIT, CONCRETE PILE		
9.25' PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP, 300 LB.	109.000	TON
GEOTEXTILE UNDER RIPRAP NON-WOVEN,	281.000	SY
TYPE V, AOS < 0.43		

SITE "B" BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14" PRESTRESSED CONCRETE PILING	660.000	LF
18" PRE-FORMED PILE HOLE	140.000	LF
31' PRECAST CONCRETE SLAB UNIT,	18.000	EA
3'-6" INTERIOR		
31' PRECAST CONCRETE SLAB UNIT,	6.000	EA
3'-6" EXTERIOR		
PRECAST CONCRETE BARRIER RAIL	186.000	LF
31' PRECAST CONCRETE CAP,	2.000	EA
INTERMEDIATE UNIT, CONCRETE PILE		
31' PRECAST CONCRETE CAP,	2.000	EA
END UNIT, CONCRETE PILE		
9.25' PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP, 300 LB.	308.000	TON
GEOTEXTILE UNDER RIPRAP NON-WOVEN,	900.000	SY
TYPE V, AOS < 0.43		

SITE "C" BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14" STEEL PILING	1,120.000	LF
18" PRE-FORMED PILE HOLE	180.000	LF
BRIDGE CONCRETE, CLASS "B"	23.750	CY
REINFORCEMENT	924.000	LB
40' PRECAST CONCRETE SLAB UNIT,	18.000	EA
3'-6" INTERIOR		
40' PRECAST CONCRETE SLAB UNIT,	6.000	EA
3'-6" EXTERIOR		
PRECAST CONCRETE BARRIER RAIL	240.000	LF
31'-2" PRECAST CONCRETE CAP,	2.000	EA
INTERMEDIATE UNIT, STEEL PILE		
31'-2" PRECAST CONCRETE CAP,	2.000	EA
END UNIT, STEEL PILE		
9.17' PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP, 300 LB.	505.000	TON
GEOTEXTILE UNDER RIPRAP,	1,544.000	SY
TYPE V, AOS < 0.43		

SECTION 900  
PROJECT NO. SAP-21(82)  
GREENE COUNTY

---

PROJECT NO. SAP-21(82)  
GREENE COUNTY

NOTICE TO CONTRACTORS:

CONTRACT TIME: 125 Working Days

BASIS OF AWARD

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Greene County, the County Engineer's office and the Office of the State Aid Engineer, 412 E. Woodrow Wilson Avenue, Jackson, Mississippi. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Donald E. Walker, County Engineer for Greene County, Mississippi, P. O. Box 16496, Hattiesburg. The Cost is fifty dollars (\$50.00) for plans and fifty dollars (\$50.00) for the proposal, non-refundable

Certified check or bid bond for five percent (5%) of the total bid, made payable to Greene County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Wayburn "danny" Smith, President  
Greene County Board of Supervisors