



OSARC
OFFICE OF
STATE AID ROAD CONSTRUCTION



RECEIVED
2-21-2020

Harry Lee James, P.E.

State Aid Engineer

P.O. Box 1850

412 E. Woodrow Wilson Ave.

Jackson, Mississippi 39216

Fax (601) 373-7141

February 18, 2020

Board of Supervisors
Itawamba County
c/o Chancery Clerk
Fulton, MS 38843

Gentlemen:

RE: **SURFACE TRANSPORTATION PROGRAM/FEDERAL AID BRIDGE REPLACEMENT**
PROJECT NO. STP/BR-0029(33)BO
ITAWAMBA COUNTY

The Plans and specifications for the above numbered project have been reviewed and are herewith approved. You are, therefore, authorized to advertise this project for bids. The work to be done under this project consists of **Box Bridge and Approaches**.

The date for opening these bids has been set for **Tuesday, March 17, 2020 at 10:00 a.m.** in the **Boardroom at Fulton**.

In accordance with the Provisions of Section 31-7-13, Mississippi Code of 1972 as amended by House Bills numbered 901 and 1306 of the 1991 regular Legislative Session, the advertisement for receipt of bids on this project must be made once each week for two (2) consecutive weeks in a regular newspaper published in your county and, further, that the date as published for the bid opening shall not be less than fifteen (15) working days after the last published notice. The date, as set above, should be no sooner than the sixteenth working day after the last advertisement appears in the newspaper.

We are returning herewith an approved copy of the Plans and Proposal Documents to be filed by your Clerk when advertisement is begun.

Sincerely,

Harry Lee James, P. E.
State Aid Engineer

Evelyn Hollins

By: Evelyn Hollins
Administrative Assistant

pc: Carrson Neal, P.E., Co. Eng./Project Eng.
Supervisor District(s) 5
Jerry Gilliland, P.E.
F.H.W.A., 00-01 (if Federal)
System Consultants Associates
McGraw Hill Construction Dodge
MS Procurement Technical Assistance Program
Associated General Contractors of Mississippi, Inc.
M.R.B.A.
Project File

OFFICE OF STATE AID ROAD CONSTRUCTION
MISSISSIPPI DEPARTMENT OF TRANSPORTATION
AND
ITAWAMBA COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed or electronic bids will be received by the Board of Supervisors of Itawamba County, Mississippi until on the day of and shortly thereafter publicly opened for the construction of 0.302 miles of BOX BRIDGE AND APPROACHES TO REPLACE BRIDGE NO. 59 AND BRIDGE NO. 60 on LAKE ITAWAMBA ROAD being known as Project No. STP-0029-00(033)/107063-701000 in Itawamba County, Mississippi. Sealed bids will be received until the designated date and time at the Itawamba County Courthouse, 201 West Main Street, Fulton, Mississippi or electronic bids will be received until the designated date and time via electronic online bid submission through www.cceplanroom.com.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

ITEM	QUANTITY	UNIT
MOBILIZATION	LUMP SUM	LS
CLEARING AND GRUBBING	LUMP SUM	LS
REMOVAL OF EXISTING BRIDGE @ STA. 129+46	1.000	UN
REMOVAL OF EXISTING BRIDGE @ STA. 137+33	1.000	UN
REMOVE AND RELAY RIPRAP	833.000	SY
UNCLASSIFIED EXCAVATION (FM)	5,424.000	CY
BORROW EXCAVATION (F.M.E.)	13,899.000	CY
(CONTRACTOR FURNISHED) (CLASS 9)		
GEOTEXTILE FABRIC STABILIZATION	6,509.000	SY
(TYPE V) (AOS <0.43)		
TEMPORARY STREAM DIVERSION	2.000	EA
GRANULAR MATERIAL (LVM), (CLASS 5, GROUP C)	228.000	CY
CRUSHED STONE SIZE 3/4" & DOWN, (FM)	1,643.000	CY
MIXING, SHAPING AND COMPACTION	4,264.000	SY
HOT MIX ASPHALT, (ST) (9.5 MM)	645.000	TON
ASPHALT FOR PRIME COAT (EA-1) or (AE-P)	1,492.000	GAL
CLASS B STRUCTURAL CONCRETE, MINOR STRUCTURES	0.540	CY
36" REINFORCED CONCRETE PIPE, CLASS III	72.000	LF
48" REINFORCED CONCRETE PIPE, CLASS III	64.000	LF
36" REINFORCED CONCRETE PIPE, END SECTION	2.000	EA
48" REINFORCED CONCRETE PIPE, END SECTION	2.000	EA
24" CORRUGATED POLYETHYLENE PIPE	40.000	LF
RIGHT-OF-WAY MARKERS (TYPE II)	27.000	EA
MAINTENANCE OF TRAFFIC	LUMP SUM	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIPE	0.606	MI
(CONTINUOUS WHITE) (60 MIL)		
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 MIL)	3,200.000	LF
TWO-WAY YELLOW REFLECTIVE HIGH	32.000	EA
PERFORMANCE RAISED MARKERS		
REFLECTORIZED TRAFFIC WARNING SIGN (ENCAPSULATED LENS)	10.000	EA
REFLECTORIZED TRAFFIC WARNING SIGN WITH SUPP. PLATE (ENCAPSULATED LENS)	4.000	EA

SECTION 900
PROJECT NO. STP-0029-00(033)/107063-701000
ITAWAMBA COUNTY

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	6.500	TON
COMMERCIAL FERTILIZER (13-13-13)	3.250	TON
AMMONIUM NITRATE	0.820	TON
SEEDING	3.250	AC
VEGETATIVE MATERIALS FOR MULCH	6.000	TON
SOLID SODDING	337.000	SY
EXCELSIOR BLANKET	2,183.000	SY
TEMPORARY SILT FENCE (TYPE I OR II) (AOS 0.15-0.84)	1,600.000	LF
WATTLES, 20"	480.000	LF
LOOSE RIPRAP, 200 LB.	300.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS <0.43	1,093.000	SY

BOX BRIDGE ITEMS:

STA.129+42.79 DOUBLE 16'X8' BOX BRIDGE REQ'D, 34.43'ALONG CENTERLINE, 3:1 WINGS, 10'COVER
ITEMS:

BOX BRIDGE CONCRETE, CLASS "BB"	303.890	CY
REINFORCEMENT	48,779.000	LB

STA. 137+39.71 DOUBLE 20'X 12' BOX BRIDGE REQ'D, 42.58' ALONG CENTERLINE, 3:1 WINGS, 5'
COVER ITEMS:

BOX BRIDGE CONCRETE, CLASS "BB"	384.850	CY
REINFORCEMENT	71,366.000	LB

NOTICE TO CONTRACTORS:

CONTRACT TIME: 140 Working Days

BASIS OF AWARD

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The attention of the BIDDER is directed to the State and Federal laws governing selection of and employment of labor.

MINIMUM WAGE RATES for this project have been predetermined by the Secretary of the Department of Labor in accordance with the requirements of Federal regulations governing the expenditure of FEDERAL AID HIGHWAY FUNDS and are set out in the labor regulations contained in the proposal.

The Board of Supervisors hereby notifies all bidders that it will affirmatively ensure that in any contract entered into pursuant to this advertisement, minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Itawamba County, the County Engineer's office and the Office of the State Aid Engineer, 412 E. Woodrow Wilson Avenue, Jackson, Mississippi. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Carrson Neal, County Engineer for Itawamba County, Mississippi, at www.cceplanroom.com. The Cost is fifty dollars (\$50.00) for plans and fifty dollars (\$50.00) for the proposal, non-refundable. PLANS AND PROPOSALS may also be downloaded electronically for an additional \$25 fee by Bidders for electronic bidding purposes only. Questions regarding electronic bidding shall be directed to Plan House Printing (662)407-0193.

Certified check or bid bond for five percent (5%) of the total bid, made payable to Itawamba County and the State of Mississippi must accompany each proposal. For bidders submitting bids electronically, the bond submitted must be either a bond issued by the Surety in electronic format or the original hard copy of the bid bond must be submitted to the Itawamba County Board of Supervisors, 201 W. Main Street, Fulton, MS prior to the bid opening in order for the bid to be valid.

The entire PROPOSAL is required to be turned in for both paper and electronic bid submission.

Bids will be accepted only under the name of the Bidder to whom PLANS AND PROPOSALS have been issued by the County Engineer, and whose name appears on the official list of Planholders maintained by the County Engineer.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Ike Johnson, President
Itawamba County Board of Supervisors