



Harry Lee James, P.E.  
State Aid Engineer  
P.O. Box 1850

412 E. Woodrow Wilson Ave.  
Jackson, Mississippi 39216  
Fax (601) 379-7141

June 3, 2020

Board of Supervisors  
Jones County  
c/o Chancery Clerk  
Laurel, MS 39440

Gentlemen:

RE: **STATE AID PROJECT**  
**PROJECT NO. SAP-34(77)**  
**JONES COUNTY**

The Plans and specifications for the above numbered project have been reviewed and are herewith approved. You are, therefore, authorized to advertise this project for bids. The work to be done under this project consists of **Precast Concrete Span Structures 3@40' with approaches to include HMA Paving, Guardrail, Thermoplastic Striping and Signage.**

The date for opening these bids has been set for **Thursday, July 9, 2020 at 10:00 a.m.** in the **Boardroom at Laurel.**

In accordance with the Provisions of Section 31-7-13, Mississippi Code of 1972 as amended by House Bills numbered 901 and 1306 of the 1991 regular Legislative Session, the advertisement for receipt of bids on this project must be made once each week for two (2) consecutive weeks in a regular newspaper published in your county and, further, that the date as published for the bid opening shall not be less than fifteen (15) working days after the last published notice. The date, as set above, should be no sooner than the sixteenth working day after the last advertisement appears in the newspaper.

We are returning herewith an approved copy of the Plans and Proposal Documents to be filed by your Clerk when advertisement is begun.

Sincerely,

Harry Lee James, P. E.  
State Aid Engineer

By: Evelyn Hollins  
Administrative Assistant

pc: Lawrence R. Clark, P.E., Co. Eng./Project Eng.  
Supervisor District(s) 1  
Butch Swales, P.E.  
F.H.W.A., 00-01 (if Federal)  
System Consultants Associates  
McGraw Hill Construction Dodge  
**MS Procurement Technical Assistance Program**  
Associated General Contractors of Mississippi, Inc.  
M.R.B.A.  
Project File

**OFFICE OF STATE AID ROAD CONSTRUCTION  
MISSISSIPPI DEPARTMENT OF TRANSPORTATION  
BOARD OF SUPERVISORS OF JONES COUNTY**

SECTION 900  
NOTICE TO CONTRACTORS

Sealed bids will be received by the Board of Supervisors of Jones County in Laurel, Mississippi until \_\_\_\_\_ A.M. on \_\_\_\_\_, 2017 and shortly thereafter publicly opened for the construction of: Two Each Precast Concrete Span Structures 3@ 40' with Approaches to include HMA Paving, Guardrail, Thermoplastic Striping and Signage project on 0.220 miles of road described as Shady Grove-Sharon-Moss Road in Jones County, Mississippi, also known as State Aid Project No. SAP-34(77).

Principal Items of Work are Approximately as Follows:

**Roadway Items**

Mobilization	L.S.	L.S.
Clearing and Grubbing	L.S.	L.S.
Removal of Bridge at Sta. 392 + 55 & Sta. 394 + 54	2.0	Unit
Unclassified Excavation (F.M.)	740.0	Cu. Yd.
Borrow Excavation (F.M.E.)	4,629.0	Cu. Yd.
(Contractor Furnished) (Class 9)		
Granular Material (L.V.M.) (Class 6, Grp. "B")	1,321.0	Cu. Yd.
Crushed Stone	665.0	Ton
Hot Mix Asphalt, ST, 9.5mm	311.0	Ton
Hot Mix Asphalt, ST, 19mm	505.0	Ton
Guard Rail, "W" Beam	387.0	L.F.
Guard Rail, Bridge End Section, Type "I", Thrie Beam	8.0	Each
Guard Rail, Terminal End Section	4.0	Each
Right- of-Way Markers (Type II)	8.0	Each
Maintenance of Traffic	L.S.	L.S.
Additional Construction Signs	0.0	Sq. Ft.
4" Wide Cold Plastic Edge Stripe	0.091	Mile
(Continuous White)		
4" Wide Cold Plastic Traffic Stripe	480.0	L.F.
(Continuous Yellow)		
4" Wide Thermoplastic Edge Stripe	0.350	Mile
(Continuous White) (60 Mils)		
4" Wide Thermoplastic Traffic Stripe	1,850.0	L.F.
(Continuous Yellow) (90 Mils)		
Two-Way Yellow Reflective High Performance Raised Markers	20.0	Each
Reflectorized Traffic Object Marker	8.0	Each
(Encapsulated Lens) (Type 3)		
Reflectorized Traffic Delineator Sign	36.0	Each
(Encapsulated Lens)		

**RECEIVED**

**AUG 04 2017**

**OSARC 1047 21**

Section 900  
 Notice to Contractors  
 Project No. SAP- (34)77  
 Jones County, MS

**Erosion Control Items**

Agricultural Limestone	3.56	Ton
Commercial Fertilizer (13:13:13)	1.78	Ton
Ammonium Nitrate	0.18	Ton
Seeding	1.78	Acre
Vegetative Materials for Mulch	3.56	Ton
Solid Sodding	200.0	Sq. Yd.
Portland Cement Conc. Paved Ditch	9.51	Cu. Yd.
Temporary Silt Fence (Type II) (AOS 0.15-0.84)	2,550.0	L.F.
Loose Riprap (300 Lb.)	77.0	Ton
Geotextile Under Riprap (Type V) (A.O.S. 0.21-0.43)	180.0	Sq. Yd.
Sediment Control Stone	80.0	Ton
Wattles, 20"	400.0	Each

**Bridge Items – Structure "A"**

Drilled Shaft, 24" Diameter	560.0	L.F.
Exploration	50.0	L.F.
Temporary Casing, 24" Diameter	50.0	L.F.
Permanent Casing, 24" Diameter	60.0	L.F.
Bridge Concrete, Class "AA"	38.96	Cu. Yd.
Reinforcement	5,140.0	Lbs.
40' Precast Concrete Slab Unit, 3.5' Interior	18.0	Each
40' Precast Concrete Slab Unit 3.5 Exterior	6.0	Each
Precast Concrete Barrier Rail	240.0	L.F.
9.17' Precast Concrete Wing	4.0	Each
Loose Riprap, 300 Lb.	185.0	Ton
Geotextile Under Riprap (Type V) (AOS 0.21-0.43)	343.0	Sq. Yd.

**Bridge Items – Structure "B"**

Drilled Shaft, 24" Diameter	560.0	L.F.
Trial Shaft, 24" Diameter	70.0	L.F.
Exploration	50.0	L.F.
Temporary Casing, 24" Diameter	50.0	L.F.
Permanent Casing, 24" Diameter	60.0	L.F.
Bridge Concrete, Class "AA"	38.96	Cu. Yd.
Reinforcement	5,140.0	Lbs.
40' Precast Concrete Slab Unit, 3.5' Interior	18.0	Each
40' Precast Concrete Slab Unit, 3.5' Exterior	6.0	Each

Section 900  
Notice to Contractors  
Project No. SAP-34(77)  
Jones County, MS

**Bridge Items – Structure “B” (Continued)**

Precast Concrete Barrier Rail	240.0	L.F.
9.17' Precast Concrete Wing	4.0	Each
Loose Riprap, 300 Lb.	186.0	Ton
Geotextile Under Riprap (Type V) (AOS 0.21-0.43)	344.0	Sq. Yd.

Contract Time: 100 Working Days

---

**BASIS OF AWARD:** The award, if made, will be made to the lowest qualified bidder on the basis of the published quantities.

Total Contract Time as Advertised: 100 Working Days

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that, in any contract entered into pursuant to this advertisement, minority business enterprises will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color or national origin in consideration for an award.

Plans and specifications are on file in the office of the Chancery Clerk of Jones County, Laurel, Mississippi, and in the Office of the State Aid Engineer, located at 412 Woodrow Wilson Avenue, Jackson, Mississippi. Plans and proposals may be secured from Lawrence R. Clark, LSBP Engineer for Jones County, located at 714 Hillcrest Drive, Laurel, Mississippi, upon payment of \$40.00 for the plans and \$40.00 for the proposals, neither of which is refundable.

Certified Check or Bid Bond for five percent (5%) of total bid payable to Jones County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letter qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid, and such proposals will not be considered in making the award.

Jerome Wyatt, President  
Board of Supervisors  
Jones County  
State of Mississippi