

**OFFICE OF
STATE AID ROAD CONSTRUCTION**

P.O. BOX 1850
JACKSON, MISSISSIPPI 39215-1850

Harry Lee James, P.E.
State Aid Engineer
Telephone (601)359-7150
www.msstateaidroads.us

412 Woodrow Wilson Avenue
Jackson, Mississippi 39216
Fax (601)359-7141
mail@osarc.ms.gov

October 3, 2018

Board of Supervisors
Jefferson Davis County
c/o Chancery Clerk
Prentiss, MS 39474

Gentlemen:

RE: **STATE AID PROJECT
PROJECT NO. SAP-33(48)
JEFFERSON DAVIS COUNTY**

The Plans and specifications for the above numbered project have been reviewed and are herewith approved. You are, therefore, authorized to advertise this project for bids. The work to be done under this project consists of **Bridge Replacement**.

The date for opening these bids has been set for **Thursday, November 15, 2018 at 10:00 a.m.** in the **Boardroom at Prentiss**.

In accordance with the Provisions of Section 31-7-13, Mississippi Code of 1972 as amended by House Bills numbered 901 and 1306 of the 1991 regular Legislative Session, the advertisement for receipt of bids on this project must be made once each week for two (2) consecutive weeks in a regular newspaper published in your county and, further, that the date as published for the bid opening shall not be less than fifteen (15) working days after the last published notice. The date, as set above, should be no sooner than the sixteenth working day after the last advertisement appears in the newspaper.

We are returning herewith an approved copy of the Plans and Proposal Documents to be filed by your Clerk when advertisement is begun.

Sincerely,

Harry Lee James, P. E.
State Aid Engineer

Evelyn Hollins

By: Evelyn Hollins
Administrative Assistant

pc: H. Les Dungan, P.E., Co. Eng./Project Eng.
Supervisor District(s) 1
Chris Dixon, P.E.
F.H.W.A. , **00-01 (if Federal)**
System Consultants Associates
McGraw Hill Construction Dodge
MS Procurement Technical Assistance Program
Associated General Contractors of Mississippi, Inc.
M.R.B.A.
Project File



OFFICE OF STATE AID ROAD CONSTRUCTION
MISSISSIPPI DEPARTMENT OF TRANSPORTATION
AND
JEFFERSON DAVIS COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Jefferson Davis County, Mississippi at the Jefferson Davis County Administrative Building, Prentiss, Mississippi, until on the day of , and shortly thereafter publicly opened for the construction of 0.188 miles of BRIDGE REPLACEMENT on the EAST ST. STEPHENS ROAD being known as Project No. SAP-33(48) in Jefferson Davis County, Mississippi.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

ITEM	QUANTITY	UNIT
<u>ROADWAY ITEMS:</u>		
MOBILIZATION	LUMP SUM	LS
CLEARING AND GRUBBING	LUMP SUM	LS
REMOVAL OF BRIDGE AT STATION 35+60	1.000	UN
REMOVAL OF PIPE (ALL SIZES)	30.000	LF
UNCLASSIFIED EXCAVATION (FM)	875.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 7)	310.000	CY
CHANNEL EXCAVATION (FM)	745.000	CY
STRUCTURE EXCAVATION	50.000	CY
GRANULAR MATERIAL (LVM), (CLASS 6, GROUP B)	1,495.000	CY
CRUSHED STONE SIZE 610, (LVM)	50.000	CY
SIZE II STABILIZER AGGREGATE, COARSE	25.000	CY
HOT MIX ASPHALT, ST 9.5 MM	239.000	TON
HOT MIX ASPHALT, ST 19 MM	433.000	TON
ASPHALT FOR PRIME COAT (EA-1)	787.000	GAL
22" X 13" REINFORCED CONCRETE ARCH PIPE, CLASS III	48.000	LF
29" X 18" REINFORCED CONCRETE ARCH PIPE, CLASS III	32.000	LF
GUARD RAIL, W-BEAM	50.000	LF
GUARD RAIL, BRIDGE END SECTION, TYPE I THRIE-BEAM	4.000	EA
GUARD RAIL, TERMINAL END SECTION	4.000	EA
RIGHT-OF-WAY MARKERS (TYPE I)	16.000	EA
MAINTENANCE OF TRAFFIC	LUMP SUM	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 MILS)	0.317	MI

SECTION 900
PROJECT NO. SAP-33(48)
JEFFERSON DAVIS COUNTY

4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 MILS)	1,951.000	LF
THERMOPLASTIC DETAIL STRIPE (4" EQUIVALENT LENGTH) (WHITE) (60 MILS)	224.000	LF
THERMOPLASTIC LEGEND (WHITE) (120 MILS)	24.000	SF
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	19.000	EA
REFLECTORIZED TRAFFIC WARNING SIGN (ENCAPSULATED LENS)	2.000	EA
REFLECTORIZED TRAFFIC REGULATORY SIGN (ENCAPSULATED LENS)	1.000	EA
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	3.000	TON
COMMERCIAL FERTILIZER (13-13-13)	1.500	TON
AMMONIUM NITRATE	0.150	TON
SEEDING	1.500	AC
VEGETATIVE MATERIALS FOR MULCH	3.000	TON
SOLID SODDING	200.000	SY
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	1,885.000	LF
WATTLES, 20"	220.000	LF
LOOSE RIPRAP, 200 LB.	100.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.21-0.43	185.000	SY

BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14" PRESTRESSED CONCRETE PILING	950.000	LF
18" PRE-FORMED PILE HOLE	220.000	LF
19' PRECAST CONCRETE SLAB UNIT, 3'-6" INTERIOR, 30 DEG SKEW, RT. FWD.	6.000	EA
31' PRECAST CONCRETE SLAB UNIT, 3'-6" INTERIOR, 30 DEG SKEW, RT. FWD.	24.000	EA
19' PRECAST CONCRETE SLAB UNIT, 3'-6' EXTERIOR, 30 DEG SKEW, RT. FWD.	2.000	EA
31' PRECAST CONCRETE SLAB UNIT, 3'-6" EXTERIOR, 30 DEG SKEW, RT. FWD.	8.000	EA

SECTION 900
PROJECT NO. SAP-33(48)
JEFFERSON DAVIS COUNTY

PRECAST CONCRETE BARRIER RAIL ✓	286.000 ✓	LF ✓
36' PRECAST CONCRETE CAP,	4.000 ✓	EA ✓
INTERMEDIATE UNIT, CONCRETE PILE,		
30 DEG SKEW, RT. FWD. ✓		
36' PRECAST CONCRETE CAP,	2.000 ✓	EA ✓
END UNIT, CONCRETE PILE,		
30 DEG SKEW, RT. FWD. ✓		
11.33' PRECAST CONCRETE WING ✓	4.000 ✓	EA ✓
LOOSE RIPRAP, 300 LB. ✓	78.000 ✓	TON ✓
GEOTEXTILE UNDER RIPRAP,	209.000 ✓	SY ✓
TYPE V, AOS 0.21-0.43 ✓		

PROJECT NO. SAP-33(48)
JEFFERSON DAVIS COUNTY

NOTICE TO CONTRACTORS:

CONTRACT TIME: 80 Working Days

BASIS OF AWARD

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Jefferson Davis County, the County Engineer's office and the Office of the State Aid Engineer, 412 E. Woodrow Wilson Avenue, Jackson, Mississippi. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from H. Les Dungan, III, County Engineer for Jefferson Davis County, Mississippi, 1574 Highway 98 East, Columbia. The Cost is fifty dollars (\$50.00) for plans and fifty dollars (\$50.00) for the proposal, non-refundable

Certified check or bid bond for five percent (5%) of the total bid, made payable to Jefferson Davis County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Macon Corky Holliman, President
Jefferson Davis County Board of Supervisors