



**OSARC**  
OFFICE OF  
STATE AID ROAD CONSTRUCTION



Harry Lee James, P.E.  
State Aid Engineer  
P.O. Box 1850

412 E Woodrow Wilson Ave  
Jackson, Mississippi 39216  
Fax (601) 359-7141

May 2, 2022

Board of Supervisors  
Lamar County  
c/o Chancery Clerk  
Purvis, MS 39475

Gentlemen:

RE: **DEPARTMENT OF ECONOMIC COMMUNITY DEVELOPMENT**  
**PROJECT NO. DECD-0037(24)B**  
**LAMAR COUNTY**

The Plans and specifications for the above numbered project have been reviewed and are herewith approved. You are, therefore, authorized to advertise this project for bids. The work to be done under this project consists of **Grade, Drain, Base, Pave, and Signalization**.

The date for opening these bids has been set for **Tuesday, June 21, 2022 at 10:00 a.m.** in the **Boardroom at Purvis**.

In accordance with the Provisions of Section 31-7-13, Mississippi Code of 1972 as amended by House Bills numbered 901 and 1306 of the 1991 regular Legislative Session, the advertisement for receipt of bids on this project must be made once each week for two (2) consecutive weeks in a regular newspaper published in your county and, further, that the date as published for the bid opening shall not be less than fifteen (15) working days after the last published notice. The date, as set above, should be no sooner than the sixteenth working day after the last advertisement appears in the newspaper.

We are returning herewith an approved copy of the Plans and Proposal Documents to be filed by your Clerk when advertisement is begun.

Sincerely,

Harry Lee James, P. E.  
State Aid Engineer

*Evelyn Hollins*

By: Evelyn Hollins  
Administrative Assistant

pc: Donald E. Walker, P.E., Co. Eng./Project Eng.  
Supervisor District(s) 1,3,&4  
Jonathan Dixon, P.E.  
F.H.W.A., 00-01 (if Federal)  
System Consultants Associates  
McGraw Hill Construction Dodge  
**MS Procurement Technical Assistance Program**  
Associated General Contractors of Mississippi, Inc.  
M.R.B.A.  
Project File

OFFICE OF STATE AID ROAD CONSTRUCTION  
MISSISSIPPI DEPARTMENT OF TRANSPORTATION  
AND  
LAMAR COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Lamar County, Mississippi at the Lamar County Courthouse, Purvis, Mississippi, until 0:00 am on the 1st day of January, 2022 and shortly thereafter publicly opened for the construction of 0.986 miles of GRADE, DRAIN, BASE, PAVE, AND SIGNALIZATION on the HEGWOOD ROAD AND LINCOLN ROAD (PHASE 1) being known as Project No. DECD-0037(24)B in Lamar County, Mississippi.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

ITEM	QUANTITY	UNIT
<u>ROADWAY ITEMS:</u>		
MOBILIZATION	LUMP SUM	LS
CLEARING AND GRUBBING	LUMP SUM	LS
REMOVAL OF OBSTRUCTIONS	LUMP SUM	LS
REMOVAL OF SIGN INCLUDING POST & FOOTING (ALL TYPES AND SIZES)	22.000	UN
REMOVAL OF CONCRETE COMBINATION CURB AND GUTTER	480.000	LF
REMOVAL OF ASPHALT DRIVEWAYS, ALL DEPTHS	1,947.000	SY
REMOVAL OF ASPHALT PAVEMENT, ALL DEPTHS	2,050.000	SY
REMOVAL OF CONCRETE DRIVEWAYS, ALL DEPTHS	759.000	SY
REMOVAL OF PIPE (ALL SIZES)	781.000	LF
UNCLASSIFIED EXCAVATION (FM)	3,840.000	CY
MUCK EXCAVATION (FM)	1,600.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9-8)	5,380.000	CY
EXCESS EXCAVATION (FM)	22.000	CY
STRUCTURE EXCAVATION	160.000	CY
CRUSHED STONE	6,591.000	TON
HOT MIX ASPHALT, (ST) ( 9.5MM)	2,075.000	TON
HOT MIX ASPHALT, (ST) (12.5MM)	3,456.000	TON
HOT MIX ASPHALT, (ST) (19MM)	2,778.000	TON
COLD MILLING OF BITUMINOUS PAVEMENT, ALL DEPTHS	1,368.000	SY
CLASS "B" STRUCTURAL CONCRETE, MINOR STRUCTURES	126.000	CY
CLASS "C" STRUCTURAL CONCRETE, MINOR STRUCTURES	7.000	CY
REINFORCING STEEL	11,434.000	LB
18" REINFORCED CONCRETE PIPE,	854.000	LF

SECTION 900  
PROJECT NO. DECD-0037(24)B  
LAMAR COUNTY

---

CLASS III		
24" REINFORCED CONCRETE PIPE,	60.000	LF
CLASS III		
54" REINFORCED CONCRETE PIPE,	96.000	LF
CLASS III		
18" REINFORCED CONCRETE PIPE,	7.000	EA
END SECTION		
24" REINFORCED CONCRETE PIPE,	1.000	EA
END SECTION		
54" REINFORCED CONCRETE PIPE,	2.000	EA
END SECTION		
15" CORRUGATED POLYETHYLENE	13.000	LF
PIPE		
18" CORRUGATED POLYETHYLENE	2,942.000	LF
PIPE		
24" CORRUGATED POLYETHYLENE	193.000	LF
PIPE		
30" CORRUGATED POLYETHYLENE	150.000	LF
PIPE		
36" CORRUGATED POLYETHYLENE	426.000	LF
PIPE		
CASTINGS	2,054.000	LB
GRATINGS	288.000	LB
UNDERGROUND STORMWATER DETENTION	1.000	EA
SYSTEM		
CONCRETE DRIVEWAY	613.000	SY
CONCRETE DRIVEWAY	1,405.000	SY
COMBINATION CONCRETE	8,087.000	LF
CURB AND GUTTER, TYPE 1		
CONCRETE ISLAND PAVEMENT	379.000	SY
RIGHT-OF-WAY MARKERS (TYPE II)	66.000	EA
MAINTENANCE OF TRAFFIC	LUMP SUM	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC TRAFFIC	0.426	MI
STRIPE (CONTINUOUS WHITE) (90 MILS)		
4" WIDE THERMOPLASTIC EDGE STRIPE	1.336	MI
(CONTINUOUS WHITE) (60 MILS)		
4" WIDE THERMOPLASTIC TRAFFIC	1.055	MI
STRIPE (SKIP YELLOW) (90 MILS)		
4" WIDE THERMOPLASTIC TRAFFIC	9,262.000	LF
STRIPE (CONTINUOUS YELLOW)		
(90 MILS)		
THERMOPLASTIC LEGEND	1,412.000	LF
(WHITE) (120 MILS)		
THERMOPLASTIC LEGEND	1,685.000	SF
(WHITE) (120 MILS)		
THERMOPLASTIC DETAIL STRIPE,	4,400.000	LF
WHITE		
THERMOPLASTIC DETAIL STRIPE,	1,994.000	LF
YELLOW		

SECTION 900  
PROJECT NO. DECD-0037(24)B  
LAMAR COUNTY

RED-CLEAR REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	70.000	EA
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	256.000	EA
REFLECTORIZED TRAFFIC REGULATORY SIGN (ENCAPSULATED LENS)	26.000	EA

EROSION CONTROL ITEMS:

TOPSOIL FOR SLOPE TREATMENT (CONTRACTOR FURNISHED) (LVM)	400.000	CY
AGRICULTURAL LIMESTONE	6.400	TON
COMMERCIAL FERTILIZER (13-13-13)	3.200	TON
AMMONIUM NITRATE	0.300	TON
SEEDING	3.200	AC
VEGETATIVE MATERIALS FOR MULCH	6.400	TON
SOLID SODDING	90.000	SY
TEMPORARY GRASSING	3.200	AC
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	7,616.000	LF
WATTLES, 20"	432.000	LF
LOOSE RIPRAP, 300 LB.	125.000	TON

TRAFFIC SIGNAL ITEMS:

TRAFFIC SIGNAL HEAD, TYPE 1	8.000	EA
TRAFFIC SIGNAL HEAD, TYPE 2 FYA	4.000	EA
SOLID STATE TRAFFIC SIGNAL CABINET ASSEMBLY, TYPE III CABINET, TYPE 1 CONTROLLER	1.000	EA
MODIFY EXISTING TRAFFIC SIGNAL CABINET ASSEMBLY	1.000	EA
POWER SERVICE PEDASTAL	1.000	EA
TRAFFIC SIGNAL EQUIPMENT POLE, TYPE III(L), 30' SHAFT, 40' & 55' ARM	1.000	EA
TRAFFIC SIGNAL EQUIPMENT POLE, TYPE III(L), 30' SHAFT, 50' & 50' ARM	8.000	CY
POLE FOUNDATIONS, CLASS "B" CONCRETE	201.000	LF
ELECTRICAL CABLE, UNDERGROUND IN CONDUIT, IMSA 20-1, AWG #8, 3 CONDUCTOR	23.000	LF
ELECTRICAL CABLE, UNDERGROUND IN CONDUIT, IMSA 20-1, AWG #10, 2 CONDUCTOR	469.000	LF
ELECTRICAL CABLE, UNDERGROUND IN CONDUIT, IMSA 20-1, AWG #14, 8 CONDUCTOR	1.000	EA
PULLBOX ENCLOSURE, TYPE 2	1.000	EA
PULLBOX ENCLOSURE, TYPE 3		

SECTION 900  
PROJECT NO. DECD-0037(24)B  
LAMAR COUNTY

---

TRAFFIC SIGNAL CONDUIT, UNDERGROUND, TYPE 4, 2"	62.000	LF
TRAFFIC SIGNAL CONDUIT, UNDERGROUND, TYPE 4, 3"	27.000	LF
TRAFFIC SIGNAL CONDUIT, UNDERGROUND DRILLED OR JACKED, ROLLED PIPE, 3"	91.000	LF
TYPE 1 OPTICAL DETECTOR	4.000	EA
TYPE 1 OPTICAL DETECTOR CABLE	418.000	LF
MULTIMODE PHASE DETECTOR	1.000	EA
VIDEO VEHICLE DETECTION SENSOR TYPE 1A	4.000	EA
VIDEO VEHICLE DETECTION CABLE	418.000	LF
TRAFFIC SIGN	30.000	SF
STREET NAME SIGN	34.000	SF

NOTICE TO CONTRACTORS:

CONTRACT TIME: 210 Working Days

BASIS OF AWARD

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Lamar County, the County Engineer's office and the Office of the State Aid Engineer, 412 E. Woodrow Wilson Avenue, Jackson, Mississippi. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

Plans and specifications are being made available via paper or digital copy. Plan Holders are required to log-in or register for an account to view or order bid documents at [www.twaplanroom.com](http://www.twaplanroom.com). The Cost is fifty dollars (\$50.00) for plans and fifty dollars (\$50.00) for the proposal, non-refundable. For questions regarding website registration and online orders, please contact Plan House at 601-336-6378. For questions related to the contract documents, please contact The Walker Associates at 601-583-2127. No partial sets of drawings or bid documents will be issued.

All Proposals shall be submitted on Bid Forms provided with the specifications. Bids may be submitted in person, or for those interested, bids can be electronically submitted at [www.twaplanroom.com](http://www.twaplanroom.com) under the project page. No oral, telegraphic, telephonic, or e-mail proposals will be considered.

Certified check or bid bond for five percent (5%) of the total bid, made payable to Lamar County and the State of Mississippi must accompany each proposal.

Bids will be accepted only under the name of the Bidder to whom PLANS AND PROPOSALS have been issued by the County Engineer, and whose name appears on the official list of planholders maintained by the County Engineer.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Warren Byrd, President  
Lamar County Board of Supervisors

Published: