



**OSARC**  
OFFICE OF  
STATE AID ROAD CONSTRUCTION

**received**  
**8/15/2022**

Harry Lee James, P.E.  
State Aid Engineer  
P.O. Box 1850

412 E Woodrow Wilson Ave.  
Jackson, Mississippi 39216  
Fax (601) 389-7141

August 9, 2022

Board of Supervisors  
Leake County  
c/o Chancery Clerk  
Carthage, MS 39051

Gentlemen:

RE: **LOCAL SYSTEM BRIDGE PROGRAM**  
**PROJECT NO. LSBP-40(18)**  
**LEAKE COUNTY**

The Plans and specifications for the above numbered project have been reviewed and are herewith approved. You are, therefore, authorized to advertise this project for bids. The work to be done under this project consists of **Bridge and Approaches**.

The date for opening these bids has been set for **Monday, September 19, 2022 at 9:00 a.m.** in the **Courthouse at Carthage**.

In accordance with the Provisions of Section 31-7-13, Mississippi Code of 1972 as amended by House Bills numbered 901 and 1306 of the 1991 regular Legislative Session, the advertisement for receipt of bids on this project must be made once each week for two (2) consecutive weeks in a regular newspaper published in your county and, further, that the date as published for the bid opening shall not be less than fifteen (15) working days after the last published notice. The date, as set above, should be no sooner than the sixteenth working day after the last advertisement appears in the newspaper.

We are returning herewith an approved copy of the Plans and Proposal Documents to be filed by your Clerk when advertisement is begun.

Sincerely,

Harry Lee James, P. E.  
State Aid Engineer

*Evelyn Hollins*

By: Evelyn Hollins  
Administrative Assistant

pc: J. Christian Gardner, P.E., Co. Eng./Project Eng.  
Supervisor District(s) 1  
Lonnie Taylor, P.E.  
F.H.W.A., 00-01 (if Federal)  
System Consultants Associates  
McGraw Hill Construction Dodge  
**MS Procurement Technical Assistance Program**  
Associated General Contractors of Mississippi, Inc.  
M.R.B.A.  
Project File

OFFICE OF STATE AID ROAD CONSTRUCTION  
MISSISSIPPI DEPARTMENT OF TRANSPORTATION  
AND  
LEAKE COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Leake County, Mississippi at the Leake County Courthouse, Carthage, Mississippi, until on the            day of            ,            and shortly thereafter publicly opened for the construction of 0.094 miles of BRIDGE AND APPROACHES on the RICE CREEK ROAD being known as Project No. LSBP-40(18) in Leake County, Mississippi.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

| ITEM  | QUANTITY  | UNIT |
|---|-----------|------|
| <u>ROADWAY ITEMS:</u>   |           |      |
| MOBILIZATION  | LUMP SUM  | LS   |
| CLEARING AND GRUBBING   | LUMP SUM  | LS   |
| REMOVAL OF BRIDGE @ STA. 11+99                                      | 1.000     | UN   |
| REMOVAL OF EXISTING ASPHALT PAVEMENT (ALL DEPTHS)                   | 872.000   | SY   |
| UNCLASSIFIED EXCAVATION (FM)  | 719.000   | CY   |
| BORROW EXCAVATION (F.M.E.)<br>(CONTRACTOR FURNISHED) (CLASS 9)      | 607.000   | CY   |
| CRUSHED STONE   | 554.000   | TON  |
| 36" REINFORCED CONCRETE PIPE,<br>CLASS III                          | 80.000    | LF   |
| 36" REINFORCED CONCRETE PIPE,<br>END SECTION                        | 4.000     | EA   |
| ROADWAY CONSTRUCTION SURVEYING                                      | LUMP SUM  | LS   |
| RIGHT-OF-WAY MARKERS (TYPE I)                                       | 8.000     | EA   |
| MAINTENANCE OF TRAFFIC  | LUMP SUM  | LS   |
| ADDITIONAL CONSTRUCTION SIGNS                                       | 0.000     | SF   |
| REFLECTORIZED TRAFFIC OBJECT MARKER<br>(ENCAPSULATED LENS) (TYPE 3) | 4.000     | EA   |
| <u>EROSION CONTROL ITEMS:</u>                                       |           |      |
| AGRICULTURAL LIMESTONE  | 2.820     | TON  |
| COMMERCIAL FERTILIZER (13:13:13)                                    | 0.640     | TON  |
| AMMONIUM NITRATE  | 0.140     | TON  |
| SEEDING   | 2.130     | AC   |
| VEGETATIVE MATERIALS FOR MULCH                                      | 6.350     | TON  |
| EXCELSIOR BLANKET   | 300.000   | SY   |
| TEMPORARY SILT FENCE<br>(TYPE II) (AOS 0.15 - 0.84)                 | 300.000   | LF   |
| WATTLES, 20"  | 1,180.000 | LF   |
| LOOSE RIPRAP, 200 LB.   | 905.000   | TON  |
| GEOTEXTILE UNDER RIPRAP,  | 1,899.000 | SY   |

RECEIVED  
17021  
OSARC 1947

SECTION 900  
PROJECT NO. LSBP-40(18)  
LEAKE COUNTY

---

TYPE V, AOS 0.21 - 0.43

BRIDGE ITEMS:

|  | LUMP SUM | LS  |
|--|----------|-----|
| BRIDGE CONSTRUCTION SURVEYING                                    |          |     |
| TEST PILE  | 2.000    | EA  |
| CONVENTIONAL STATIC PILE LOAD TEST                               | 0.000    | EA  |
| 14" PRESTRESSED CONCRETE PILING                                  | 990.000  | LF  |
| 18" PRE-FORMED PILE HOLES  | 655.000  | LF  |
| 40' PRECAST CONCRETE SLAB UNIT,<br>3.5' INTERIOR                 | 18.000   | EA  |
| 40' PRECAST CONCRETE SLAB UNIT,<br>3.5' EXTERIOR                 | 6.000    | EA  |
| PRECAST CONCRETE BARRIER RAIL                                    | 240.000  | LF  |
| 31.17' PRECAST CONCRETE CAP,<br>INTERMEDIATE UNIT, CONCRETE PILE | 2.000    | EA  |
| 31.17' PRECAST CONCRETE CAP,<br>END UNIT, CONCRETE PILE          | 2.000    | EA  |
| 9.17' PRECAST CONCRETE WING                                      | 4.000    | EA  |
| LOOSE RIPRAP, 300 LB.  | 110.000  | TON |
| GEOTEXTILE UNDER RIPRAP,   | 230.000  | SY  |
| TYPE V, NON WOVEN, AOS 0.21 < 0.43                               |          |     |

NOTICE TO CONTRACTORS:

CONTRACT TIME: 90 Working Days

BASIS OF AWARD

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Leake County, the LSBP Engineer's office and the Office of the State Aid Engineer, 412 E. Woodrow Wilson Avenue, Jackson, Mississippi. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from J. Christian Gardner, LSBP Engineer for Leake County, Mississippi, P. O. Drawer A, Indianola. The Cost is fifty dollars (\$50.00) for plans and fifty dollars (\$50.00) for the proposal, non-refundable

Certified check or bid bond for five percent (5%) of the total bid, made payable to Leake County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Oliver Smith, President  
Leake County Board of Supervisors