



**OSARC**  
OFFICE OF  
STATE AID ROAD CONSTRUCTION

**received**  
8/25/2022

Harry Lee James, P.E.  
State Aid Engineer  
P.O. Box 1850

412 E. Woodrow Wilson Ave.  
Jackson, Mississippi 39216  
Fax (601) 379-7141

August 23, 2022

Board of Supervisors  
Prentiss County  
c/o Chancery Clerk  
Booneville, MS 38829

Gentlemen:

RE: **EASTERN FEDERAL LAND  
PROJECT NO. EFL-0059(43)B  
PRENTISS COUNTY**

The Plans and specifications for the above numbered project have been reviewed and are herewith approved. You are, therefore, authorized to advertise this project for bids. The work to be done under this project consists of **Grade, Drain, Base and DBST Pave.**

The date for opening these bids has been set for **Wednesday, October 19, 2022 at 10:00 a.m.** in the **Boardroom at Booneville.**

In accordance with the Provisions of Section 31-7-13, Mississippi Code of 1972 as amended by House Bills numbered 901 and 1306 of the 1991 regular Legislative Session, the advertisement for receipt of bids on this project must be made once each week for two (2) consecutive weeks in a regular newspaper published in your county and, further, that the date as published for the bid opening shall not be less than fifteen (15) working days after the last published notice. The date, as set above, should be no sooner than the sixteenth working day after the last advertisement appears in the newspaper.

We are returning herewith an approved copy of the Plans and Proposal Documents to be filed by your Clerk when advertisement is begun.

Sincerely,

Harry Lee James, P. E.  
State Aid Engineer

*Evelyn Hollins*

By: Evelyn Hollins  
Administrative Assistant

pc: Kenneth P. Geno, Jr., P.E., Co. Eng./Project Eng.  
Supervisor District(s) 4  
Jared Keen, P.E.  
F.H.W.A., 00-01 (if Federal)  
System Consultants Associates  
McGraw Hill Construction Dodge  
**MS Procurement Technical Assistance Program**  
Associated General Contractors of Mississippi, Inc.  
M.R.B.A.  
Project File

OFFICE OF STATE AID ROAD CONSTRUCTION  
MISSISSIPPI DEPARTMENT OF TRANSPORTATION  
AND  
PRENTISS COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed or electronic bids will be received by the Board of Supervisors of Prentiss County, Mississippi until \_\_\_\_\_ AM on the \_\_\_\_\_ day of \_\_\_\_\_, \_\_\_\_\_ and shortly thereafter publicly opened for the construction of 1.336 miles of GRADE, DRAIN, BASE AND SURFACING on the ROAD A- CR 3560 (BAYBERRY RD); ROAD B-CR 3485 (GIN BRANCH RD) being known as Project No.EFL-0059(43)B in Prentiss County, Mississippi. Sealed bids will be received until the designated date and time at the Prentiss County Chancery Building, 100 N Main Street, Booneville, Mississippi or electronic bids will be received until the designated date and time via electronic online bid submission through [www.cceplanroom.com](http://www.cceplanroom.com).

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

ITEM	QUANTITY	UNIT
<u>ROADWAY ITEMS:</u>		
MOBILIZATION	LUMP SUM	LS
CLEARING AND GRUBBING	LUMP SUM	LS
REMOVAL OF OBSTRUCTIONS	LUMP SUM	LS
UNCLASSIFIED EXCAVATION (FM)	5,678.000	CY
BORROW EXCAVATION (LVM) (CONTRACTOR FURNISHED, CLASS 9-6)	1,122.000	CY
GRANULAR MATERIAL (LVM), (CL.5, GP.C)	70.000	CY
GRANULAR MATERIAL (LVM), (CL.9, GP.B)	8,545.000	CY
CRUSHED STONE (SIZE 3/4" & DOWN), (LVM)	240.000	CY
PORTLAND CEMENT	6,224.000	CWT
SOIL-CEMENT-WATER MIXING (MULTIPLE PASS MIXERS)	18,392.000	SY
POLYMERIZED-EMULSIFIED ASPHALT, GRADE CRS-2P	14,821.000	GAL
COARSE AGGREGATE COVER MATERIAL, SIZE 6	324.000	CY
SEAL AGGREGATE COVER MATERIAL, SIZE 7	175.000	CY
BLOTTER MATERIAL	25.000	CY
CLASS "B" STRUCTURAL CONCRETE, MINOR STRUCTURES	0.948	CY
24" REINFORCED CONCRETE PIPE, CLASS III	40.000	LF
24" REINFORCED CONCRETE PIPE, END SECTION	2.000	EA
29" X 18" REINFORCED CONCRETE	72.000	LF
ARCH PIPE, CLASS III		
36" X 22" REINFORCED CONCRETE	40.000	LF
ARCH PIPE, CLASS III		
44" X 27" REINFORCED CONCRETE	32.000	LF
ARCH PIPE, CLASS III		
29" X 18" REINFORCED CONCRETE	4.000	EA
ARCH PIPE, END SECTION		
36" X 22" REINFORCED CONCRETE	2.000	EA
ARCH PIPE, END SECTION		

SECTION 900  
PROJECT NO. EFL-0059(43)B  
PRENTISS COUNTY

44" X 27" REINFORCED CONCRETE	2.000	EA
ARCH PIPE, END SECTION		
15" CORRUGATED POLYETHYLENE PIPE	480.000	LF
18" CORRUGATED POLYETHYLENE PIPE	190.000	LF
24" CORRUGATED POLYETHYLENE PIPE	30.000	LF
48" TYPE A WOVEN WIRE FENCE	710.000	LF
48" TYPE I, CLASS "C" CHAIN LINK FENCE	230.000	LF
BARBED WIRE FENCE (2 STRANDS, 12 1/2	710.000	LF
GAUGE GALVANIZED BARBED WIRE, BARBS		
14 GAUGE ROUND 4 POINT (5'O.C.)		
GATE, 20' SLIDING GATE	1.000	EA
LINE POSTS (7'-0", 1-1/2" GALVANIZED STEEL)	21.000	EA
LINE POSTS (7'-0", 2-1/2" GALVANIZED STEEL)	2.000	EA
LINE POSTS (8'-0" GALVANIZED STEEL	60.000	EA
RAIL STUDDED "T" SECTION)		
BRACE POSTS (8'-0" 4"X 6" TIMBER POST)	9.000	EA
BRACE POSTS (8'-0" 6"X 6" TIMBER POST)	15.000	EA
BRACE POSTS (10'-0", 1-1/4" GALVANIZED STEEL)	4.000	EA
GATE POSTS (7'-0", 3-1/2" GALVANIZED STEEL)	2.000	EA
CONCRETE ANCHORS	40.000	EA
RIGHT-OF-WAY MARKERS (TYPE II)	88.000	EA
MAINTENANCE OF TRAFFIC	LUMP SUM	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE TRAFFIC STRIPE (CONTINUOUS WHITE)	14,045.000	LF
4" WIDE TRAFFIC STRIPE (CONTINUOUS YELLOW)	14,064.000	LF
DETAIL TRAFFIC STRIPE	252.000	LF
REFLECTORIZED TRAFFIC WARNING SIGN	6.000	EA
(ENCAPSULATED LENS)		
REFLECTORIZED TRAFFIC REGULATORY	3.000	EA
SIGN (ENCAPSULATED LENS)		
REFLECTORIZED TRAFFIC WARNING SIGN	6.000	EA
WITH SUPP. PLATE (ENCAPSULATED LENS)		

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	11.000	TON
COMMERCIAL FERTILIZER (13-13-13)	5.500	TON
AMMONIUM NITRATE	1.400	TON
SEEDING	5.500	AC
VEGETATIVE MATERIALS FOR MULCH	11.000	TON
SOLID SODDING	1,393.000	SY
TEMPORARY SILT FENCE	5,000.000	LF
(TYPE I OR II) (AOS 0.15-0.84)		
WATTLES, 20"	700.000	LF
LOOSE RIPRAP, 200 LB.	70.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS <0.43	140.000	SY

SECTION 900  
PROJECT NO. EFL-0059(43)B  
PRENTISS COUNTY

WATERLINE & APPURTENANCES RELOC. ITEMS:

DIP FITTINGS, MJ COMPACT	72.000	LB
6" x 0.188" OPEN TRENCH STEEL	200.000	LF
ENCASEMENT FOR 2" PVC WATER LINE PIPE		
2" PVC WATER PIPE LINE, CLASS 200	300.000	LF
4" PVC WATER PIPE LINE, CLASS 200	460.000	LF
4" WET TAP (CUT PIPE)	2.000	EA
4" MACHINE TAP	2.000	EA
CONNECTION TO SMALL DIAMETER PIPE	12.000	EA
3/4" PVC WATER SERVICE LINE	30.000	LF
RESET METERS	1.000	EA
SERVICE LINE RECONNECTION TO	1.000	EA
EXISTING SERVICE LINE		
2-1/2" PVC WATER PIPE LINE, CLASS 200	420.000	LF
FLUSHING HYDRANT ARRANGEMENT	2.000	EA
LOCATING, EXCAVATION, & VERIFICATION	31.000	EA
OF EXISTING LINE LOCATION; ELEVATION & SIZE;		
RESTORATION OF EXCAVATED AREA		

**RECEIVED**

MAY 19 2022

OSARC 1947 35

NOTICE TO CONTRACTORS:

CONTRACT TIME: 150 Working Days

BASIS OF AWARD

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The attention of the BIDDER is directed to the State and Federal laws governing selection of and employment of labor.

MINIMUM WAGE RATES for this project have been predetermined by the Secretary of the Department of Labor in accordance with the requirements of Federal regulations governing the expenditure of FEDERAL AID HIGHWAY FUNDS and are set out in the labor regulations contained in the proposal.

The Board of Supervisors hereby notifies all bidders that it will affirmatively ensure that in any contract entered into pursuant to this advertisement, minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Prentiss County, the County Engineer's office and the Office of the State Aid Engineer, 412 E. Woodrow Wilson Avenue, Jackson, Mississippi. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Kenneth P. Geno, Jr., LSBP Engineer for Prentiss County, Mississippi, at [www.cceplanroom.com](http://www.cceplanroom.com). The Cost is fifty dollars (\$50.00) for plans and fifty dollars (\$50.00) for the proposal, non-refundable. PLANS AND PROPOSALS may also be downloaded electronically for an additional \$25 fee by Bidders for electronic bidding purposes only. Questions regarding electronic bidding shall be directed to Plan House Printing (662)407-0193.

Certified check or bid bond for five percent (5%) of the total bid, made payable to Prentiss County and the State of Mississippi must accompany each proposal. For bidders submitting bids electronically, the bond submitted must be either a bond issued by the Surety in electronic format or the original hard copy of the bid bond must be submitted to the Prentiss County Board of Supervisors, 100 N. Main Street, Booneville, MS 38829 prior to the bid opening in order for the bid to be valid.

**The entire PROPOSAL is required to be turned in for both paper and electronic bid submission.**

Bids will be accepted only under the name of the Bidder to whom PLANS AND PROPOSALS have been issued by the County Engineer, and whose name appears on the official list of Planholders maintained by the County Engineer.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Matt Murphy, President  
Prentiss County Board of Supervisors