



OSARC
OFFICE OF
STATE AID ROAD CONSTRUCTION



RECEIVED
9/14/2021

Harry Lee James, P.E.
State Aid Engineer
P.O. Box 1850

412 E. Woodrow Wilson Ave.
Jackson, Mississippi 39216
Fax (601) 359-7141

September 10, 2021

Board of Supervisors
Quitman County
c/o Chancery Clerk
Marks, MS 38646

NRICS
91366

Gentlemen:

RE: **STATE AID PROJECT**
PROJECT NO. SAP-60(42)
QUITMAN COUNTY

The Plans and specifications for the above numbered project have been reviewed and are herewith approved. You are, therefore, authorized to advertise this project for bids. The work to be done under this project consists of **Bridge Approaches**.

The date for opening these bids has been set for **Friday, October 15, 2021 at 10:00 a.m.** in the **Courthouse at Marks**.

In accordance with the Provisions of Section 31-7-13, Mississippi Code of 1972 as amended by House Bills numbered 901 and 1306 of the 1991 regular Legislative Session, the advertisement for receipt of bids on this project must be made once each week for two (2) consecutive weeks in a regular newspaper published in your county and, further, that the date as published for the bid opening shall not be less than fifteen (15) working days after the last published notice. The date, as set above, should be no sooner than the sixteenth working day after the last advertisement appears in the newspaper.

We are returning herewith an approved copy of the Plans and Proposal Documents to be filed by your Clerk when advertisement is begun.

Sincerely,

Harry Lee James, P. E.
State Aid Engineer

Evelyn Hollins

By: Evelyn Hollins
Administrative Assistant

pc: J. Wayne Morrison, P.E., Co. Eng./Project Eng.
Supervisor District(s) 3
Stephen Johnson, P.E.
F.H.W.A. , 00-01 (if Federal)
System Consultants Associates
McGraw Hill Construction Dodge
MS Procurement Technical Assistance Program
Associated General Contractors of Mississippi, Inc.
M.R.B.A.
Project File

OFFICE OF STATE AID ROAD CONSTRUCTION
MISSISSIPPI DEPARTMENT OF TRANSPORTATION
AND
QUITMAN COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Quitman County, Mississippi at the Quitman County Courthouse, Marks, Mississippi, until on the day of and shortly thereafter publicly opened for the construction of 0.104 miles of BRIDGE & APPROACHES on the HOOD ROAD being known as Project No. SAP-60(42) in Quitman County, Mississippi.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

ITEM	QUANTITY	UNIT
<u>ROADWAY ITEMS:</u>		
MOBILIZATION	LUMP SUM	LS
CLEARING AND GRUBBING	LUMP SUM	LS
REMOVAL OF BRIDGE @ STA 430 + 28	1.000	UN
UNCLASSIFIED EXCAVATION (FM)	100.000	CY
GRANULAR MATERIAL (LVM).	100.000	CY
(CLASS 4, GROUP B)		
HOT MIX ASPHALT, (ST) (12.5 MM)	301.000	TON
GUARD RAIL, W/B EAM	375.000	LF
GUARD RAIL, BRIDGE END SECTION,	4.000	EA
TYPE "I"		
GUARD RAIL, TERMINAL END SECTION	4.000	EA
RIGHT-OF-WAY MARKERS (TYPE I)	12.000	EA
MAINTENANCE OF TRAFFIC	LUMP SUM	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE TRAFFIC STRIPE	1,100.000	LF
(CONTINUOUS WHITE)		
4" WIDE TRAFFIC STRIPE	1,100.000	LF
(CONTINUOUS YELLOW)		
REFLECTORIZED TRAFFIC OBJECT MARKER	4.000	EA
(ENCAPSULATED LENS)(TYPE 3)		
<u>EROSION CONTROL ITEMS:</u>		
AGRICULTURAL LIMESTONE	1.980	TON
COMMERCIAL FERTILIZER (13.13.13)	0.990	TON
SEEDING	0.990	AC
VEGETATIVE MATERIALS FOR MULCH	2.970	TON
TEMPORARY SILT FENCE, TYPE I	320.000	LF
(AOS 0.15 - 0.84)		
WATTLES 20"	100.000	LF
LOOSE RIPRAP, 300 LB.	40.000	TON
GEOTEXTILE UNDER RIPRAP,	80.000	SY
TYPE V, NON-WOVEN, AOS < 0.43		

SECTION 900
PROJECT NO. SAP-60(42)
QUITMAN COUNTY

BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
24" PRE-FORMED PILE HOLES	200.000	LF
19' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR, 30 DEG SKEW RIGHT FORWARD	18.000	EA
19' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR, 30 DEG SKEW RIGHT FORWARD	6.000	EA
PRECAST CONCRETE BARRIER RAIL	114.000	LF
LOOSE RIPRAP, 300 LB.	100.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, NON-WOVEN, AOS < 0.43	190.000	SY

PILING ALTERNATE #1 ITEMS:

18" PRESTRESSED CONCRETE PILING	800.000	LF
BRIDGE CONCRETE, CLASS "A"	51.600	CY
REINFORCEMENT	9,466.000	LB

PILING ALTERNATE #2 ITEMS:

14" STEEL PILING	800.000	LF
BRIDGE CONCRETE, CLASS "A"	58.240	CY
REINFORCEMENT	9,553.000	LB

PROJECT NO. SAP-60 (42)
QUITMAN COUNTY

NOTICE TO CONTRACTORS:

CONTRACT TIME: 90 Working Days

BASIS OF AWARD

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Quitman County, the County Engineer's office and the Office of the State Aid Engineer, 412 E. Woodrow Wilson Avenue, Jackson, Mississippi. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from J. Wayne Morrison, County Engineer for Quitman County, Mississippi, P. O. Box 567, Yazoo City. The Cost is fifty dollars (\$50.00) for plans and fifty dollars (\$50.00) for the proposal, non-refundable

Certified check or bid bond for five percent (5%) of the total bid, made payable to Quitman County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Manuel Killebrew, President
Quitman County Board of Supervisors