OFFICE OF STATE AID ROAD CONSTRUCTION MISSISSIPPI DEPARTMENT OF TRANSPORTATION AND

TISHOMINGO COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Tishomingo County at the Tishomingo County Courthouse, located at 1008 Battleground Drive, Iuka, Mississippi, until 10:00 am on the $20^{\rm th}$ day of March, 2017 and shortly thereafter publicly opened for the construction of 0.141 miles of BOX BRIDGE AND APPROACHES TO REPLACE 2 PIPES on SALEM CEMETARY ROAD (COUNTY ROAD 992) being known as Project No. SAP-71(71) in Tishomingo County, Mississippi.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

ITEM	QUANTITY	UNIT
ROADWAY ITEMS:		
MOBILIZATION	LUMP SUM	LS
CLEARING AND GRUBBING	LUMP SUM	LS
REMOVAL OF PIPE (ALL SIZES)	60.000	LF
BORROW EXCAVATION (F.M.E.)	6,446.000	CY
(CONTRACTOR FURNISHED) (CLASS 9)		
GEOTEXTILE FABRIC STABILIZATION	3,083.000	SY
(TYPE V) (AOS <0.43)		
GRANULAR MATERIAL (FM),	92.000	CY
(CLASS 5, GROUP C)		
CRUSHED STONE SIZE 3/4" & DOWN, (FM)	792.000	CY
MIXING, SHAPING AND COMPACTION	2,044.000	SY
HOT MIX ASPHALT, (ST) (9.5 MM)	310.000	TON
ASPHALT FOR PRIME COAT (EA-1 OR AE-P)	716.000	GAL
36" REINFORCED CONCRETE PIPE, CLASS III	120.000	LF
48" REINFORCED CONCRETE PIPE, CLASS III	96.000	LF
RIGHT-OF-WAY MARKERS (TYPE I)	15.000	EA
MAINTENANCE OF TRAFFIC	LUMP SUM	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 MIL)	0.284	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 MIL)	1,500.000	LF
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	10.000	EA
TEMPORARY STREAM DIVERSION	1.000	EA
EROSION CONTROL ITEMS:		
AGRICULTURAL LIMESTONE	3.160	TON
COMMERCIAL FERTILIZER (13-13-13)	1.580	TON
AMMONIUM NITRATE	0.400	TON
SEEDING	1.580	AC
VEGETATIVE MATERIALS FOR MULCH	3.160	TON
SOLID SODDING	493.000	SY
PORTLAND CEMENT CONCRETE PAVED DITCH	76.040	CY

SECTION 900 PROJECT NO. SAP-71(71) TISHOMINGO COUNTY

115HOMINGO COUNTI		
TEMPORARY SILT FENCE	700.000	LF
(TYPE I OR II) (AOS 0.15-0.84)	700.000	11
LOOSE RIPRAP, 200 LB.	350.000	TON
GEOTEXTILE UNDER RIPRAP,	648.000	SY
TYPE V, AOS ,0.43		
WATTLES, 20"	550.000	LF
BRIDGE ITEMS:		
BOX BRIDGE CONCRETE, CLASS "BB"	156.020	CY
REINFORCEMENT	29,876.000	LB

NOTICE TO CONTRACTORS:

CONTRACT TIME: 90 Working Days

BASIS OF AWARD

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The Board of Supervisors hereby notifies all bidders that it will affirmatively ensure that in any contract entered into pursuant to this advertisement, minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Tishomingo County, the County Engineer's office and the Office of the State Aid Engineer, 412 E. Woodrow Wilson Avenue, Jackson, Mississippi. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Roland Humphrey, County Engineer for Tishomingo County, Mississippi, P. O. Box 1526, Tupelo. The Cost is fifty dollars (\$50.00) for plans and fifty dollars (\$50.00) for the proposal, non-refundable.

Certified check or bid bond for five percent (5%) of the total bid, made payable to Tishomingo County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Greg Collier, President Tishomingo County Board of Supervisors

Publish: February 16th & February 23rd, 2017