

OFFICE OF STATE AID ROAD CONSTRUCTION
MISSISSIPPI DEPARTMENT OF TRANSPORTATION
AND
ITAWAMBA COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Itawamba County, Mississippi at the Itawamba County Courthouse, 201 W Main Street, Fulton, Mississippi, until 10:00 am on the 31st day of May, 2017 and shortly thereafter publicly opened for the construction of 0.085 miles of BRIDGE & APPROACHES TO REPLACE BRIDGE NO. 99 on CUMMINGS ROAD being known as Project No. LSBP-29(32) in Itawamba County, Mississippi.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

ITEM	QUANTITY	UNIT
<u>ROADWAY ITEMS:</u>		
MOBILIZATION	LUMP SUM	LS
CLEARING AND GRUBBING	LUMP SUM	LS
REMOVAL OF EXISTING BRIDGE @ STA. 36+40	1.000	UN
REMOVAL OF PAVEMENT (ALL TYPES)	700.000	SY
UNCLASSIFIED EXCAVATION (FM)	467.000	CY
EXCESS EXCAVATION (FM)	410.000	CY
GEOTEXTILE FABRIC STABILIZATION (TYPE V) (AOS <0.43)	1,320.000	SY
CRUSHED STONE SIZE 3/4" & DOWN, (FM)	236.000	CY
36" CORRUGATED POLYETHYLENE PIPE	88.000	LF
RIGHT-OF-WAY MARKERS (TYPE I)	12.000	EA
MAINTENANCE OF TRAFFIC	LUMP SUM	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC WARNING SIGN (ENCAPSULATED LENS)	2.000	EA
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS)(TYPE 3)	4.000	EA
<u>EROSION CONTROL ITEMS:</u>		
AGRICULTURAL LIMESTONE	1.000	TON
COMMERCIAL FERTILIZER (13-13-13)	0.500	TON
SEEDING	0.500	AC
SOLID SODDING	100.000	SY
EXCELSIOR BLANKET	2,045.000	SY
TEMPORARY SILT FENCE (TYPE I OR II) (AOS 0.15-0.84)	350.000	LF
WATTLES, 20"	280.000	LF

BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
12" STEEL PILING	800.000	LF
BRIDGE CONCRETE, CLASS "B"	5.330	CY
REINFORCEMENT	100.000	LB
19' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	6.000	EA
31' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	6.000	EA
40' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	6.000	EA
19' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	2.000	EA
31' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	2.000	EA
40' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	2.000	EA
PRECAST CONCRETE BARRIER RAIL	180.000	LF
31.33' PRECAST CONCRETE CAP,	2.000	EA
INTERMEDIATE UNIT, STEEL PILE		
31' PRECAST CONCRETE CAP, END UNIT, STEEL PILE	2.000	EA
9.25' PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP, 200 LB.	177.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS <0.43	328.000	SY

NOTICE TO CONTRACTORS:

CONTRACT TIME: 140 Working Days

BASIS OF AWARD

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement; minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Itawamba County, the LSBP Engineer's office and the Office of the State Aid Engineer, 412 E. Woodrow Wilson Avenue, Jackson, Mississippi. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Carrson Neal, LSBP Engineer for Itawamba County, Mississippi, P. O. Box 1526, Tupelo. The Cost is fifty dollars (\$50.00) for plans and fifty dollars (\$50.00) for the proposal, non-refundable.

Certified check or bid bond for five percent (5%) of the total bid, made payable to Itawamba County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Cecil "Ike" Johnson, President
Itawamba County Board of Supervisors

Publish: April 26th & May 3rd, 2017