

OFFICE OF STATE AID ROAD CONSTRUCTION
MISSISSIPPI DEPARTMENT OF TRANSPORTATION
AND
JEFFERSON DAVIS COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Jefferson Davis County, Mississippi at the Jefferson Davis County Administrative Building, Prentiss, Mississippi, until 1:30 pm on the 6th day of October, 2014 and shortly thereafter publicly opened for the construction of 0.263 miles of BRIDGE REPLACEMENT, BASE & SURFACING on the ROSE HILL - DYKES ROAD being known as Project No. BR-0033(18)B in Jefferson Davis County, Mississippi.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

<u>ITEM</u>	<u>QUANTITY</u>	<u>UNIT</u>
<u>ROADWAY ITEMS:</u>		
MOBILIZATION	LUMP SUM	LS
CLEARING AND GRUBBING	LUMP SUM	LS
REMOVAL OF BRIDGE AT STATION 14+11	1.000	UN
REMOVAL OF BRIDGE AT STATION 7+80	1.000	UN
REMOVAL OF PIPE (ALL SIZES)	24.000	LF
UNCLASSIFIED EXCAVATION (FM)	2,990.000	CY
BORROW EXCAVATION (F.M.E.)	495.000	CY
(CONTRACTOR FURNISHED) (CLASS 7)		
CHANNEL EXCAVATION (FM)	1,065.000	CY
STRUCTURE EXCAVATION	620.000	CY
GRANULAR MATERIAL (LVM),	2,150.000	CY
(CLASS 6, GROUP B)		
SIZE (II) STABILIZER AGGREGATE,	150.000	CY
COARSE		
HOT MIX ASPHALT, ST 9.5 MM	333.000	TON
HOT MIX ASPHALT, ST 19 MM	724.000	TON
ASPHALT FOR PRIME COAT (EA-1)	1,151.000	GAL
18" REINFORCED CONCRETE PIPE, CLASS III	80.000	LF
GUARD RAIL, W-BEAM	175.000	LF
GUARD RAIL, BRIDGE END SECTION,	4.000	EA
TYPE I THRIE-BEAM		
GUARD RAIL, TERMINAL END SECTION	4.000	EA
RIGHT-OF-WAY MARKERS (TYPE I)	21.000	EA
MAINTENANCE OF TRAFFIC	LUMP SUM	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIPE	0.530	MI
(CONTINUOUS WHITE) (60 MILS)		
4" WIDE THERMOPLASTIC TRAFFIC	2,800.000	LF
STRIPE (CONTINUOUS YELLOW) (90 MILS)		

SECTION 900
PROJECT NO. BR-0033(18)B
JEFFERSON DAVIS COUNTY

TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	32.000	EA
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS)(TYPE 3)	4.000	EA

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	6.000	TON
COMMERCIAL FERTILIZER (13-13-13)	1.410	TON
AMMONIUM NITRATE	0.300	TON
SEEDING	3.000	AC
VEGETATIVE MATERIALS FOR MULCH	6.000	TON
SOLID SODDING	400.000	SY
EROSION CONTROL FABRIC	1,725.000	SY
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	2,975.000	LF
LOOSE RIPRAP, 200 LB.	430.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.21-0.43	905.000	SY
WATTLES, 20"	715.000	LF

BRIDGE ITEMS:

SITE "A" ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14" PRESTRESSED CONCRETE PILING	520.000	LF
31' PRECAST CONCRETE SLAB UNIT, 3'-6" INTERIOR	18.000	EA
31' PRECAST CONCRETE SLAB UNIT, 3'-6" EXTERIOR	6.000	EA
PRECAST CONCRETE BARRIER RAIL	186.000	LF
31' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE	2.000	EA
31' PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE	2.000	EA
9.25' PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP, 300 LB.	285.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.21-0.43	682.000	SY

BOX BRIDGE ITEMS:

SITE "B" ITEMS:

BOX BRIDGE CONCRETE, CLASS "BB"	234.390	CY
REINFORCEMENT	26,030.000	LB

NOTICE TO CONTRACTORS:

CONTRACT TIME: 120 Working Days

BASIS OF AWARD

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The attention of the BIDDER is directed to the State and Federal laws governing selection of and employment of labor.

MINIMUM WAGE RATES for this project have been predetermined by the Secretary of the the Department of Labor in accordance with the requirements of Federal regulations governing the expenditure of FEDERAL AID HIGHWAY FUNDS and are set out in the labor regulations contained in the proposal.

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Jefferson Davis County, the County Engineer's office and the Office of the State Aid Engineer, 412 E. Woodrow Wilson Avenue, Jackson, Mississippi. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from H. Les Dungan, III, County Engineer for Jefferson Davis County, Mississippi, 1574 Highway 98 East, Columbia. The Cost is fifty dollars (\$50.00) for plans and fifty dollars (\$50.00) for the proposal, non-refundable

Certified check or bid bond for five percent (5%) of the total bid, made payable to Jefferson Davis County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Bobby Rushing, President
Jefferson Davis County Board of Supervisors

Publish on: September 3, 2014
September 10, 2014