

**OFFICE OF STATE AID ROAD CONSTRUCTION  
MISSISSIPPI DEPARTMENT OF TRANSPORTATION  
AND  
JACKSON COUNTY BOARD OF SUPERVISORS**

**SECTION 900**

**NOTICE TO CONTRACTORS:**

Sealed bids will be received by the Board of Supervisors of Jackson County, Mississippi at the Jackson County Services Building, Pascagoula, Mississippi, until 1:00 p.m. on the 28<sup>th</sup> day of April, 2015, and shortly thereafter publicly opened for the construction of 0.208 miles of BRIDGE REPLACEMENT and APPROACHES on OLD BILOXI ROAD, being known as Project No. BR-0116(14)B in Jackson County, Mississippi.

Sealed bids are to be addressed to and received by Terry Miller, Clerk of the Jackson County Board of Supervisors, Jackson County Services Building, Suite R, 2915 Canty Street, Pascagoula, Mississippi 39568, (phone 228/769-3499), prior to 1:00 p.m., on the day of the bid opening.

**PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:**

<u>ITEM</u>	<u>QUANTITY</u>	<u>UNIT</u>
<b><u>ROADWAY ITEMS:</u></b>		
MOBILIZATION	LUMP SUM	LS
CLEARING AND GRUBBING	LUMP SUM	LS
REMOVAL OF BRIDGE @ STA. 15+14	1.000	UN
REMOVAL OF PIPE (ALL SIZES)	96.000	LF
UNCLASSIFIED EXCAVATION (FM)	733.000	CY
BORROW EXCAVATION (F.M.E.)	1,940.000	CY
(CONTRACTOR FURNISHED) (CLASS 7)		
EXCESS EXCAVATION (LVM)	457.000	CY
GRANULAR MATERIAL (LVM),	1,467.000	CY
(CLASS 9, GROUP B)		
CRUSHED STONE SIZE 610,	160.000	CY
(LVM)		
HOT MIX ASPHALT, (ST) ( 9.5 mm)	220.000	TON
HOT MIX ASPHALT, (ST) (19 mm)	585.200	TON
GUARD RAIL, "W" BEAM, COMPLETE-IN-PLACE	275.000	LF
GUARD RAIL, BRIDGE END SECTION,	4.000	EA
TYPE "I" THRIE BEAM, COMPLETE-IN-PLACE		
GUARD RAIL, TERMINAL END SECTION	4.000	EA
RIGHT-OF-WAY MARKERS (TYPE I)	11.000	EA
MAINTENANCE OF TRAFFIC	LUMP SUM	LS
ADDITIONAL CONSTRUCTION SIGNS	1.000	SF
4" WIDE THERMOPLASTIC EDGE STRIP	0.416	MI
(CONTINUOUS WHITE) (60 MILS)		
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW)	2,200.000	LF
(90 MILS)		
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	27.000	EA
REFLECTORIZED TRAFFIC WARNING SIGN (ENCAPSULATED LENS)	2.000	EA
REFLECTORIZED TRAFFIC OBJECT MARKER	4.000	EA

SECTION 900  
PROJECT NO. BR-0116(14)B  
JACKSON COUNTY

---

(ENCAPSULATED LENS) (TYPE 3)

EROSION CONTROL ITEMS:

TOPSOIL FOR SLOPE TREATMENT (CONTRACTOR FURNISHED) (LVM)	1,850.000	CY
AGRICULTURAL LIMESTONE	4.580	TON
COMMERCIAL FERTILIZER (13-13-13)	2.290	TON
AMMONIUM NITRATE	1.150	TON
SEEDING	2.290	AC
VEGETATIVE MATERIALS FOR MULCH	4.580	TON
SOLID SODDING	761.000	SY
EXCELSIOR BLANKET	2,120.000	SY
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	3,011.000	LF
LOOSE RIPRAP, 100 LB.	27.600	TON
GEOTEXTILE UNDER BRIDGE ABUTMENT, TYPE V, AOS 0.21-0.43	151.800	SY
WATTLES, 20"	270.000	LF

BRIDGE ITEMS:

TEST PILE	6.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14" PRESTRESSED CONCRETE PILING	800.000	LF
16" PRESTRESSED CONCRETE PILING	440.000	LF
18" PRESTRESSED CONCRETE PILING	1,080.000	LF
BRIDGE CONCRETE, CLASS "A"	275.600	CY
31' PRESTRESSED CONCRETE BEAM, TYPE 1+2	615.000	LF
100' PRESTRESSED CONCRETE BEAM, TYPE IV	498.750	LF
REINFORCEMENT	46,589.000	LB
CONCRETE RAILING	446.840	LF
LOOSE RIPRAP, 200 LB.	319.000	TON
LOOSE RIPRAP, 300 LB.	164.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.21-0.43	895.000	SY

NOTICE TO CONTRACTORS:

CONTRACT TIME: 120 Working Days

BASIS OF AWARD

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The attention of the BIDDER is directed to the State and Federal laws governing selection of and employment of labor.

MINIMUM WAGE RATES for this project have been predetermined by the Secretary of the the Department of Labor in accordance with the requirements of Federal regulations governing the expenditure of FEDERAL AID HIGHWAY FUNDS and are set out in the labor regulations contained in the proposal.

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Jackson County, the County Engineer's office and the Office of the State Aid Engineer, 412 E. Woodrow Wilson Avenue, Jackson, Mississippi. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Robert Diamond, County Engineer for Jackson County, Mississippi, P. O. Box 205, Luceale. The Cost is fifty dollars (\$50.00) for plans and fifty dollars (\$50.00) for the proposal, non-refundable

Certified check or bid bond for five percent (5%) of the total bid, made payable to Jackson County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Barry Cumbest, President  
Jackson County Board of Supervisors