

OFFICE OF STATE AID ROAD CONSTRUCTION
MISSISSIPPI DEPARTMENT OF TRANSPORTATION
AND
HANCOCK COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Hancock County, Mississippi at the Hancock County Annex, Bay St. Louis, Mississippi, until 1:30 pm on the 6th day of November, 2017 and shortly thereafter publicly opened for the construction of 0.236 miles of GRADE, DRAIN, BASE, PAVE on the STANDARD DEDEAUX ROAD being known as Project No. STP-0127(2)B in Hancock County, Mississippi.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

ITEM	QUANTITY	UNIT
<u>ROADWAY ITEMS:</u>		
MOBILIZATION	LUMP SUM	LS
CLEARING AND GRUBBING	1.300	AC
REMOVAL OF ASPHALT PAVEMENT	1,553.000	SY
UNCLASSIFIED EXCAVATION (FM)	480.000	CY
BORROW EXCAVATION (F.M.E.)	1,151.000	CY
(CONTRACTOR FURNISHED) (CLASS 7)		
GRANULAR MATERIAL (FM),	312.000	CY
(CLASS 5, GROUP B)		
GRANULAR MATERIAL (FM),	1,811.000	CY
(CLASS 9, GROUP B)		
HOT MIX ASPHALT, ST 9.5 MM	431.000	TON
HOT MIX ASPHALT, ST 19 MM	576.000	TON
HOT MIX ASPHALT, ST 19 MM,	106.000	TON
BASE REPAIR		
HOT MIX ASPHALT, ST 9.5 MM,	58.000	TON
LEVELING		
COLD MILLING OF BITUMINOUS	1,000.000	SY
PAVEMENT, ALL DEPTHS		
RUMBLE STRIPS, GROUND-IN	0.101	MI
CLASS B STRUCTURAL CONCRETE,	0.166	CY
MINOR STRUCTURES		
24" REINFORCED CONCRETE PIPE,	40.000	LF
CLASS III		
24" REINFORCED CONCRETE PIPE,	2.000	EA
END SECTION		
RIGHT-OF-WAY MARKERS (TYPE I)	8.000	EA
MAINTENANCE OF TRAFFIC	LUMP SUM	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIPE	0.583	MI
(CONTINUOUS WHITE) (60 MILS)		
4" WIDE THERMOPLASTIC TRAFFIC	3,143.880	LF
STRIPE (CONTINUOUS YELLOW)		
(90 MILS)		

SECTION 900
PROJECT NO. STP-0127(2)B
HANCOCK COUNTY

THERMOPLASTIC LEGEND (WHITE) (90 MILS)	50.000	SF
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	36.000	EA
REFLECTORIZED TRAFFIC WARNING SIGN (ENCAPSULATED LENS)	15.000	EA
REFLECTORIZED TRAFFIC REGULATORY SIGN (ENCAPSULATED LENS)	2.000	EA

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	4.500	TON
COMMERCIAL FERTILIZER (13-13-13)	2.250	TON
AMMONIUM NITRATE	0.225	TON
SEEDING	2.250	AC
VEGETATIVE MATERIALS FOR MULCH	4.500	TON
TEMPORARY SILT FENCE (TYPE II)	3,070.000	LF
WATTLES, 20"	620.000	LF

PROJECT NO. STP-0127(2)B
HANCOCK COUNTY

NOTICE TO CONTRACTORS:

CONTRACT TIME: 120 Working Days

BASIS OF AWARD

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The attention of the BIDDER is directed to the State and Federal laws governing selection of and employment of labor.

MINIMUM WAGE RATES for this project have been predetermined by the Secretary of the the Department of Labor in accordance with the requirements of Federal regulations governing the expenditure of FEDERAL AID HIGHWAY FUNDS and are set out in the labor regulations contained in the proposal.

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Hancock County, the County Engineer's office and the Office of the State Aid Engineer, 412 Woodrow Wilson Avenue, Jackson, Mississippi. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Geoffery Clemens, County Engineer for Hancock County, Mississippi, P. O. Box 2795, Bay St. Louis. The Cost is one hundred ten dollars (\$110.00) for pla