

**OFFICE OF  
STATE AID ROAD CONSTRUCTION**  
MISSISSIPPI DEPARTMENT OF TRANSPORTATION  
P.O. BOX 1850  
JACKSON, MISSISSIPPI 39215-1850

**H. Carey Webb, P.E.**  
State Aid Engineer  
Telephone (601)359-7150  
www.msstateaidroads.us

412 Woodrow Wilson Avenue  
Jackson, Mississippi 39216  
Fax (601)359-7141  
mail@osarc.state.ms.us

February 10, 2017

Board of Supervisors  
Tishomingo County  
c/o Chancery Clerk  
Iuka, MS 38852

Gentlemen:

RE: **STATE AID PROJECT  
PROJECT NO. SAP-71(71)  
TISHOMINGO COUNTY**

The Plans and specifications for the above numbered project have been reviewed and are herewith approved. You are, therefore, authorized to advertise this project for bids. The work to be done under this project consists of **Approaches and Replace Pipe with a Box Bridge**.


The date for opening these bids has been set for **Monday, March 20, 2017 at 10:00 a.m.** in the **Courthouse at Iuka**.

In accordance with the Provisions of Section 31-7-13, Mississippi Code of 1972 as amended by House Bills numbered 901 and 1306 of the 1991 regular Legislative Session, the advertisement for receipt of bids on this project must be made once each week for two (2) consecutive weeks in a regular newspaper published in your county and, further, that the date as published for the bid opening shall not be less than fifteen (15) working days after the last published notice. The date, as set above, should be no sooner than the sixteenth working day after the last advertisement appears in the newspaper.

We are returning herewith an approved copy of the Plans and Proposal Documents to be filed by your Clerk when advertisement is begun.

Sincerely,

H. Carey Webb P. E.  
State Aid Engineer



By: Evelyn Hollins  
Administrative Assistant

pc: Roland Humphrey, P.E., Co. Eng./Project Eng.  
Supervisor District(s) 4  
Joel Bridges, P.E.  
F.H.W.A. , 00-01 (*if Federal*)  
System Consultants Associates  
McGraw Hill Construction Dodge  
**MS Procurement Technical Assistance Program**  
Associated General Contractors of Mississippi, Inc.  
M.R.B.A.  
Project File

OFFICE OF STATE AID ROAD CONSTRUCTION  
MISSISSIPPI DEPARTMENT OF TRANSPORTATION  
AND  
TISHOMINGO COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Tishomingo County, Mississippi at the Tishomingo County Courthouse, Iuka, Mississippi, until on the            day of            ,            and shortly thereafter publicly opened for the construction of 0.141 miles of BOX BRIDGE AND APPROACHES TO REPLACE 2 PIPES on the SALEM CEMETARY ROAD (COUNTY ROAD 992) being known as Project No. SAP-71(71) in Tishomingo County, Mississippi.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

ITEM	QUANTITY	UNIT
<u>ROADWAY ITEMS:</u>		
MOBILIZATION	LUMP SUM	LS
CLEARING AND GRUBBING	LUMP SUM	LS
REMOVAL OF PIPE (ALL SIZES)	60.000	LF
BORROW EXCAVATION (F.M.E.)	6,446.000	CY
(CONTRACTOR FURNISHED) (CLASS 9)		
GEOTEXTILE FABRIC STABILIZATION	3,083.000	SY
(TYPE V) (AOS <0.43)		
GRANULAR MATERIAL (FM),	92.000	CY
(CLASS 5, GROUP C)		
CRUSHED STONE SIZE 3/4" & DOWN,	792.000	CY
(FM)		
MIXING, SHAPING AND COMPACTION	2,044.000	SY
HOT MIX ASPHALT, (ST) (9.5 MM)	310.000	TON
ASPHALT FOR PRIME COAT	716.000	GAL
(EA-1 OR AE-P)		
36" REINFORCED CONCRETE PIPE,	120.000	LF
CLASS III		
48" REINFORCED CONCRETE PIPE,	96.000	LF
CLASS III		
RIGHT-OF-WAY MARKERS (TYPE I)	15.000	EA
MAINTENANCE OF TRAFFIC	LUMP SUM	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIPE	0.284	MI
(CONTINUOUS WHITE) (60 MIL)		
4" WIDE THERMOPLASTIC TRAFFIC	1,500.000	LF
STRIPE (CONTINUOUS YELLOW)		
(90 MIL)		
TWO-WAY YELLOW REFLECTIVE HIGH	10.000	EA
PERFORMANCE RAISED MARKERS		
TEMPORARY STREAM DIVERSION	1.000	EA

EROSION CONTROL ITEMS:

SECTION 900  
PROJECT NO. SAP-71(71)  
TISHOMINGO COUNTY

---

AGRICULTURAL LIMESTONE	3.160	TON
COMMERCIAL FERTILIZER (13-13-13)	1.580	TON
AMMONIUM NITRATE	0.400	TON
SEEDING	1.580	AC
VEGETATIVE MATERIALS FOR MULCH	3.160	TON
SOLID SODDING	493.000	SY
PORTLAND CEMENT CONCRETE	76.040	CY
PAVED DITCH		
TEMPORARY SILT FENCE	700.000	LF
(TYPE I OR II) (AOS 0.15-0.84)		
LOOSE RIPRAP, 200 LB.	350.000	TON
GEOTEXTILE UNDER RIPRAP,	648.000	SY
TYPE V, AOS ,0.43		
WATTLES, 20"	550.000	LF

BRIDGE ITEMS:

BOX BRIDGE CONCRETE, CLASS "BB"	156.020	CY
REINFORCEMENT	29,876.000	LB

NOTICE TO CONTRACTORS:

CONTRACT TIME: 90 Working Days

BASIS OF AWARD

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Tishomingo County, the County Engineer's office and the Office of the State Aid Engineer, 412 E. Woodrow Wilson Avenue, Jackson, Mississippi. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Roland Humphery, County Engineer for Tishomingo County, Mississippi, P. O. Box 1526, Tupelo. The Cost is fifty dollars (\$50.00) for plans and fifty dollars (\$50.00) for the proposal, non-refundable

Certified check or bid bond for five percent (5%) of the total bid, made payable to Tishomingo County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Greg Collier, President  
Tishomingo County Board of Supervisors