

**OFFICE OF  
STATE AID ROAD CONSTRUCTION**  
MISSISSIPPI DEPARTMENT OF TRANSPORTATION  
P.O. BOX 1850  
JACKSON, MISSISSIPPI 39215-1850

**H. Carey Webb, P.E.**  
State Aid Engineer  
Telephone (601)359-7150  
www.msstateaidroads.us

412 Woodrow Wilson Avenue  
Jackson, Mississippi 39216  
Fax (601)359-7141  
mail@osarc.state.ms.us

February 24, 2017

Board of Supervisors  
Lamar County  
c/o Chancery Clerk  
Purvis, MS 39475

Gentlemen:

RE: **SURFACE TRANSPORTATION PROGRAM/FEDERAL AID BRIDGE REPLACEMENT**  
**PROJECT NO. STP/BR-0200(16)B**  
**LAMAR COUNTY**

The Plans and specifications for the above numbered project have been reviewed and are herewith approved. You are, therefore, authorized to advertise this project for bids. The work to be done under this project consists of **Bridge Replacement**.

The date for opening these bids has been set for **Friday, March 31, 2017 at 10:00 a.m.** in the **Courthouse at Purvis**.

In accordance with the Provisions of Section 31-7-13, Mississippi Code of 1972 as amended by House Bills numbered 901 and 1306 of the 1991 regular Legislative Session, the advertisement for receipt of bids on this project must be made once each week for two (2) consecutive weeks in a regular newspaper published in your county and, further, that the date as published for the bid opening shall not be less than fifteen (15) working days after the last published notice. The date, as set above, should be no sooner than the sixteenth working day after the last advertisement appears in the newspaper.

We are returning herewith an approved copy of the Plans and Proposal Documents to be filed by your Clerk when advertisement is begun.

Sincerely,

H. Carey Webb P. E.  
State Aid Engineer

*Evelyn Hollins*

By: Evelyn Hollins  
Administrative Assistant

pc: Donald E. Walker, P.E., Co. Eng./Project Eng.  
Supervisor District(s) 3  
Lonnie Taylor, P.E.  
F.H.W.A. , 00-01 (if Federal)  
System Consultants Associates  
McGraw Hill Construction Dodge  
**MS Procurement Technical Assistance Program**  
Associated General Contractors of Mississippi, Inc.  
M.R.B.A.  
Project File



OFFICE OF STATE AID ROAD CONSTRUCTION  
MISSISSIPPI DEPARTMENT OF TRANSPORTATION  
AND  
LAMAR COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Lamar County, Mississippi at the Lamar County Courthouse, Purvis, Mississippi, until on the day of , and shortly thereafter publicly opened for the construction of 0.148 miles of BRIDGE REPLACEMENT on the PURVIS-COLUMBIA ROAD being known as Project No. STP/BR-0200(16)B in Lamar County, Mississippi.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

ITEM	QUANTITY	UNIT
<u>ROADWAY ITEMS:</u>		
MOBILIZATION	LUMP SUM	LS
CLEARING AND GRUBBING	LUMP SUM	LS
REMOVAL OF BRIDGE (STA. 125+62.00)	1.000	UN
REMOVAL OF PIPE, ALL SIZES	22.000	LF
REMOVAL OF ASPHALT PAVEMENT, (ALL DEPTHS)	1,398.000	SY
UNCLASSIFIED EXCAVATION (FM)	296.000	CY
BORROW EXCAVATION) (CONTRACTOR FURNISHED, LVM, CLASS 9-8)	2,493.000	CY
EXCESS EXCAVATION (FM)	780.000	CY
GRANULAR MATERIAL (LVM), (CLASS 5, GROUP C)	872.000	CY
CRUSHED STONE	609.000	TON
HOT MIX ASPHALT, (ST) ( 9.5mm)	129.000	TON
HOT MIX ASPHALT, (ST) (12.5mm)	163.000	TON
HOT MIX ASPHALT, (ST) (19mm)	255.000	TON
CLASS "B" STRUCTURAL CONCRETE, MINOR STRUCTURES	0.252	CY
18" REINFORCED CONCRETE PIPE, CLASS III	24.000	LF
18" REINFORCED CONCRETE PIPE END SECTION	2.000	EA
22" x 13" CONCRETE ARCH PIPE, CLASS III	180.000	LF
22" X 13' CONCRETE ARCH PIPE END SECTION	2.000	EA
GUARD RAIL, "W BEAM"	250.000	LF
GUARD RAIL, BRIDGE END SECTION, TYPE "I", THRIE BEAM	4.000	EA
GUARD RAIL, TERMINAL END SECTION	4.000	EA
RIGHT-OF-WAY MARKERS (TYPE II)	15.000	EA
MAINTENANCE OF TRAFFIC	LUMP SUM	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF



SECTION 900  
PROJECT NO. STP/BR-0200(16)B  
LAMAR COUNTY

4" WIDE COLD PLASTIC EDGE STRIPE (CONTINUOUS WHITE)	0.068	MI
4" WIDE COLD PLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW)	360.000	LF
4" WIDE THERMOPLASTIC EDGE STRIP (CONTINUOUS WHITE) (60 MILS)	0.229	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 MILS)	1,210.000	LF
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	18.000	EA
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	3.300	TON
COMMERCIAL FERTILIZER (13-13-13)	1.650	TON
AMMONIUM NITRATE	0.180	TON
SEEDING	1.650	AC
VEGETATIVE MATERIALS FOR MULCH	3.300	TON
SOLID SODDING	20.000	SY
EXCELSIOR BLANKET	400.000	SY
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	1,775.000	LF
LOOSE RIPRAP, 300 LB.	15.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.21-0.43	20.000	SY
WATTLES, 20"	96.000	LF

BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14" STEEL PILING	1,710.000	LF
BRIDGE CONCRETE, CLASS "A"	228.250	CY
40' PRESTRESSED CONCRETE BEAM TYPE I+2	397.500	LF
100' PRESTRESSED CONCRETE BEAM TYPE IV	498.750	LF
REINFORCEMENT	36,398.000	LB
CONCRETE RAILING	360.000	LF
LOOSE RIPRAP, 300 LB.	504.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.21-0.43	1,329.000	SY



PROJECT NO. STP/BR-0200(16)B  
LAMAR COUNTY

NOTICE TO CONTRACTORS:

CONTRACT TIME: 120 Working Days

BASIS OF AWARD

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The attention of the BIDDER is directed to the State and Federal laws governing selection of and employment of labor.

MINIMUM WAGE RATES for this project have been predetermined by the Secretary of the the Department of Labor in accordance with the requirements of Federal regulations governing the expenditure of FEDERAL AID HIGHWAY FUNDS and are set out in the labor regulations contained in the proposal.

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Lamar County, the County Engineer's office and the Office of the State Aid Engineer, 412 E. Woodrow Wilson Avenue, Jackson, Mississippi. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Donald E. Walker, County Engineer for Lamar County, Mississippi, P. O. Box 16496, Hattiesburg. The Cost is thirty five dollars (\$35.00) for plans and twenty five dollars (\$25.00) for the proposal, non-refundable

Certified check or bid bond for five percent (5%) of the total bid, made payable to Lamar County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Joe Bounds, President  
Lamar County Board of Supervisors

