

OFFICE OF STATE AID ROAD CONSTRUCTION
MISSISSIPPI DEPARTMENT OF TRANSPORTATION
AND
MONTGOMERY COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Montgomery County, Mississippi at the Montgomery County Courthouse, Winona, Mississippi, until 8:10 am on the 30th day of September, 2022 and shortly thereafter publicly opened for the construction of 0.075 miles of REPLACE BRIDGE AND APPROACHES on the PROVIDENCE ROAD being known as Project No. ERBR-49(03) in Montgomery County, Mississippi.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

ITEM	QUANTITY	UNIT
<u>ROADWAY ITEMS:</u>		
MOBILIZATION	Lump Sum	LS
CLEARING AND GRUBBING	Lump Sum	LS
REMOVAL OF BRIDGE @ STA. 141+55	1.000	UN
REMOVAL OF ASPHALT PAVEMENT (ALL DEPTHS)	46.000	SY
EXCESS EXCAVATION (FM)	1,659.000	CY
CRUSHED STONE	240.000	TON
HOT MIX ASPHALT, (ST) (9.5 MM)	100.000	TON
GUARD RAIL, "W" BEAM	100.000	LF
GUARD RAIL, BRIDGE END SECTION, TYPE "I" THRIE BEAM	4.000	EA
GUARD RAIL, TERMINAL END SECTION	4.000	EA
ROADWAY CONSTRUCTION SURVEYING	Lump Sum	LS
BRIDGE CONSTRUCTION SURVEYING	Lump Sum	LS
MAINTENANCE OF TRAFFIC	Lump Sum	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (90 MILS)	0.152	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (120 MILS)	0.152	MI
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	10.000	EA
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA

SECTION 900
PROJECT NO. ERBR-49(03)
MONTGOMERY COUNTY

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	0.240	TON
COMMERCIAL FERTILIZER (13:13:13)	0.040	TON
AMMONIUM NITRATE	0.010	TON
SEEDING	0.120	AC
VEGETATIVE MATERIALS FOR MULCH	0.360	TON
EXCELSIOR BLANKET	300.000	SY
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15 - 0.84)	300.000	LF
LOOSE RIPRAP, 200 LB	800.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.21 - 0.43	1,470.000	SY
WATTLES, 20"	300.000	LF

BRIDGE ITEMS:

CLASS "B" STRUCTURAL CONCRETE, MINOR STRUCTURES (FOR PILE ENCASEMENTS)	24.000	CY
REINFORCING STEEL (FOR PILE ENCASEMENTS)	302.000	LB
TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14" STEEL PILING (HP 14X73)	3,120.000	LF
18" PRE-FORMED PILE HOLES	200.000	LF
PILING CUTOFF (14" STEEL PILE)	0.000	EA
BRIDGE CONCRETE, CLASS "A"	244.720	CY
31' PRESTRESSED CONCRETE BEAM	307.500	LF
40' PRESTRESSED CONCRETE BEAM	397.500	LF
60' PRESTRESSED CONCRETE BEAM	298.750	LF
REINFORCEMENT	43,858.000	LB
CONCRETE RAILING	402.840	LF
LOOSE RIPRAP, 300 LB	225.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.21 - 0.43	485.000	SY

SECTION 900
PROJECT NO. ERBR-49(03)
MONTGOMERY COUNTY

NOTICE TO CONTRACTORS:

CONTRACT TIME 90 WORKING DAYS

BASIS OF AWARD

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The attention of the BIDDER is directed to the State and Federal laws governing selection of and employment of labor.

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND PROPOSALS may be secured from J. Christian Gardner, County Engineer for Montgomery County, Mississippi, P.O. Drawer 1197, Kosciusko. The Cost is fifty dollars (\$50.00) for plans and fifty dollars (\$50.00) for the proposal, non-refundable.

Certified check or bid bond for five percent (5%) of the total bid, made payable to Montgomery County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Ron Wood, President
Montgomery County Board of Supervisors