



OSARC
OFFICE OF
STATE AID ROAD CONSTRUCTION



RECEIVED
2/3/2021

Harry Lee James, P.E.
State Aid Engineer
P.O. Box 1850

412 E. Willow Wilson Ave.
Jackson, Mississippi 39216
Fax (601) 373-7141

February 1, 2021

Board of Supervisors
Clarke County
c/o Chancery Clerk
Quitman, MS 39355

Gentlemen:

RE: **STATE AID PROJECT**
PROJECT NO. SAP-12(69)
CLARKE COUNTY

The Plans and specifications for the above numbered project have been reviewed and are herewith approved. You are, therefore, authorized to advertise this project for bids. The work to be done under this project consists of **Construct a 3 Span @ 31 L.F. Precast Span Bridge on Piles with Approaches, Base and HMA Paving, Guardrails, Traffic Striping and Signage.**

The date for opening these bids has been set for **Monday, March 8, 2021 at 10:00 a.m.** in the **Chancery at Quitman.**

In accordance with the Provisions of Section 31-7-13, Mississippi Code of 1972 as amended by House Bills numbered 901 and 1306 of the 1991 regular Legislative Session, the advertisement for receipt of bids on this project must be made once each week for two (2) consecutive weeks in a regular newspaper published in your county and, further, that the date as published for the bid opening shall not be less than fifteen (15) working days after the last published notice. The date, as set above, should be no sooner than the sixteenth working day after the last advertisement appears in the newspaper.

We are returning herewith an approved copy of the Plans and Proposal Documents to be filed by your Clerk when advertisement is begun.

Sincerely,

Harry Lee James, P. E.
State Aid Engineer

Evelyn Hollins

By: Evelyn Hollins
Administrative Assistant

pc: Lawrence R. Clark, P.E., Co. Eng./Project Eng.
Supervisor District(s) 5
Butch Swales, P.E.
F.H.W.A., 00-01 (if Federal)
System Consultants Associates
McGraw Hill Construction Dodge
MS Procurement Technical Assistance Program
Associated General Contractors of Mississippi, Inc.
M.R.B.A.
Project File

OFFICE OF STATE AID ROAD CONSTRUCTION

BOARD OF SUPERVISORS OF CLARKE COUNTY

SECTION 900
NOTICE TO CONTRACTORS

Sealed bids will be received by the Board of Supervisors of Clarke County in Quitman, Mississippi until 10:00 A.M., on Monday _____, 2020, and shortly thereafter publicly opened for the construction of: Bridge & Approaches on 0.171 miles of County Road 650 (Hopewell-Shiloh Road), in District Five Clarke County, Mississippi, also known as State Aid Project No. SAP-12(69).

Principal Items of Work are Approximately as Follows:

Roadway Items

Mobilization	Lump Sum	L.S.
Clearing & Grubbing	Lump Sum	L.S.
Removal of Pipe (All Sizes)	3.00	Unit
Unclassified Excavation (F.M.)	693.00	Cu. Yd.
Borrow Excavation (FME) Contractor Furnished (Class 9-6)	3,273.00	Cu. Yd.
Granular Material (LVM)(Class 9, Group "B")	1,152.00	Cu. Yd.
Crushed Stone	467.00	Ton
Hot Mix Asphalt (ST)(9.5 mm)	163.00	Ton
Hot Mix Asphalt (ST)(19 mm)	440.00	Ton
Guard Rail, "W" Beam	175.00	Lin. Ft.
Guard Rail, Bridge End Section, Type "A" Modified	4.00	Each
Guard Rail, Terminal End Section	4.00	Each
Roadway Construction Surveying	Lump Sum	L.S.
Right-Of-Way Markers (Type II)	16.00	Each
Maintenance of Traffic	Lump Sum	L.S.
Additional Construction Signs	0.00	Sq. Ft.
4" Wide Cold Plastic Edge Stripe (Continuous White)	0.035	Mile
4" Wide Cold Plastic Traffic Stripe (Continuous Yellow)	186.00	Lin. Ft.
4" Wide Thermoplastic Edge Stripe (Continuous White) (60 Mil)	0.306	Mile
4" Wide Thermoplastic Traffic Stripe (Continuous Yellow) (90 mil)	1,615.00	Lin. Ft.
Two-Way Yellow Reflective High Performance Raised Markers	17.00	Each
Reflectorized Traffic Warning Sign (Encapsulated Lens)	15.00	Each
Reflectorized Traffic Object Marker (Encapsulated Lens)(Type 3)	4.00	Each
Reflectorized Traffic Delineator Sign (Encapsulated Lens)	18.00	Each
Reflectorized Traffic Warning Sign with Supplemental Plate (Encapsulated Lens)	2.00	Each
Geotextile Under Bridge End Treatments, Type V, ADS (<0.43)	142.00	Sq. Yd.

Erosion Control Items

Agricultural Limestone	3.18	Ton
Commercial Fertilizer (13:13:13)	1.59	Ton
Ammonium Nitrate	0.159	Ton
Seeding	1.59	Acre
Vegetative Material for Mulch	3.18	Ton
Solid Sodding	150.00	Ton
Temporary Silt Fence (Type II)	1,900.00	Lin. Ft.
Wattles, 12"	100.00	Lin. Ft.
Loose Riprap (300 lbs.)	125.00	Ton
Geotextile Under Riprap Non-Woven, Type V, AOS (0.21 – 0.43)	180.00	Sq. Yd.
Sediment Control Stone, Size 57	80.00	Ton

Bridge Items

Test Pile	2.00	Each
Conventional Static Pile Load Test	0.00	Each
14" Prestressed Concrete Piling	450.00	Lin. Ft.
18" Pre-Formed Pile Hole	390.00	Lin. Ft.
31' Precast Concrete Slab Unit, 3.5' Interior	18.00	Each
31' Precast Concrete Slab Unit, Curb	6.00	Each
Beam Type Railing with Concrete Posts	186.00	Lin. Ft.
29.0' Precast Concrete Cap, Intermediate Unit Concrete Pile	2.00	Each
29.0' Precast Concrete Cap, End Unit, Concrete Pile	2.00	Each
7.5' Precast Concrete Wing	4.00	Each
Loose Riprap, (300 Lb.)	203.00	Ton
Geotextile Under Riprap Non-Woven, Type V, AOS (<0.43)	424.00	Sq. Yd.

Contract Time: 60 Working Days

BASIS OF AWARD: The award, if made, will be made to the lowest qualified bidder on the basis of the published quantities.

Total Contract Time as Advertised: 60 Working Days

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that, in any contract entered into pursuant to this advertisement, minority business enterprises will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color or national origin in consideration for an award.

The Plans, Specifications, and Contract documents are on file and can be viewed and obtained online via the website of the County Engineer, Lawrence R. Clark, P.E. at www.clarkengineersprojects.com. By use of the website the plan holders shall have the option of obtaining hard copy of the Plans and Specifications and/or shall have the opportunity to submit an official bid online.

All hard copy proposals shall be directed to the attention of The Clarke County Board of Supervisors with the outside of the envelope marked "Project No. SAP-12(69) Bid Proposal for CR 650 Precast Bridge Project".

Section 900
Notice to Contractors
Project No. SAP-12(69)
Clarke County, MS

Contractor shall indicate certificate of responsibility number on the outside of the envelope. Online bids shall be accepted and opened as instructed on the website and in the Contract Documents.

Certified Check or Bid Bond for five percent (5%) of total bid payable to Clarke County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letter qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid, and such proposals will not be considered in making the award.

Lorenzo Carter, President
Clarke County Board of Supervisors
State of Mississippi

Published Dates: