OSARC
OFFICE OF
STATE AID ROAD CONSTRUCTION

RECEIVED
10-29-2020

Harry Lee James, P.E.
State Aid Engineer
P.O. Box 1850

412 E. Woodrow Wilson Ave.
Jackson, Mississippi 39216
Fax (601) 359-7141

October 28, 2020

Board of Supervisors
Hinds County
c/o Chancery Clerk
Jackson, MS 39205-0686

Gentlemen:

RE: **LOCAL SYSTEM BRIDGE PROGRAM**
PROJECT NO. **LSBP-25(44)**
HINDS COUNTY

The Plans and specifications for the above numbered project have been reviewed and are herewith approved. You are, therefore, authorized to advertise this project for bids. The work to be done under this project consists of **Bridge Replacement and Approaches**.

The date for opening these bids has been set for **Monday, December 7, 2020** at **9:00 a.m.** in the **Boardroom**at **Jackson.**

In accordance with the Provisions of Section 31-7-13, Mississippi Code of 1972 as amended by House Bills numbered 901 and 1306 of the 1991 regular Legislative Session, the advertisement for receipt of bids on this project must be made once each week for two (2) consecutive weeks in a regular newspaper published in your county and, further, that the date as published for the bid opening shall not be less than fifteen (15) working days after the last published notice. The date, as set above, should be no sooner than the sixteenth working day after the last advertisement appears in the newspaper.

We are returning herewith an approved copy of the Plans and Proposal Documents to be filed by your Clerk when advertisement is begun.

Sincerely,

Harry Lee James, P. E.
State Aid Engineer

Evelyn Hollins

By: Evelyn Hollins
Administrative Assistant

pc: Tommy Avant, P.E., Co. Eng./Project Eng.
Supervisor District(s) 2
Edward D Holland, P.E.
F.H.W.A. , **00-01** (*if Federal*)
System Consultants Associates
McGraw Hill Construction Dodge
MS Procurement Technical Assistance Program
Associated General Contractors of Mississippi, Inc.
M.R.B.A.
Project File

OFFICE OF STATE AID ROAD CONSTRUCTION
MISSISSIPPI DEPARTMENT OF TRANSPORTATION
AND HINDS COUNTY BOARD OF SUPERVISIORS

SECTION 900

NOTICE TO CONTRACTORS :

Sealed bids will be received by the Chancery Clerk's Office of Hinds County, Mississippi at 316 South President Street, Jackson, Mississippi 39201 until_____ on the _____ day of _____, and shortly thereafter publicly opened for the construction of 0.161 miles of Bridge Replacement and Approaches on Louis Brown Road being known as Project No. LSBP-25(44) in Hinds County, Mississippi.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS

ITEM	QUANTITY	UNIT
ROADWAY ITEMS :		
MOBILIZATION	LUMP SUM	LS
CLEARING AND GRUBBING	LUMP SUM	LS
REMOVAL OF PRECAST BRIDGE @STA.14+29.39	1.00	UN
REMOVAL OF ASPHALT PAVEMENT	1,762.00	SY
UNCLASSIFIED EXCAVATION (FM)	1,118.00	CY
BORROW EXCAVATION (FME) (CONTRACTOR FURNISHED), CLASS 9	300.00	CY
GRANULAR MATERIAL (LVM) (CLASS 5, GROUP B)	686.00	CY
RIGHT-OF-WAY MARKERS (TYPE II)	16.00	EA
MAINTENANCE OF TRAFFIC	LS	LS
ADDITIONAL CONSTRUCTION SIGNS	0.00	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) TYPE 3	4.000	EA
EROSION ITEMS :		
AGRICULTURAL LIMESTONE	3.120	TON
COMMERCIAL FERTILIZER (13:13:13)	1.560	TON
SEEDING	1.560	AC
VEGETATIVE MATERIAL FOR MULCH	3.120	TON
TEMPORARY SILT FENCE (TYPE II)(AOS .15-.84)	1,500.000	LF
WATTLES, 20"	200.000	LF

BRIDGE ITEMS :

26'-6" CLEAR ROADWAY WIDTH
STA.14+07.00, 2@19', 1@31', 2@19' PRECAST CONCRETE SPANS
30° LT. FWD. SKEW

ITEM	QUANTITY	UNIT
TEST PILES	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14" PRESTRESSED CONCRETE PILING	1,060.000	LF
18" PRE-FORMED PILE HOLE	620.000	LF
19' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR, 30° SKEW, LT. FWD.	24.000	EA
31' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR, 30° SKEW, LT. FWD.	6.000	EA
19' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR, 30° SKEW, LT. FWD	8.000	EA
31' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR, 30° SKEW, LT. FWD	2.000	EA
BEAM TYPE RAILING WITH CONCRETE POSTS	214.000	LF
33.50' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE, , 30° SKEW, LT. FWD	4.000	EA
33.50' PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE, 30° SKEW, LT. FWD	2.000	EA
9.33' PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP, 300 Lb.	260.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.21-0.43	482.000	SY

CONTRACT TIME: 60 Working Days

BASIS OF AWARD

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Hinds County, Eddie Jean Carr, Second Floor, Chancery Court Building, 316 South President Street, Jackson, Mississippi 39201, the County Engineer's office, IMS, 126 East Amite Street, Jackson, Mississippi 39201, and the Office of the State Aid Engineer, 412 Woodrow Wilson Avenue, Jackson, Mississippi. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Tommy Avant, LSBP Engineer for Hinds County, Mississippi, IMS, 126 East Amite Street, Jackson, Mississippi 39201. The cost is fifty dollars ($50.00) for plans and fifty dollars ($50.00) for the proposal, non-refundable.

Certified check or bid bond for fiver percent (5%) of the total bid, made payable to Hinds County and the State of Mississippi must accompany each proposal.

Bids must be hand delivered, or otherwise physically delivered by public or private couriers or delivery service, including but not limited to U.S. Postal Service, Certified Mail with return receipt requested, United Parcel Service, Federal Express, or by any other delivery method wherein receipt of sadi bids must be acknowledged, in writing, by the addressee at _____ to **Eddie Jean Carr, Chancery Clerk,** Second Floor, Chancery Court Building, 316 South President Street, Jackson, Mississippi 39201 or P.O. Box 686, Jackson, Mississippi 39205.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Mike Morgan, President
Hinds County Board of Supervisors
Eddie Jean Carr
Chancery Clerk
By: Erika K.Epps, D.C.