



OSARC
OFFICE OF
STATE AID ROAD CONSTRUCTION



RECEIVED
2/28/2022

Harry Lee James, P.E.
State Aid Engineer
P.O. Box 1850

412 E. Woodrow Wilson Ave.
Jackson, Mississippi 39216
Fax (601) 339-7141

February 25, 2022

Board of Supervisors
Hancock County
c/o Chancery Clerk
Bay St. Louis, MS 39520

Gentlemen:

RE: **STATE AID PROJECT**
PROJECT NO. SAP-23(30)
HANCOCK COUNTY

The Plans and specifications for the above numbered project have been reviewed and are herewith approved. You are, therefore, authorized to advertise this project for bids. The work to be done under this project consists of **Bridge Replacement & Approaches**.

The date for opening these bids has been set for **Monday, April 18, 2022 at 10:00 a.m.** in the **Boardroom at Bay St. Louis.**

In accordance with the Provisions of Section 31-7-13, Mississippi Code of 1972 as amended by House Bills numbered 901 and 1306 of the 1991 regular Legislative Session, the advertisement for receipt of bids on this project must be made once each week for two (2) consecutive weeks in a regular newspaper published in your county and, further, that the date as published for the bid opening shall not be less than fifteen (15) working days after the last published notice. The date, as set above, should be no sooner than the sixteenth working day after the last advertisement appears in the newspaper.

We are returning herewith an approved copy of the Plans and Proposal Documents to be filed by your Clerk when advertisement is begun.

Sincerely,

Harry Lee James, P. E.
State Aid Engineer

Evelyn Hollins

By: Evelyn Hollins
Administrative Assistant

pc: Geoffrey Clemens, P.E., Co. Eng./Project Eng.
Supervisor District(s) 3&5
Jay Richardson, P.E.
F.H.W.A., **00-01 (if Federal)**
System Consultants Associates
McGraw Hill Construction Dodge
MS Procurement Technical Assistance Program
Associated General Contractors of Mississippi, Inc.
M.R.B.A.
Project File

OFFICE OF STATE AID ROAD CONSTRUCTION
MISSISSIPPI DEPARTMENT OF TRANSPORTATION
AND
HANCOCK COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Hancock County, Mississippi at the Hancock County Annex, Bay St. Louis, Mississippi, until on the day of , and shortly thereafter publicly opened for the construction of 0.232 miles of BRIDGE REPLACEMENT AND APPROACHES on the KILN-DELISLE being known as Project No. SAP-23(30) in Hancock County, Mississippi.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

| ITEM | QUANTITY | UNIT |
|--|-----------|------|
| <u>ROADWAY ITEMS:</u> | | |
| MOBILIZATION | LUMP SUM | LS |
| CLEARING AND GRUBBING | LUMP SUM | LS |
| REMOVAL OF BRIDGE (STA 475+25.87) | 1.000 | UN |
| UNCLASSIFIED EXCAVATION (FM) | 1,672.000 | CY |
| BORROW EXCAVATION (CONTRACTOR FURNISHED, LVM, CLASS 9) | 4,643.000 | CY |
| GRANULAR MATERIAL (LVM), (CLASS 5, GROUP C) | 29.730 | CY |
| HOT MIX ASPHALT, (ST) (12.5 MM) | 289.000 | TON |
| HOT MIX ASPHALT, (ST) (19 MM) | 277.000 | TON |
| BASE REPAIRS | | |
| HOT MIX ASPHALT, (ST) (19 MM), TRENCH WIDENING | 12.000 | TON |
| COLD MILLING OF BITUMINOUS PAVEMENT, ALL DEPTHS | 1,412.000 | SY |
| GUARD RAIL, W BEAM | 325.000 | LF |
| GUARD RAIL, BRIDGE END SECTION | 4.000 | EA |
| GUARD RAIL, TERMINAL END SECTION | 4.000 | EA |
| RIGHT-OF-WAY MARKERS (TYPE I) | 4.000 | EA |
| MAINTENANCE OF TRAFFIC | LUMP SUM | LS |
| ADDITIONAL CONSTRUCTION SIGNS | 0.000 | SF |
| 4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 MILS) | 0'.460 | MI |
| 4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 MILS) | 2,462.540 | LF |
| REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3) | 4.000 | EA |
| <u>EROSION CONTROL ITEMS:</u> | | |
| AGRICULTURAL LIMESTONE | 0.100 | TON |
| COMMERCIAL FERTILIZER (13-13-13) | 0.050 | TON |

SECTION 900
PROJECT NO. SAP-23(30)
HANCOCK COUNTY

| | | |
|--------------------------------|-----------|-----|
| AMMONIUM NITRATE | 0.100 | TON |
| SEEDING | 0.050 | AC |
| VEGETATIVE MATERIALS FOR MULCH | 0.100 | TON |
| TEMPORARY SILT FENCE | 2,345.000 | LF |
| (TYPE I) (AOS 0.15 - 0.84) | | |
| WATTLES, 20" | 150.000 | LF |

BRIDGE ITEMS:

| | | |
|------------------------------------|------------|-----|
| TEST PILE | 4.000 | EA |
| CONVENTIONAL STATIC PILE LOAD TEST | 0.000 | EA |
| 14" PRESTRESSED CONCRETE PILING | 2,160.000 | LF |
| 16" PRESTRESSED CONCRETE PILING | 540.000 | LF |
| 18" PRE-FORMED PILE HOLES | 100.000 | LF |
| 20" PRE-FORMED PILE HOLES | 100.000 | LF |
| BRIDGE CONCRETE, CLASS "A" | 385.000 | CY |
| 40' PRESTRESSED CONCRETE BEAM | 1,113.000 | LF |
| TYPE I+2 | | |
| 80' PRESTRESSED CONCRETE BEAM | 558.250 | LF |
| TYPE III | | |
| REINFORCEMENT | 65,539.000 | LB |
| CONCRETE RAILING | 480.000 | LF |
| LOOSE RIPRAP, 300 LB. | 243.000 | TON |
| GEOTEXTILE UNDER RIPRAP, | 414.000 | SY |
| TYPE V, AOS 0.21 - 0.43 | | |

NOTICE TO CONTRACTORS:

CONTRACT TIME: 120 Working Days

BASIS OF AWARD

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Hancock County, the County Engineer's office and the Office of the State Aid Engineer, 412 E. Woodrow Wilson Avenue, Jackson, Mississippi. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Geoffery Clemens, County Engineer for Hancock County, Mississippi, P. O. Box 2795, Bay St. Louis. The Cost is one hundred dollars (\$100.00) for plans and seventy five dollars (\$75.00) for the proposal, non-refundable

Certified check or bid bond for five percent (5%) of the total bid, made payable to Hancock County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Blaine Lafontaine, President
Hancock County Board of Supervisors