



Harry Lee James, P.E.

State Aid Engineer

P.O. Box 1850

422 E. Woodrow Wilson Ave.

Jackson, Mississippi 39216

Fax (601) 339-7141

July 16, 2019



Board of Supervisors
Pearl River County
c/o Chancery Clerk
Poplarville, MS 39470

Gentlemen:

RE: **STATE AID PROJECT**
PROJECT NO. SAP-55(59)
PEARL RIVER COUNTY

The Plans and specifications for the above numbered project have been reviewed and are herewith approved. You are, therefore, authorized to advertise this project for bids. The work to be done under this project consists of **Bridge Replacement**.

The date for opening these bids has been set for **Tuesday, August 27, 2019 at 10:00 a.m.** in the **Boardroom** at **Poplarville**.

In accordance with the Provisions of Section 31-7-13, Mississippi Code of 1972 as amended by House Bills numbered 901 and 1306 of the 1991 regular Legislative Session, the advertisement for receipt of bids on this project must be made once each week for two (2) consecutive weeks in a regular newspaper published in your county and, further, that the date as published for the bid opening shall not be less than fifteen (15) working days after the last published notice. The date, as set above, should be no sooner than the sixteenth working day after the last advertisement appears in the newspaper.

We are returning herewith an approved copy of the Plans and Proposal Documents to be filed by your Clerk when advertisement is begun.

Sincerely,

Harry Lee James, P. E.
State Aid Engineer

Evelyn Hollins

By: Evelyn Hollins
Administrative Assistant

pc: H. Les Dungan, III, P.E., Co. Eng./Project Eng.
Supervisor District(s) 5
Mr. Chris Dixon, P.E.
F.H.W.A., **00-01 (if Federal)**
System Consultants Associates
McGraw Hill Construction Dodge
MS Procurement Technical Assistance Program
Associated General Contractors of Mississippi, Inc.
M.R.B.A.
Project File

OFFICE OF STATE AID ROAD CONSTRUCTION
MISSISSIPPI DEPARTMENT OF TRANSPORTATION
AND
PEARL RIVER COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Pearl River County, Mississippi at the Pearl River County Courthouse, Poplarville, Mississippi, until on the day of , and shortly thereafter publicly opened for the construction of 0.094 miles of BRIDGE REPLACEMENT on the ANCHOR LAKE ROAD being known as Project No. SAP-55(59) in Pearl River County, Mississippi. Electronic bids can be submitted at www.centralbidding.com. For any questions relating to the electronic bidding process, please call 225-810-4814.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

<u>ITEM</u>	<u>QUANTITY</u>	<u>UNIT</u>
<u>ROADWAY ITEMS:</u>		
MOBILIZATION	LUMP SUM	LS
CLEARING AND GRUBBING	LUMP SUM	LS
REMOVAL OF BRIDGE AT STATION 45+00	1.000	UN
REMOVAL OF RIPRAP	250.000	SY
UNCLASSIFIED EXCAVATION (FM)	80.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 7)	75.000	CY
CHANNEL EXCAVATION (FM)	300.000	CY
GRANULAR MATERIAL (LVM), (CLASS 6, GROUP C)	245.000	CY
HOT MIX ASPHALT, ST 9.5 MM	126.000	TON
HOT MIX ASPHALT, ST 9.5 MM, LEVELING	58.000	TON
COLD MILLING OF BITUMINOUS PAVEMENT, ALL DEPTHS	200.000	SY
GUARD RAIL, W-BEAM	275.000	LF
GUARD RAIL, BRIDGE END SECTION, TYPE I THRIE-BEAM	4.000	EA
GUARD RAIL, TERMINAL END SECTION	4.000	EA
ROADWAY CONSTRUCTION SURVEYING	LUMP SUM	LS
MAINTENANCE OF TRAFFIC	LUMP SUM	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 MILS)	0.189	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (SKIP YELLOW) (90 MILS)	0.095	MI

SECTION 900
PROJECT NO. SAP-55(59)
PEARL RIVER COUNTY

4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (90 MILS)	500.000	LF
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	10.000	EA
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS)(TYPE 3)	4.000	EA

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	1.000	TON
COMMERCIAL FERTILIZER (13-13-13)	0.500	TON
AMMONIUM NITRATE	0.050	TON
SEEDING	0.500	AC
VEGETATIVE MATERIALS FOR MULCH	1.000	TON
SOLID SODDING	200.000	SY
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	350.000	LF
WATTLES, 20"	100.000	LF
LOOSE RIPRAP, 200 LB.	100.000	TON
GEOTEXTILE UNDER RIPRAP NON-WOVEN, TYPE V, AOS < 0.43	185.000	SY

BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14" PRESTRESSED CONCRETE PILING	660.000	LF
18" PRE-FORMED PILE HOLE	140.000	LF
19' PRECAST CONCRETE SLAB UNIT, 3'-6" INTERIOR	6.000	EA
31' PRECAST CONCRETE SLAB UNIT, 3'-6" INTERIOR	12.000	EA
19' PRECAST CONCRETE SLAB UNIT, 3'-6" EXTERIOR	2.000	EA
31' PRECAST CONCRETE SLAB UNIT, 3'-6" EXTERIOR	4.000	EA
PRECAST CONCRETE BARRIER RAIL	162.000	LF
31' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE	2.000	EA
31' PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE	2.000	EA
9.25' PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP, 300 LB.	203.000	TON
GEOTEXTILE UNDER RIPRAP NON-WOVEN, TYPE V, AOS < 0.43	500.000	SY

NOTICE TO CONTRACTORS:

CONTRACT TIME: 70 Working Days

BASIS OF AWARD

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Pearl River County, the County Engineer's office and the Office of the State Aid Engineer, 412 E. Woodrow Wilson Avenue, Jackson, Mississippi. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from H. Les Dungan, III, County Engineer for Pearl River County, Mississippi, 925 Goodyear Blvd., Picayune. The Cost is fifty dollars (\$50.00) for plans and fifty dollars (\$50.00) for the proposal, non-refundable. Or official bid documents can be downloaded from Central Bidding at www.centralbidding.com.

Certified check or bid bond for five percent (5%) of the total bid, made payable to Pearl River County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Sandy Kane Smith, President
Pearl River County Board of Supervisors