



Harry Lee James, P.E.

State Aid Engineer

P.O. Box 1850

412E Worlow Wilson Auc.

Jackson Msissipi 30216

Fax (601) 370-7141

May 6, 2021

Board of Supervisors Tishomingo County c/o Chancery Clerk Iuka, MS 38852

Gentlemen:

RE:

STATE AID PROJECT PROJECT NO. SAP-71(74) TISHOMINGO COUNTY

The Plans and specifications for the above numbered project have been reviewed and are herewith approved. You are, therefore, authorized to advertise this project for bids. The work to be done under this project consists of **Prestressed Concrete Bridge and Approaches**.

The date for opening these bids has been set for Tuesday, June 1, 2021 at 10:00 a.m. in the Boardroomat Iuka.

In accordance with the Provisions of Section 31-7-13, Mississippi Code of 1972 as amended by House Bills numbered 901 and 1306 of the 1991 regular Legislative Session, the advertisement for receipt of bids on this project must be made once each week for two (2) consecutive weeks in a regular newspaper published in your county and, further, that the date as published for the bid opening shall not be less than fifteen (15) working days after the last published notice. The date, as set above, should be no sooner than the <a href="mailto:sixteenth">sixteenth</a> working day after the last advertisement appears in the newspaper.

We are returning herewith an approved copy of the Plans and Proposal Documents to be filed by your Clerk when advertisement is begun.

Sincerely,

Harry Lee James, P. E. State Aid Engineer

Edyn Hollins

By: Evelyn Hollins

Administrative Assistant

pc: Kenneth P. Geno Jr., P.E., Co. Eng./Project Eng. Supervisor District(s) 2

Jared Keen, P.E. F.H.W.A., 00-01 (if Federal) System Consultants Associates

McGraw Hill Construction Dodge
MS Procurement Technical Assistance Program
Associated General Contractors of Mississippi, Inc.

M.R.B.A. Project File

# OFFICE OF STATE AID ROAD CONSTRUCTION MISSISSIPPI DEPARTMENT OF TRANSPORTATION AND

# TISHOMINGO COUNTY BOARD OF SUPERVISORS

## SECTION 900

## NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Tishomingo County, Mississippi at the Tishomingo County Courthouse, 1008 Battleground Drive, Iuka, Mississippi, until on the day of and shortly thereafter publicly opened for the construction of 0.132 miles of PRESTRESSED CONCRETE BRIDGE & APPROACHES ON COUNTY ROAD 133 (MOUNT GILEAD ROAD) being known as Project No.SAP-71(74) in Tishomingo County, Mississippi.

## PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

ITEM	QUANTITY	UNIT	
ROADWAY ITEMS:			
MOBILIZATION CLEARING AND GRUBBING REMOVAL OF BRIDGE @ STA. 433+81 UNCLASSIFIED EXCAVATION (FM)	LUMP SUM	LS	
CLEARING AND GRUBBING	LUMP SUM	LS	
REMOVAL OF BRIDGE @ STA. 433+81	1.000	UN	
UNCLASSIFIED EXCAVATION (FM)	2,313.000	CY	
BORROW EXCAVATION (F.M.E.)	1,490.000	CY	
(CONTRACTOR FURNISHED) (CLASS 9)	,		
GEOTEXTILE FABRIC STABILIZATION	2,250.000	SY	
(TYPE V) (NON-WOVEN) (AOS<0.43)			
GRANULAR MATERIAL (LVM), (CL.5, GP.C) CRUSHED STONE SIZE 3/4"& DOWN, (FM)	108.000	CY	
CRUSHED STONE SIZE 3/4"& DOWN, (FM)	651.000	CY	
MIXING, SHAPING AND COMPACTION	1,504.000	SY	
HOT MIX ASPHALT, ST, 9.5MM	227.000	TON	
ASPHALT FOR PRIME COAT (MC-70 OR EA-1)	526.000	GAL	
24" REINFORCED CONCRETE PIPE, CLASS III	48.000	LF	
24" REINFORCED CONCRETE PIPE FND SECTION	2.000	EA	
GUARD RAIL, W BEAM_ GUARD RAIL, BRIDGE END SECTION, TYPE "I" THRIE BEAM GUARD RAIL, TERMINAL END SECTION RIGHT-OF-WAY MARKERS (TYPE II) MAINTENANCE OF TRAFFIC ADDITIONAL CONSTRUCTION SIGNS 4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (60 MILS)	50.000	LF	
GUARD RAIL, BRIDGE END SECTION,	4.000	EA	
TYPE "I" THRIE BEAM			
GUARD RAIL, TERMINAL END SECTION	4.000	EA	
RIGHT-OF-WAY MARKERS (TYPE II)	6.000	EA	
MAINTENANCE OF TRAFFIC	LUMP SUM	LS	
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF	
4" WIDE THERMOPLASTIC EDGE STRIPE	0.265	MI	
(CONTINUOUS WHITE) (60 MILS)			
4" WIDE THERMOPLASTIC TRAFFIC	1,400.000	LF	
STRIPE (CONTINUOUS YELLOW)			
(90 MILS)			
TWO-WAY YELLOW REFLECTIVE HIGH	14.000	EA	
PERFORMANCE RAISED MARKERS			
PERFORMANCE RAISED MARKERS REFLECTORIZED TRAFFIC OBJECT MARKER	4.000	EA	
(ENCAPSULATED LENS) (TYPE 3)			
REFLECTORIZED TRAFFIC DELINEATOR	16.000	EA	
SIGN (ENCAPSULATED LENS)			

EROSION CONTROL ITEMS:		
AGRICULTURAL LIMESTONE	4.000	TON
COMMERCIAL FERTILIZER (13-13-13)	2.000	TON
AMMONIUM NITRATE	0.500	TON
SEEDING	2.000	AC
VEGETATIVE MATERIALS FOR MULCH	3.500	TON
SOLID SODDING	100.000	SY
EXCELSIOR BLANKET	1,160.000	SY
TEMPORARY SILT FENCE	320.000	$_{ m LF}$
(TYPE I OR II) (AOS 0.15-0.84)		
WATTLES, 20"	520.000	$_{ m LF}$
LOOSE RIPRAP, 200 LB.	640.000	TON
GEOTEXTILE UNDER RIPRAP,	1,260.000	SY
TYPE V, NON-WOVEN, AOS <0.43		
BRIDGE ITEMS:		
TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14" STEEL PILING	1,620.000	LF
20" PRE-FORMED PILE HOLES	1,325.000	LF
BRIDGE CONCRETE, CLASS "A"	188.000	CY
31' PRESTRESSED CONCRETE BEAM TYPE I+2	307.500	LF
60' PRESTRESSED CONCRETE BEAM TYPE III	298.750	LF
REINFORCEMENT	29,230.000	LB
CONCRETE RAILING	244.000	LF
LOOSE RIPRAP, 200 LB.	405.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, (NON-WOVEN), AOS <0.43	750.000	SY

PROJECT NO. SAP-71(74)
TISHOMINGO COUNTY

#### NOTICE TO CONTRACTORS:

CONTRACT TIME:

135 Working Days

### BASIS OF AWARD

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The Board of Supervisors hereby notifies all bidders that it will affirmatively ensure that in any contract entered into pursuant to this advertisement, minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Tishomingo County, the County Engineer's office and the Office of the State Aid Engineer, 412 E. Woodrow Wilson Avenue, Jackson, Mississippi. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Kenneth P. Geno, Jr., County Engineer for Tishomingo County, Mississippi, P. O. Box 1526, Tupelo. The Cost is fifty dollars (\$50.00) for plans and fifty dollars (\$50.00) for the proposal, non-refundable

Certified check or bid bond for five percent (5%) of the total bid, made payable to Tishomingo County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Michael Busby, President Tishomingo County Board of Supervisors

Page 3 of 3