OFFICE OF
STATE AID ROAD CONSTRUCTION

MISSISSIPPI DEPARTMENT OF TRANSPORTATION
P.O. BOX 1850
JACKSON, MISSISSIPPI 39215-1850

H. Carey Webb, P.E.
State Aid Engineer
Telephone (601)359-7150
www.msstateaidroads.us

412 Woodrow Wilson Avenue
Jackson, Mississippi 39216
Fax (601)359-7141
mail@osarc.state.ms.us

July 29, 2016

Board of Supervisors
Tippah County
c/o Chancery Clerk
Ripley, MS 38663

RECEIVED
AUG 01 2016
MINORITY & SMALL BUSINESS
DEVELOPMENT DIVISION

Gentlemen:

RE: **LOCAL SYSTEM BRIDGE PROGRAM**
PROJECT NO. **LSBP-70(25)**
TIPPAH COUNTY

The Plans and specifications for the above numbered project have been reviewed and are herewith approved. You are, therefore, authorized to advertise this project for bids. The work to be done under this project consists of **Bridge and Approaches to Replace Bridge number 50.**.

The date for opening these bids has been set for **Friday, September 2, 2016** at **10:00 a. m.** in the **Chancery Building** at **Ripley.**

In accordance with the Provisions of Section 31-7-13, Mississippi Code of 1972 as amended by House Bills numbered 901 and 1306 of the 1991 regular Legislative Session, the advertisement for receipt of bids on this project must be made once each week for two (2) consecutive weeks in a regular newspaper published in your county and, further, that the date as published for the bid opening shall not be less than fifteen (15) working days after the last published notice. The date, as set above, should be no sooner than the sixteenth working day after the last advertisement appears in the newspaper.

We are returning herewith an approved copy of the Plans and Proposal Documents to be filed by your Clerk when advertisement is begun.

Sincerely,

H. Carey Webb P. E.
State Aid Engineer

Polly Robinson

By: Polly Robinson
Administrative Assistant

SCANNED
Per: AB
Date: 8/1/16

pc: Kenneth P. Geno, Jr., P.E., Co. Eng./Project Eng.
Supervisor District(s)2
Joel Bridges, P.E.
F.H.W.A. , **00-01** (***if Federal***)
System Consultants Associates
McGraw Hill Construction Dodge
MS Procurement Technical Assistance Program
Associated General Contractors of Mississippi, Inc.
M.R.B.A.
Project File

OFFICE OF STATE AID ROAD CONSTRUCTION
MISSISSIPPI DEPARTMENT OF TRANSPORTATION
AND
TIPPAH COUNTY BOARD OF SUPERVISORS

RECEIVED
AUG 01 2016
MINORITY BUSINESS
DEVELOPMENT DIVISION

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Tippah County, Mississippi at the Tippah County Chancery Building, Ripley, Mississippi, until on the day of , and shortly thereafter publicly opened for the construction of 0.094 miles of BRIDGE & APPROACHES TO REPLACE BRIDGE NO. 50 on the TIPPAH CREEK NORTH being known as Project No. LSBP-70(25) in Tippah County, Mississippi.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

ITEM	QUANTITY	UNIT
ROADWAY ITEMS:		
MOBILIZATION	LUMP SUM	LS
CLEARING AND GRUBBING	LUMP SUM	LS
REMOVAL OF STA. 111+03	1.000	UN
UNCLASSIFIED EXCAVATION (FM)	326.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	767.000	CY
GRANULAR MATERIAL (LVM), (CLASS 5, GROUP C)	478.000	CY
CLASS "B" STRUCTURAL CONCRETE, MINOR STRUCTURES	0.410	CY
24" CORRUGATED POLYETHYLENE PIPE	106.000	LF
RIGHT-OF-WAY MARKERS (TYPE I)	8.000	EA
MAINTENANCE OF TRAFFIC	LUMP SUM	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS)(TYPE I)	4.000	EA
EROSION CONTROL ITEMS:		
AGRICULTURAL LIMESTONE	1.000	TON
COMMERCIAL FERTILIZER (13-13-13)	0.500	TON
SEEDING	0.500	AC
SOLID SODDING	100.000	SY
EXCELSIOR BLANKET	1,170.000	SY
TEMPORARY SILT FENCE (TYPE I OR II) (AOS 0.15-0.84)	900.000	LF
WATTLES, 20"	160.000	LF
BRIDGE ITEMS:		
REMOVE AND RELAY RIPRAP	162.000	SY

RECEIVED
MAR 25 2016
OSARC 1947 21

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
12" STEEL PILING	640.000	LF
18" PRE-FORMED PILE HOLES	475.000	LF
BRIDGE CONCRETE, CLASS "B"	7.610	CY
REINFORCEMENT	144.000	LB
31' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	12.000	EA
40' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	6.000	EA
31' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	4.000	EA
40' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	2.000	EA
PRECAST CONCRETE BARRIER RAIL	204.000	LF
31.33' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE,	2.000	EA
31' PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE,	2.000	EA
9.25' PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP, 200 LB.	120.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE VI, AOS <0.43	385.000	SY

RECEIVED
MAR 25 2016
OSARC 1947 2.

PROJECT NO. LSBP-70(25)
TIPPAH COUNTY

NOTICE TO CONTRACTORS:

CONTRACT TIME: 75 Working Days

BASIS OF AWARD

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Tippah County, the LSBP Engineer's office and the Office of the State Aid Engineer, 412 E. Woodrow Wilson Avenue, Jackson, Mississippi. This project shall be constructed in acccordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Kenneth P. Geno, Jr., LSBP Engineer for Tippah County, Mississippi, P. O. Box 1526, Tupelo. The Cost is fifty dollars ($50.00) for plans and fifty dollars ($50.00) for the proposal, non-refundable

Certified check or bid bond for five percent (5%) of the total bid, made payable to Tippah County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Eddie Stroupe, President
Tippah County Board of Supervisors